


Data Science Interview Questions


(30 days of Interview Preparation)



INEURON.AI

Q1. What is the difference between AI, Data Science, ML, and DL?

Ans 1 :



Artificial Intelligence: AI is purely math and scientific exercise, but when it became computational, it started to solve human problems formalized into a subset of computer science. Artificial intelligence has changed the original computational statistics paradigm to the modern idea that machines could mimic actual human capabilities, such as decision making and performing more "human" tasks. Modern AI is divided into two categories

1. General AI - Planning, decision making, identifying objects, recognizing sounds, social & business transactions
2. Applied AI - driverless/ Autonomous car or machine smartly trade stocks

Machine Learning: Instead of engineers "teaching" or programming computers to have what they need to carry out tasks, that perhaps computers could teach themselves – learn something without being explicitly programmed to do so. ML is a form of AI where based on more data, and they can change actions and response, which will make more efficient, adaptable and scalable. e.g., navigation apps and recommendation engines. Classified into:-

1. Supervised
2. Unsupervised
3. Reinforcement learning

Data Science: Data science has many tools, techniques, and algorithms called from these fields, plus others – to handle big data

The goal of data science, somewhat similar to machine learning, is to make accurate predictions and to automate and perform transactions in real-time, such as purchasing internet traffic or automatically generating content.

INEURON.AI

Data science relies less on math and coding and more on data and building new systems to process the data. Relying on the fields of data integration, distributed architecture, automated machine learning, data visualization, data engineering, and automated data-driven decisions, data science can cover an entire spectrum of data processing, not only the algorithms or statistics related to data.

Deep Learning: It is a technique for implementing ML.

ML provides the desired output from a given input, but DL reads the input and applies it to another data. In ML, we can easily classify the flower based upon the features. Suppose you want a machine to look at an image and determine what it represents to the human eye, whether a face, flower, landscape, truck, building, etc.

Machine learning is not sufficient for this task because machine learning can only produce an output from a data set – whether according to a known algorithm or based on the inherent structure of the data. You might be able to use machine learning to determine whether an image was of an “X” – a flower, say – and it would learn and get more accurate. But that output is binary (yes/no) and is dependent on the algorithm, not the data. In the image recognition case, the outcome is not binary and not dependent on the algorithm.

The neural network performs MICRO calculations with computational on many layers. Neural networks also support weighting data for ‘confidence’. These results in a probabilistic system, vs. deterministic, and can handle tasks that we think of as requiring more ‘human-like’ judgment.

Q2. What is the difference between Supervised learning, Unsupervised learning and Reinforcement learning?

Ans 2:

Machine Learning

Machine learning is the scientific study of algorithms and statistical models that computer systems use to effectively perform a specific task without using explicit instructions, relying on patterns and inference instead.

Building a model by learning the patterns of historical data with some relationship between data to make a data-driven prediction.

Types of Machine Learning

- Supervised Learning
- Unsupervised Learning
- Reinforcement Learning

Supervised learning

In a supervised learning model, the algorithm learns on a labeled dataset, to generate reasonable predictions for the response to new data. (Forecasting outcome of new data)

- Regression
- Classification

INEURON.AI

Unsupervised learning


An unsupervised model, in contrast, provides unlabelled data that the algorithm tries to make sense of by extracting features, co-occurrence and underlying patterns on its own. We use unsupervised learning for

- Clustering
- Anomaly detection
- Association
- Autoencoders

Reinforcement Learning

Reinforcement learning is less supervised and depends on the learning agent in determining the output solutions by arriving at different possible ways to achieve the best possible solution.

Q3. Describe the general architecture of Machine learning.



Business understanding: Understand the given use case, and also, it's good to know more about the domain for which the use cases are built.

Data Acquisition and Understanding: Data gathering from different sources and understanding the data. Cleaning the data, handling the missing data if any, data wrangling, and EDA(Exploratory data analysis).

INEURON.AI

Modeling: *Feature Engineering* - scaling the data, feature selection - not all features are important. We use the backward elimination method, correlation factors, PCA and domain knowledge to select the features.

Model Training based on trial and error method or by experience, we select the algorithm and train with the selected features.

Model evaluation Accuracy of the model , confusion matrix and cross-validation.

If accuracy is not high, to achieve higher accuracy, we tune the model...either by changing the algorithm used or by feature selection or by gathering more data, etc.

Deployment - Once the model has good accuracy, we deploy the model either in the cloud or Raspberry pi or any other place. Once we deploy, we monitor the performance of the model.if its good...we go live with the model or reiterate the all process until our model performance is good.

It's not done yet!!!


What if, after a few days, our model performs badly because of new data. In that case, we do all the process again by collecting new data and redeploy the model.

Q4. What is Linear Regression?

Ans 4:

Linear Regression tends to establish a relationship between a dependent variable(Y) and one or more independent variable(X) by finding the best fit of the straight line.

The equation for the Linear model is $Y = mX+c$, where m is the slope and c is the intercept



In the above diagram, the blue dots we see are the distribution of 'y' w.r.t 'x.' There is no straight line that runs through all the data points. So, the objective here is to fit the best fit of a straight line that will try to minimize the error between the expected and actual value.

Q5. OLS Stats Model (Ordinary Least Square)

Ans 5:

OLS is a stats model, which will help us in identifying the more significant features that can have an influence on the output. OLS model in python is executed as:

```
lm = smf.ols(formula = 'Sales ~ am+constant', data = data).fit() lm.conf_int() lm.summary()
```

And we get the output as below,

OLS Regression Results						
Dep. Variable:	mpg	R-squared:	0.360			
Model:	OLS	Adj. R-squared:	0.338			
Method:	Least Squares	F-statistic:	16.86			
Date:	Wed, 17 Jan 2018	Prob (F-statistic):	0.000285			
Time:	14:07:51	Log-Likelihood:	-95.242			
No. Observations:	32	AIC:	194.5			
Df Residuals:	30	BIC:	197.4			
Df Model:	1					
Covariance Type:	nonrobust					
coef	std err	t	P> t	[0.025	0.975]	
constant	17.1474	1.125	15.247	0.000	14.851	19.444
am	7.2449	1.764	4.106	0.000	3.642	10.848
Omnibus:	0.480	Durbin-Watson:	1.065			
Prob(Omnibus):	0.787	Jarque-Bera (JB):	0.589			
Skew:	0.051	Prob(JB):	0.745			
Kurtosis:	2.343	Cond. No.	2.46			

The higher the t-value for the feature, the more significant the feature is to the output variable. And also, the p-value plays a role in rejecting the Null hypothesis (Null hypothesis stating the features has zero significance on the target variable.). If the p-value is less than 0.05 (95% confidence interval) for a feature, then we can consider the feature to be significant.

Q6. What is L1 Regularization (L1 = lasso) ?

Ans 6:

The main objective of creating a model (training data) is making sure it fits the data properly and reduce the loss. Sometimes the model that is trained will fit the data but it may fail and give a poor performance during analyzing of data (test data). This leads to overfitting. Regularization came to overcome overfitting.

Lasso Regression (Least Absolute Shrinkage and Selection Operator) adds "Absolute value of magnitude" of coefficient, as penalty term to the loss function.

INEURON.AI

Lasso shrinks the less important feature's coefficient to zero; thus, removing some feature altogether. So, this works well for feature selection in case we have a huge number of features.

L1 Regularization

$$\text{Cost} = \sum_{i=0}^N (y_i - \sum_{j=0}^M x_{ij} W_j)^2 + \lambda \sum_{j=0}^M |W_j|$$

L2 Regularization

$$\text{Cost} = \sum_{i=0}^N (y_i - \sum_{j=0}^M x_{ij} W_j)^2 + \lambda \sum_{j=0}^M W_j^2$$

The diagram illustrates the cost function as a sum of two components. The first component, labeled "Loss function", is represented by a downward-pointing triangle under the term $\sum_{i=0}^N (y_i - \sum_{j=0}^M x_{ij} W_j)^2$. The second component, labeled "Regularization Term", is represented by a downward-pointing triangle under the term $\lambda \sum_{j=0}^M W_j^2$.

Methods like Cross-validation, Stepwise Regression are there to handle overfitting and perform feature selection work well with a small set of features. These techniques are good when we are dealing with a large set of features.

Along with shrinking coefficients, the **lasso performs feature selection**, as well. (Remember the 'selection' in the lasso full-form?) Because some of the coefficients become exactly zero, which is equivalent to the particular feature being excluded from the model.

Q7. L2 Regularization(L2 = Ridge Regression)


Ans 7:

$$Cost\ function = Loss + \frac{\lambda}{2m} * \sum \|w\|^2$$

Overfitting happens when the model learns signal as well as noise in the training data and wouldn't perform well on new/unseen data on which model wasn't trained on.

To avoid overfitting your model on training data like **cross-validation sampling**, **reducing the number of features**, **pruning**, **regularization**, etc.

So to avoid overfitting, we perform Regularization.



The Regression model that uses L2 regularization is called Ridge Regression.

The formula for Ridge Regression:-

$$J(\theta) = \frac{1}{2m} \left[\sum_{i=1}^m (h_\theta(x^{(i)}) - y^{(i)})^2 + \lambda \sum_{j=1}^n \theta_j^2 \right]$$
$$\min_{\theta} J(\theta)$$

Regularization adds the penalty as model complexity increases. The regularization parameter (lambda) penalizes all the parameters except intercept so that the model generalizes the data and won't overfit.

Ridge regression adds "squared magnitude of the coefficient" as penalty term to the loss function. Here the box part in the above image represents the L2 regularization element/term.

$$\sum_{i=1}^n (y_i - \sum_{j=1}^p x_{ij}\beta_j)^2 + \lambda \sum_{j=1}^p \beta_j^2$$

Lambda is a hyperparameter.

INEURON.AI

If lambda is zero, then it is equivalent to OLS. But if lambda is very large, then it will add too much weight, and it will lead to under-fitting.

Ridge regularization forces the weights to be small but does not make them zero and does not give the sparse solution.

Ridge is not robust to outliers as square terms blow up the error differences of the outliers, and the regularization term tries to fix it by penalizing the weights

Ridge regression performs better when all the input features influence the output, and all with weights are of roughly equal size.

L2 regularization can learn complex data patterns.

Q8. What is R square(where to use and where not)?

Ans 8.

R-squared is a statistical measure of how close the data are to the fitted regression line. It is also known as the coefficient of determination, or the coefficient of multiple determination for multiple regression.

The definition of R-squared is the percentage of the response variable variation that is explained by a linear model.

R-squared = Explained variation / Total variation

R-squared is always between 0 and 100%.

0% indicates that the model explains none of the variability of the response data around its mean.

100% indicates that the model explains all the variability of the response data around its mean.

In general, the higher the R-squared, the better the model fits your data.

$$R^2 = 1 - \frac{SS_{Regression}}{SS_{Total}}$$

Sum Squared Regression Error
↓
Sum Squared Total Error

$$R^2 = 1 - \frac{SS_{RES}}{SS_{TOT}} = \frac{\sum_i (y_i - \hat{y}_i)^2}{\sum_i (y_i - \bar{y})^2}$$

INEURON.AI

There is a problem with the R-Square. The problem arises when we ask this question to ourselves.** Is it good to add as many independent variables as possible?**

The answer is No because we understand that each independent variable should have a meaningful impact. But, even** if we add independent variables which are not meaningful**, will it improve R-Square value?

Yes, this is the basic problem with R-Square. How many junk independent variables or important independent variable or impactful independent variable you add to your model, the R-Squared value will always increase. It will never decrease with the addition of a newly independent variable, whether it could be an impactful, non-impactful, or bad variable, so we need another way to measure equivalent R-Square, which penalizes our model with any junk independent variable.

So, we calculate the **Adjusted R-Square** with a better adjustment in the formula of generic R-square.

$$R^2_{\text{adjusted}} = 1 - \frac{(1 - R^2)(N - 1)}{N - p - 1}$$


where

R^2 = sample R-square
p = Number of predictors
N = Total sample size.

Q9. What is Mean Square Error?

The mean squared error tells you how close a regression line is to a set of points. It does this by taking the distances from the points to the regression line (these distances are the “errors”) and squaring them.

Giving an intuition



The line equation is $y = Mx + B$. We want to find **M (slope)** and **B (y-intercept)** that minimizes the squared error.

$$\text{MSE} = \frac{1}{n} \sum_{i=1}^n (y_i - \tilde{y}_i)^2$$


Q10. Why Support Vector Regression? Difference between SVR and a simple regression model?

Ans 10:


In simple linear regression, try to minimize the error rate. But in SVR, we try to fit the error within a certain threshold.

Main Concepts:-

1. Boundary
2. Kernel
3. Support Vector
4. Hyper Plane




Blueline: Hyper Plane; Red Line: Boundary-Line



INEURON.AI

Our best fit line is the one where the hyperplane has the maximum number of points. We are trying to do here is trying to decide a decision boundary at 'e' distance from the original hyperplane such that data points closest to the hyperplane or the support vectors are within that boundary line




DATA SCIENCE INTERVIEW PREPARATION (30 Days of Interview Preparation)

#DAY 02

Q1. What is Logistic Regression?

Answer:

The logistic regression technique involves the dependent variable which can be represented in the binary 0 or true or false yes or no values which means that the outcome could only be in either one form of two. For example it can be utilized when we need to find the probability of a successful or fail event.



Logistic Regression is used when the dependent variable (target) is categorical.


Model

Output = 0 or

$$Z = WX + B$$

$$h\theta(x) = \text{sigmoid}(Z)$$

$$h\theta(x) = \log P(X) / -P(X) = WX + B$$



If Z goes to infinity Y predicted will become 1 and if Z goes to negative infinity Y predicted will become 0.

The output from the hypothesis is the estimated probability. This is used to infer how confident can predicted value be actual value when given an input X .

Cost Function

$$\text{Cost}(h_{\theta}(x), y) = -y \log(h_{\theta}(x)) - (1-y) \log(1-h_{\theta}(x))$$

If $y = 1$, $(1-y)$ term will become zero, therefore $-\log(h_{\theta}(x))$ alone will be present

If $y = 0$, (y) term will become zero, therefore $-\log(1-h_{\theta}(x))$ alone will be present

$$\begin{aligned}\text{Cost } h_{\theta}(x) \text{ Y Actual} &= -\log h_{\theta}(x) \text{ if } y=1 \\ &= -\log(1-h_{\theta}(x)) \text{ if } y=0\end{aligned}$$

This implementation is for binary logistic regression. For data with more than 2 classes softmax regression has to be used.

Q2. Difference between logistic and linear regression?

Answer:

Linear and Logistic regression are the most basic form of regression which are commonly used. The essential difference between these two is that Logistic regression is used when the dependent variable is binary. In contrast Linear regression is used when the dependent variable is continuous and the nature of the regression line is linear.

Key Differences between Linear and Logistic Regression

Linear regression models data using continuous numeric value. As against logistic regression models the data in the binary values.


Linear regression requires to establish the linear relationship among dependent and independent variables whereas it is not necessary for logistic regression.

In linear regression the independent variable can be correlated with each other. On the contrary in the logistic regression the variable must not be correlated with each other.

Q3. Why we can't do a classification problem using Regression?

Answer:-


With linear regression you fit a polynomial through the data - say like on the example below we fit a straight line through {tumor size tumor type} sample set.



Above malignant tumors get 1 and non-malignant ones get 0 and the green line is our hypothesis $h(x)$. To make predictions we may say that for any given tumor size x if $h(x)$ gets bigger than 0.5 we predict malignant tumors. Otherwise we predict benignly.

It looks like this way we could correctly predict every single training set sample but now let's change the task a bit.

Intuitively it's clear that all tumors larger certain threshold are malignant. So let's add another sample with huge tumor size and run linear regression again.



Now our $h(x) > 0.5 \rightarrow$ malignant doesn't work anymore. To keep making correct predictions we need to change it to $h(x) > 0.2$ or something - but that's not how the algorithm should work.

We cannot change the hypothesis each time a new sample arrives. Instead we should learn it off the training set data and then using the hypothesis we've learned make correct predictions for the data we haven't seen before.


Linear regression is unbounded.

Q4. What is Decision Tree?

A decision tree is a type of supervised learning algorithm that can be used in classification as well as regressor problems. The input to a decision tree can be both continuous as well as categorical. The decision tree works on an if-then statement. Decision tree tries to solve a problem by using tree representation Node and Leaf.

Assumptions while creating a decision tree
 1. Initially all the training set is considered as a root
 2. Feature values are preferred to be categorical if continuous then they are discretized
 3. Records are

distributed recursively on the basis of attribute values 4 Which attributes are considered to be in root node or internal node is done by using a statistical approach



Q5. Entropy, Information Gain, Gini Index, Reducing Impurity?

Answer:

There are different attributes which define the split of nodes in a decision tree There are few algorithms to find the optimal split

ID3(Iterative Dichotomiser 3): This solution uses Entropy and Information gain as metrics to form a better decision tree The attribute with the highest information gain is used as a root node and a similar approach is followed after that Entropy is the measure that characterizes the impurity of an arbitrary collection of examples

Entropy

Entropy $H(S)$ is a measure of the amount of uncertainty in the (data) set S (i.e. entropy characterizes the (data) set S).

$$H(S) = \sum_{c \in C} -p(c) \log_2 p(c)$$

Where,

- * S – The current (data) set for which entropy is being calculated (changes every iteration of the ID3 algorithm)
- * C – Set of classes in S $C = \{ \text{yes}, \text{no} \}$
- * $p(c)$ – The proportion of the number of elements in class c to the number of elements in set S

When $H(S) = 0$, the set S is perfectly classified (i.e. all elements in S are of the same class).

In ID3, entropy is calculated for each remaining attribute. The attribute with the **smallest** entropy is used to split the set S on this iteration. The higher the entropy, the higher the potential to improve the classification here.

Entropy varies from 0 to 0 if all the data belong to a single class and if the class distribution is equal In this way entropy will give a measure of impurity in the dataset

Steps to decide which attribute to split

Compute the entropy for the dataset

- 2 For every attribute
- 2 Calculate entropy for all categorical values
- 2.2 Take average information entropy for the attribute
- 2.3 Calculate gain for the current attribute
 - 3 Pick the attribute with the highest information gain
 - 4 Repeat until we get the desired tree

A leaf node is decided when entropy is zero

Information Gain = $-\sum \frac{S_b}{S} * \text{Entropy } S_b$
 Sb - Subset S - entire data


2) CART Algorithm (Classification and Regression trees): In CART we use the GINI index as a metric. Gini index is used as a cost function to evaluate split in a dataset.

Steps to calculate Gini for a split

Calculate Gini for subnodes using formula **sum of the square of probability for success and failure ($p^2 + q^2$)**.

- 2 Calculate Gini for split using weighted Gini score of each node of that split

Choose the split based on higher Gini value



Split on Gender

$$\text{Gini for sub-node Female} = 0.2 * 0.2 + 0.8 * 0.8 = 0.68$$

$$\text{Gini for sub-node Male} = 0.65 * 0.65 + 0.35 * 0.35 = 0.55$$

Weighted Gini for Split Gender = $0/30 * 0.68 + 20/30 * 0.55 = 0.59$

Similar for Split on Class

Gini for sub-node Class IX = $0.43 * 0.43 + 0.57 * 0.57 = 0.5$

Gini for sub-node Class X = $0.56 * 0.56 + 0.44 * 0.44 = 0.5$

Weighted Gini for Split Class = $4/30 * 0.5 + 6/30 * 0.5 = 0.5$

Here Weighted Gini is high for gender so we consider splitting based on gender

Q6. How to control leaf height and Pruning?

Answer:

To control the leaf size we can set the parameters -

1 Maximum depth :

Maximum tree depth is a limit to stop the further splitting of nodes when the specified tree depth has been reached during the building of the initial decision tree

NEVER use maximum depth to limit the further splitting of nodes. In other words: use the largest possible value.

2 Minimum split size:

Minimum split size is a limit to stop the further splitting of nodes when the number of observations in the node is lower than the minimum split size

This is a good way to limit the growth of the tree. When a leaf contains too few observations further splitting will result in overfitting modeling of noise in the data

3 Minimum leaf size

Minimum leaf size is a limit to split a node when the number of observations in one of the child nodes is lower than the minimum leaf size


Pruning is mostly done to reduce the chances of overfitting the tree to the training data and reduce the overall complexity of the tree

There are two types of pruning **Pre-pruning** and **Post-pruning**

Pre-pruning is also known as the **early stopping criteria**. As the name suggests the criteria are set as parameter values while building the model. The tree stops growing when it meets any of these pre-pruning criteria or it discovers the pure classes

- 2 In Post-pruning the idea is to allow the decision tree to grow fully and observe the CP value. Next we prune/cut the tree with the optimal **CP** Complexity Parameter value as the parameter.

The CP complexity parameter is used to control tree growth. If the cost of adding a variable is higher than the value of CP tree growth stops.



Q7. How to handle a decision tree for numerical and categorical data?

Answer:

Decision trees can handle both categorical and numerical variables at the same time as features. There is not any problem in doing that.

Every split in a decision tree is based on a feature.

If the feature is categorical, the split is done with the elements belonging to a particular class

- 2 **If the feature is continuous, the split is done with the elements higher than a threshold.**

At every split the decision tree will take the best variable at that moment. This will be done according to an impurity measure with the split branches. And the fact that the variable used to do split is categorical or continuous is irrelevant in fact decision trees categorize continuous variables by creating binary regions with the threshold.

At last the good approach is to always convert your **categoricals to continuous** using **LabelEncoder** or **OneHotEncoding**.

Q8. What is the Random Forest Algorithm?

Answer:

Random Forest is an ensemble machine learning algorithm that follows the bagging technique. The base estimators in the random forest are decision trees. Random forest randomly selects a set of features that are used to decide the best split at each node of the decision tree.

Looking at it step-by-step this is what a random forest model does

Random subsets are created from the original dataset **bootstrapping**

- 2 At each node in the decision tree only a random set of features are considered to decide the best split
- 3 A decision tree model is fitted on each of the subsets
- 4 The final prediction is calculated by averaging the predictions from all decision trees

To sum up, the Random forest randomly selects data points and features and builds multiple trees (Forest).

Random Forest is used for feature importance selection. The attribute `.feature_importances_` is used to find feature importance

Some Important Parameters -

- n_estimators** - It defines the number of decision trees to be created in a random forest
- 2 **criterion** - "Gini" or "Entropy."
- 3 **min_samples_split** - Used to define the minimum number of samples required in a leaf node before a split is attempted
- 4 **max_features** -It defines the maximum number of features allowed for the split in each decision tree
- 5. **n_jobs** - The number of jobs to run in parallel for both fit and predict. **Always keep (-1) to use all the cores for parallel processing.**

Q9. What is Variance and Bias tradeoff?

Answer:


In predicting models the prediction error is composed of two different errors

- Bias
- 2 Variance

It is important to understand the variance and bias trade-off which tells about to minimize the Bias and Variance in the prediction and avoids overfitting & under fitting of the model

Bias It is the difference between the expected or average prediction of the model and the correct value which we are trying to predict Imagine if we are trying to build more than one model by collecting different data sets and later on evaluating the prediction we may end up by different prediction for all the models So bias is something which measures how far these model prediction from the correct prediction It always leads to a high error in training and test data

Variance Variability of a model prediction for a given data point We can build the model multiple times so the variance is how much the predictions for a given point vary between different realizations of the model




For example Voting Republican - 3 Voting Democratic - 6 Non-Respondent - 2 Total - 50

The probability of voting Republican is $3 / (3 + 6)$ or 44.8% We put out our press release that the Democrats are going to win by over 0 points; but when the election comes around it turns out they lose by 0 points That certainly reflects poorly on us Where did we go wrong in our model?

Bias scenario's using a phonebook to select participants in our survey is one of our sources of bias By only surveying certain classes of people it skews the results in a way that will be consistent if we repeated the entire model building exercise Similarly not following up with respondents is another source of bias as it consistently changes the mixture of responses we get On our bulls-eye diagram these move us away from the center of the target but they would not result in an increased scatter of estimates

Variance scenarios the small sample size is a source of variance If we increased our sample size the results would be more consistent each time we repeated the survey and prediction The results still might be highly inaccurate due to our large sources of bias but the variance of predictions will be reduced



Q10. What are Ensemble Methods?

Answer

Bagging and Boosting

Decision trees have been around for a long time and also known to suffer from bias and variance
You will have a large bias with simple trees and a large variance with complex trees

Ensemble methods - which combines several decision trees to produce better predictive performance than utilizing a single decision tree. The main principle behind the ensemble model is that a group of weak learners come together to form a strong learner

Two techniques to perform ensemble decision trees

- 1 Bagging
- 2 Boosting

Bagging (Bootstrap Aggregation) is used when our goal is to reduce the variance of a decision tree. Here the idea is to create several subsets of data from the training sample chosen randomly with replacement. Now each collection of subset data is used to train their decision trees. As a result we end up with an ensemble of different models. Average of all the predictions from different trees are used which is more robust than a single decision tree.

Boosting is another ensemble technique to create a collection of predictors. In this technique learners are learned sequentially with early learners fitting simple models to the data and then analyzing data

for errors. In other words we fit consecutive trees random sample and at every step the goal is to solve for net error from the prior tree.

When a hypothesis misclassifies an input its weight is increased so that the next hypothesis is more likely to classify it correctly. By combining the whole set at the end converts weak learners into a better performing model.

The different types of boosting algorithms are

1. AdaBoost
2. Gradient Boosting
3. XGBoost


Q11. What is SVM Classification?


Answer:

SVM or Large margin classifier is a supervised learning algorithm that uses a powerful technique called SVM for classification.


We have two types of SVM classifiers

1) Linear SVM In Linear SVM the data points are expected to be separated by some apparent gap. Therefore the SVM algorithm predicts a straight hyperplane dividing the two classes. The hyperplane is also called as maximum margin hyperplane.





2) Non-Linear SVM: It is possible that our data points are not linearly separable in a p-dimensional space but can be linearly separable in a higher dimension. Kernel tricks make it possible to draw nonlinear hyperplanes. Some standard kernels are a. Polynomial Kernel b. RBF kernel mostly used.



Advantages of SVM classifier

- 1 SVMs are effective when the number of features is quite large
- 2 It works effectively even if the number of features is greater than the number of samples
- 3 Non-Linear data can also be classified using customized hyperplanes built by using kernel trick
- 4 It is a robust model to solve prediction problems since it maximizes margin

Disadvantages of SVM classifier:

- The biggest limitation of the Support Vector Machine is the choice of the kernel. The wrong choice of the kernel can lead to an increase in error percentage.
- 2 With a greater number of samples it starts giving poor performances
 - 3 SVMs have good generalization performance but they can be extremely slow in the test phase
 - 4 SVMs have high algorithmic complexity and extensive memory requirements due to the use of quadratic programming

Q11. What is Naive Bayes Classification and Gaussian Naive Bayes

Answer:

Bayes Theorem finds the probability of an event occurring given the probability of another event that has already occurred Bayes theorem is stated mathematically as the following equation

$$P(A|B) = \frac{P(B|A) P(A)}{P(B)}$$

↓ ↓
 THE PROBABILITY OF "B" BEING TRUE GIVEN THAT "A" IS TRUE THE PROBABILITY OF "A" BEING TRUE
 ↑ ↑
 THE PROBABILITY OF "A" BEING TRUE GIVEN THAT "B" IS TRUE THE PROBABILITY OF "B" BEING TRUE

Now with regards to our dataset we can apply Bayes theorem in following way

$$P(y|X) = \{P(X|y) P(y)\} / \{P(X)\}$$

where y is class variable and X is a dependent feature vector of size n where

$$X = x_1 \ x_2 \ x_3 \dots x_n$$

	OUTLOOK	TEMPERATURE	HUMIDITY	WINDY	PLAY GOLF
0	Rainy	Hot	High	False	No
1	Rainy	Hot	High	True	No
2	Overcast	Hot	High	False	Yes
3	Sunny	Mild	High	False	Yes
4	Sunny	Cool	Normal	False	Yes
5	Sunny	Cool	Normal	True	No
6	Overcast	Cool	Normal	True	Yes
7	Rainy	Mild	High	False	No
8	Rainy	Cool	Normal	False	Yes
9	Sunny	Mild	Normal	False	Yes
10	Rainy	Mild	Normal	True	Yes
11	Overcast	Mild	High	True	Yes
12	Overcast	Hot	Normal	False	Yes
13	Sunny	Mild	High	True	No

To clear an example of a feature vector and corresponding class variable can be refer st row of the dataset

$X = \text{Rainy Hot High False}$ $y = \text{No So}$ basically $P(X|y)$ here means the probability of Not playing golf given that the weather conditions are Rainy outlook Temperature is hot high humidity and no wind


Naive Bayes Classification

We assume that no pair of features are dependent. For example the temperature being Hot has nothing to do with the humidity or the outlook being Rainy does not affect the winds. Hence the features are assumed to be independent.

- Secondly each feature is given the same weight or importance. For example knowing the only temperature and humidity alone can't predict the outcome accurately. None of the attributes is irrelevant and assumed to be contributing equally to the outcome.

Gaussian Naive Bayes

Continuous values associated with each feature are assumed to be distributed according to a Gaussian distribution. A Gaussian distribution is also called Normal distribution. When plotted it gives a bell-shaped curve which is symmetric about the mean of the feature values as shown below.



This is as simple as calculating the mean and standard deviation values of each input variable x for each class value.

$$\text{Mean } (x) = 1/n * \text{sum}(x)$$

Where n is the number of instances and x is the values for an input variable in your training data. We can calculate the standard deviation using the following equation:

$$\text{Standard deviation}(x) = \sqrt{1/n * \text{sum}((x - \text{mean}(x))^2)}$$

When to use what? Standard Naive Bayes only supports categorical features while Gaussian Naive Bayes only supports continuously valued features.

Q12. What is the Confusion Matrix?

Answer:

A confusion matrix is a table that is often used to describe the performance of a classification model or classifier on a set of test data for which the true values are known. It allows the visualization of the performance of an algorithm.

A confusion matrix is a summary of prediction results on a classification problem. The number of correct and incorrect predictions are summarized with count values and broken down by each class.

This is the key to the confusion matrix

It gives us insight not only into the errors being made by a classifier but more importantly the types of errors that are being made.

	<i>Class 1 Predicted</i>	<i>Class 2 Predicted</i>
<i>Class 1 Actual</i>	TP	FN
<i>Class 2 Actual</i>	FP	TN

Here

- Class 1 Positive
- Class 2 Negative

Definition of the Terms

- 1 **Positive (P)** Observation is positive for example is an apple
- 2 **Negative (N)** Observation is not positive for example is not an apple
- 3 **True Positive (TP)** Observation is positive and is predicted to be positive
- 4 **False Negative (FN)** Observation is positive but is predicted negative
- 5 **True Negative (TN)** Observation is negative and is predicted to be negative
- 6 **False Positive (FP)** Observation is negative but is predicted positive

Q13. What is Accuracy and Misclassification Rate?

Answer

Accuracy

Accuracy is defined as the ratio of the sum of True Positive and True Negative by Total $\frac{TP+TN}{TP+TN+FP+FN}$

$$\text{Accuracy} = \frac{TP + TN}{TP + TN + FP + FN}$$

However, there are problems with accuracy. It assumes equal costs for both kinds of errors. A 99% accuracy can be excellent, good, mediocre, poor, or terrible depending upon the problem.

Misclassification Rate

Misclassification Rate is defined as the ratio of the sum of False Positive and False Negative by Total TP+TN+FP+FN

Misclassification Rate is also called Error Rate

	Actual Positive	Actual Negative
Predicted Positive	True Positive(TP)	False Positive(FP) (Type 1 Error)
Predicted Negative	False Negative(FN) (Type 2 Error)	True Negative(TN)

Accuracy = $\frac{\text{True Positive} + \text{True Negative}}{\text{Total Population}}$	Error Rate/Misclassification rate = $\frac{\text{False Positive} + \text{False Negative}}{\text{Total Population}}$
Precision = $\frac{\text{True Positive}}{\text{Predicted Positive}(TP+FP)}$	Sensitivity/Recall = $\frac{\text{True Positive}}{\text{Actual Positive}(TP+FN)}$
Specificity = $\frac{\text{True Negative}}{\text{Actual Negative}(FP+TN)}$	F1 Score = $\frac{2 * (\text{Recall} * \text{Precision})}{\text{Recall} + \text{Precision}}$

Q14. True Positive Rate & True Negative Rate

Answer:

True Positive Rate:

Sensitivity (SN) is calculated as the number of correct positive predictions divided by the total number of positives. It is also called **Recall (REC)** or true positive rate (TPR). The best sensitivity is 1.0, whereas the worst is 0.0.

$$SN = \frac{TP}{TP+FN} = \frac{TP}{P}$$

True Negative Rate

Specificity (SP) is calculated as the number of correct negative predictions divided by the total number of negatives. It is also called a true negative rate (TNR). The best specificity is 1.0, whereas the worst is 0.0.

$$SN = \frac{TP}{TPFN} = \frac{TP}{P}$$

Q15. What is False Positive Rate & False negative Rate?

False Positive Rate

False positive rate FPR is calculated as the number of incorrect positive predictions divided by the total number of positives. The best false positive rate is 0.0 whereas the worst is 1.0. It can also be calculated as 1 - specificity

$$SN = \frac{TP}{TPFN} = \frac{TP}{P}$$

False Negative Rate

False Negative rate FPR is calculated as the number of incorrect negative predictions divided by the total number of negatives. The best false negative rate is 0.0 whereas the worst is 1.0

Name	Formula	Explanation
True Positive Rate (TP rate)	$TP / (TP + FP)$	The closer to 1, the better. TP rate = 1 when FP = 0. (No false positives)
True Negative Rate (TN rate)	$TN / (TN + FN)$	The closer to 1, the better. TN rate = 1 when FN = 0. (No false negatives)
False Positive Rate (FP rate)	$FP / (FP + TN)$	The closer to 0, the better. FP rate = 0 when FP = 0. (No false positives)
False Negative Rate (FN rate)	$FN / (FN + TP)$	The closer to 0, the better. FN rate = 0 when FN = 0. (No false negatives)

Q16. What are F1 Score, precision and recall?

Recall -

Recall can be defined as the ratio of the total number of correctly classified positive examples divide to the total number of positive examples

High Recall indicates the class is correctly recognized small number of FN

2 Low Recall indicates the class is incorrectly recognized large number of FN

Recall is given by the relation

$$\text{Recall} = \frac{\text{TP}}{\text{TP} + \text{FN}}$$

Precision:

To get the value of precision we divide the total number of correctly classified positive examples by the total number of predicted positive examples

High Precision indicates an example labeled as positive is indeed positive a small number of FP

2 Low Precision indicates an example labeled as positive is indeed positive large number of FP

The relation gives precision

$$\text{Precision} = \frac{\text{TP}}{\text{TP} + \text{FP}}$$

Remember -

High recall low precision This means that most of the positive examples are correctly recognized low FN but there are a lot of false positives

Low recall high precision This shows that we miss a lot of positive examples high FN but those we predict as positive are indeed positive low FP

F-measure/F1-Score

Since we have two measures Precision and Recall it helps to have a measurement that represents both of them We calculate an **F-measure**, which uses **Harmonic Mean** in place of **Arithmetic Mean** as it punishes the extreme values more.

The F-Measure will always be nearer to the smaller value of Precision or Recall.

$$F\text{-measure} = \frac{2 * \text{Recall} * \text{Precision}}{\text{Recall} + \text{Precision}}$$

Q17. What is RandomizedSearchCV?

Answer

Randomized search CV is used to perform a random search on hyperparameters Randomized search CV uses a fit and score method predict proba decision_func transform etc

The parameters of the estimator used to apply these methods are optimized by cross-validated search over parameter settings

In contrast to GridSearchCV not all parameter values are tried out but rather a fixed number of parameter settings is sampled from the specified distributions The number of parameter settings that are tried is given by n_iter

Code Example

```
class sklearn.model_selection.RandomizedSearchCV(estimator, param_distributions,
n_iter=10, scoring=None, fit_params=None, n_jobs=None, iid='warn', refit=True,
cv='warn', verbose=0, pre_dispatch='2n_jobs', random_state=None, error_score='raise-
deprecating', return_train_score='warn')
```

Q18. What is GridSearchCV?

Answer

Grid search is the process of performing hyperparameter tuning to determine the optimal values for a given model

CODE Example -

```
from sklearn.model_selection import GridSearchCV
from sklearn.svm import SVR
gsc = GridSearchCV(estimator=SVR(kernel='rbf'), param_grid=[{'C': [0, 0.001, 0.0001], 'epsilon': [0.001, 0.0005, 0.0001], 'gamma': [0.001, 0.0005, 0.0001]}, {'C': [0.05, 0.1, 0.2, 0.5, 1, 2, 5, 10], 'epsilon': [0.001, 0.0005, 0.0001], 'gamma': [0.001, 0.0005, 0.0001]}], cv=5, scoring='neg_mean_squared_error', verbose=0, n_jobs=-1)
```


Grid search runs the model on all the possible range of hyperparameter values and outputs the best model

Q19. What is BayesianSearchCV?

Answer:

Bayesian search in contrast to the grid and random search keeps track of past evaluation results which they use to form a probabilistic model mapping hyperparameters to a probability of a score on the objective function

$$P(score | \text{hyperparameters})$$



Code

```
from skopt import BayesSearchCV
opt = BayesSearchCV(SVC)
```

```
{  
    'C'    e-6  e+6 'log-uniform'  
    'gamma'  e-6  e+  'log-uniform'  
    'degree'   8  #integer valued parameter  
    'kernel'  ['linear' 'poly' 'rbf']  
}  
n_iter=32  
cv=3
```

Q20. What is ZCA Whitening?

Answer:

Zero Component Analysis

Making the co-variance matrix as the Identity matrix is called whitening. This will remove the first and second-order statistical structure

ZCA transforms the data to zero means and makes the features linearly independent of each other


In some image analysis applications especially when working with images of the color and tiny type it is frequently interesting to apply some whitening to the data before e.g. training a classifier

DATA SCIENCE INTERVIEW PREPARATION (30 Days of Interview Preparation)

DAY 03

Q1. How do you treat heteroscedasticity in regression?

Heteroscedasticity means unequal scattered distribution. In regression analysis we generally talk about the heteroscedasticity in the context of the error term. Heteroscedasticity is the systematic change in the spread of the residuals or errors over the range of measured values. Heteroscedasticity is the problem because *Ordinary least squares (OLS)* regression assumes that all residuals are drawn from a random population that has a constant variance.



What causes Heteroscedasticity?

Heteroscedasticity occurs more often in datasets where we have a large range between the largest and the smallest observed values. There are many reasons why heteroscedasticity can exist and a generic explanation is that the error variance changes proportionally with a factor.

We can categorize Heteroscedasticity into two general types -

Pure heteroscedasticity:- It refers to cases where we specify the correct model and let us observe the non-constant variance in residual plots

Impure heteroscedasticity:- It refers to cases where you incorrectly specify the model and that causes the non-constant variance. When you leave an important variable out of a model the omitted effect is absorbed into the error term. If the effect of the omitted variable varies throughout the observed range of data it can produce the telltale signs of heteroscedasticity in the residual plots.

How to Fix Heteroscedasticity

Redefining the variables

If your model is a cross-sectional model that includes large differences between the sizes of the observations you can find different ways to specify the model that reduces the impact of the size

differential To do this change the model from using the raw measure to using rates and per capita values Of course this type of model answers a slightly different kind of question You'll need to determine whether this approach is suitable for both your data and what you need to learn

Weighted regression

It is a method that assigns each data point to a weight based on the variance of its fitted value The idea is to give small weights to observations associated with higher variances to shrink their squared residuals Weighted regression minimizes the sum of the weighted squared residuals When you use the correct weights heteroscedasticity is replaced by homoscedasticity

Q2. What is multicollinearity, and how do you treat it?

Multicollinearity means independent variables are highly correlated to each other In regression analysis it's an important assumption that the regression model should not be faced with a problem of multicollinearity

If two explanatory variables are highly correlated it's hard to tell which affects the dependent variable Let's say Y is regressed against X₁ and X₂ and where X₁ and X₂ are highly correlated Then the effect of X₁ on Y is hard to distinguish from the effect of X₂ on Y because any increase in X₁ tends to be associated with an increase in X₂

Another way to look at the multicollinearity problem is Individual t-test P values can be misleading It means a P-value can be high which means the variable is not important even though the variable is important

Correcting Multicollinearity

Remove one of the highly correlated independent variables from the model If you have two or more factors with a high VIF remove one from the model

2 Principle Component Analysis PCA - It cuts the number of interdependent variables to a smaller set of uncorrelated components Instead of using highly correlated variables use components in the model that have eigenvalue greater than

3 Run PROC VARCLUS and choose the variable that has a minimum -R² ratio within a cluster

4 Ridge Regression - It is a technique for analyzing multiple regression data that suffer from multicollinearity

5 If you include an interaction term the product of two independent variables you can also reduce multicollinearity by "centering" the variables By "centering" it means subtracting the mean from the values of the independent variable before creating the products

When is multicollinearity not a problem?

If your goal is to predict Y from a set of X variables then multicollinearity is not a problem. The predictions will still be accurate and the overall R² or adjusted R² quantifies how well the model predicts the Y values.

- 2 Multiple dummy binary variables that represent a categorical variable with three or more categories

Q3. What is market basket analysis? How would you do it in Python?

Market basket analysis is the study of items that are purchased or grouped in a single transaction or multiple sequential transactions. Understanding the relationships and the strength of those relationships is valuable information that can be used to make recommendations cross-sell up-sell offer coupons etc.

Market Basket Analysis is one of the key techniques used by large retailers to uncover associations between items. It works by looking for combinations of items that occur together frequently in transactions. To put it another way it allows retailers to identify relationships between the items that people buy.

Q4. What is Association Analysis? Where is it used?

Association analysis uses a set of transactions to discover rules that indicate the likely occurrence of an item based on the occurrences of other items in the transaction.

The technique of association rules is widely used for retail basket analysis. It can also be used for classification by using rules with class labels on the right-hand side. It is even used for outlier detection with rules indicating infrequent/abnormal association.

Association analysis also helps us to identify cross-selling opportunities for example we can use the rules resulting from the analysis to place associated products together in a catalog in the supermarket or the Webshop or apply them when targeting a marketing campaign for product B at customers who have already purchased product A.

Association rules are given in the form as below

A=>B[Support Confidence] The part before => is referred to as if Antecedent and the part after => is referred to as then Consequent

Where A and B are sets of items in the transaction data a and B are disjoint sets

Computer=>Anti-virusSoftware[Support=20% confidence=60%] Above rule says

20% transaction show Anti-virus software is bought with purchase of a Computer

2 60% of customers who purchase Anti-virus software is bought with purchase of a Computer

An example of Association Rules * Assume there are 100 customers

0 of them bought milk 8 bought butter and 6 bought both of them 2 bought milk => bought butter


2 support = P Milk & Butter = 6/ 100 = 0.06

3 confidence = support/P Butter = 0.06/0.08 = 0.75

4 lift = confidence/P Milk = 0.75/0.06 = 7.5

Q5. What is KNN Classifier ?

KNN means **K-Nearest Neighbour** Algorithm. It can be used for both classification and regression



It is the simplest machine learning algorithm. Also known as **lazy learning** why? Because it does not create a generalized model during the time of training so the testing phase is very important where it does the actual job. Hence Testing is very costly - in terms of time & money. Also called an instance-based or memory-based learning.

In k-NN classification the output is a class membership. An object is classified by a plurality vote of its neighbors with the object being assigned to the class most common among its k nearest neighbors. k is a positive integer typically small. If k = 1 then the object is assigned to the class of that single nearest neighbor.

In **k-NN regression** the output is the property value for the object. This value is the average of the values of k nearest neighbors.

Distance functions

Euclidean

$$\sqrt{\sum_{i=1}^k (x_i - y_i)^2}$$

Manhattan

$$\sum_{i=1}^k |x_i - y_i|$$

Minkowski

$$\left(\sum_{i=1}^k (x_i - y_i)^q \right)^{1/q}$$

All three distance measures are only valid for continuous variables. In the instance of categorical variables the Hamming distance must be used.

Hamming Distance

$$D_H = \sum_{i=1}^k |x_i - y_i|$$

$$x = y \Rightarrow D = 0$$

$$x \neq y \Rightarrow D = 1$$

X	Y	Distance
Male	Male	0
Male	Female	1

How to choose the value of K: K value is a hyperparameter which needs to choose during the time of model building.

Also a small number of neighbors are most flexible fit which will have a low bias but the high variance and a large number of neighbors will have a smoother decision boundary which means lower variance but higher bias.

We should choose an odd number if the number of classes is even. It is said the most common values are to be 3 & 5.

Q6. What is Pipeline in sklearn ?

A pipeline is what chains several steps together once the initial exploration is done. For example some codes are meant to transform features normalize numerically or turn text into vectors or fill up missing data and they are transformers; other codes are meant to predict variables by fitting an algorithm.

such as random forest or support vector machine they are estimators Pipeline chains all these together which can then be applied to training data in block

Example of a pipeline that imputes data with the most frequent value of each column and then fit a decision tree classifier

```
From sklearn.pipeline import Pipeline  
steps = [ 'imputation' Imputer missing_values='NaN' strategy = 'most_frequent' axis=0  
         'clf' DecisionTreeClassifier ]  
pipeline = Pipeline steps  
clf = pipeline fit X_train y_train '''
```

Instead of fitting to one model it can be looped over several models to find the best one

```
classifiers = [ KNeighborsClassifier 5 RandomForestClassifier GradientBoostingClassifier ]  
for clf in classifiers  
    steps = [ 'imputation' Imputer missing_values='NaN' strategy = 'most_frequent' axis=0  
             'clf' clf ]  
  
pipeline = Pipeline steps
```

I also learned the pipeline itself can be used as an estimator and passed to cross-validation or grid search

```
from sklearn.model_selection import KFold  
from sklearn.model_selection import cross_val_score  
kfold = KFold n_splits= 0 random_state=seed  
results = cross_val_score pipeline X_train y_train cv=kfold  
print results mean
```

Q7. What is Principal Component Analysis(PCA), and why we do?

The main idea of principal component analysis PCA is to reduce the dimensionality of a data set consisting of many variables correlated with each other either heavily or lightly while retaining the variation present in the dataset up to the maximum extent The same is done by transforming the variables to a new set of variables which are known as the principal components or simply the PCs and are orthogonal ordered such that the retention of variation present in the original variables decreases as we move down in the order So in this way the st principal component retains maximum variation that was present in the original components The principal components are the eigenvectors of a covariance matrix and hence they are orthogonal

Main important points to be considered

- Normalize the data
- 2 Calculate the covariance matrix
- 3 Calculate the eigenvalues and eigenvectors
- 4 Choosing components and forming a feature vector
- 5 Forming Principal Components

Q8. What is t-SNE?

t-SNE t-Distributed Stochastic Neighbor Embedding is a non-linear dimensionality reduction algorithm used for exploring high-dimensional data. It maps multi-dimensional data to two or more dimensions suitable for human observation. With the help of the t-SNE algorithms you may have to plot fewer exploratory data analysis plots next time you work with high dimensional data.

Q9. VIF(Variation Inflation Factor), Weight of Evidence & Information

Value. Why and when to use?

Variation Inflation Factor

It provides an index that measures how much the variance the square of the estimate's standard deviation of an estimated regression coefficient is increased because of collinearity.

$VIF = \frac{1}{1 - R^2}$ where R^2 of jth variable is the coefficient of determination of the model that includes all independent variables except the jth predictor.

Where R^2 of jth variable is the multiple R^2 for the regression of X_j on the other independent variables a regression that does not involve the dependent variable Y.

If $VIF > 5$ then there is a problem with multicollinearity.

Understanding VIF

If the variance inflation factor of a predictor variable is 5 this means that variance for the coefficient of that predictor variable is 5 times as large as it would be if that predictor variable were uncorrelated with the other predictor variables.

In other words if the variance inflation factor of a predictor variable is 5 this means that the standard error for the coefficient of that predictor variable is 2.23 times $\sqrt{5} = 2.23$ as large as it would be if that predictor variable were uncorrelated with the other predictor variables.

Weight of evidence (WOE) and information value (IV) are simple yet powerful techniques to perform variable transformation and selection



The formula to create WOE and IV is

$$WOE = \ln\left(\frac{\text{Event}\%}{\text{Non Event}\%}\right)$$

$$IV = \sum (\text{Event}\% - \text{Non Event}\%) * \ln\left(\frac{\text{Event}\%}{\text{Non Event}\%}\right)$$

Here is a simple table that shows how to calculate these values

Variable Name	Min. Value	Max. Value	Count	# Event	# Non Event	Event%	Non event%	WOE	Event% - Non event%	IV
Age	10	20	1200	150	1050	28.3%	19.0%	0.3992	9.3%	0.03718
Age	21	30	900	120	780	22.6%	14.1%	0.4733	8.5%	0.04040
Age	31	40	1090	110	980	20.8%	17.7%	0.1580	3.0%	0.00479
Age	41	50	1460	100	1360	18.9%	24.6%	-0.2650	-5.7%	0.01517
Age	50	inf	1410	50	1360	9.4%	24.6%	-0.9582	-15.2%	0.14525
Total			6060	530	5530					0.24279

The IV value can be used to select variables quickly


Information Value (IV)	Predictive Power
< 0.02	useless for prediction
0.02 to 0.1	weak predictor
0.1 to 0.3	medium predictor
0.3 to 0.5	strong predictor
> 0.5	suspicious or too good to be true

Q10: How to evaluate that data does not have any outliers ?

In statistics outliers are data points that don't belong to a certain population. It is an abnormal observation that lies far away from other values. An outlier is an observation that diverges from otherwise well-structured data.


Detection:

Method 1 Standard Deviation: In statistics If a data distribution is approximately normal then about 68% of the data values lie within one standard deviation of the mean and about 95% are within two standard deviations and about 99.7% lie within three standard deviations




Therefore if you have any data point that is more than 3 times the standard deviation then those points are very likely to be anomalous or outliers


Method 2 Boxplots Box plots are a graphical depiction of numerical data through their quantiles. It is a very simple but effective way to visualize outliers. Think about the lower and upper whiskers as the boundaries of the data distribution. Any data points that show above or below the whiskers can be considered outliers or anomalous



Method 3 - Violin Plots Violin plots are similar to box plots except that they also show the probability density of the data at different values usually smoothed by a kernel density estimator. Typically a violin plot will include all the data that is in a box plot a marker for the median of the data a box or marker indicating the interquartile range and possibly all sample points if the number of samples is not too high.



Method 4 - Scatter Plots A scatter plot is a type of plot or mathematical diagram using Cartesian coordinates to display values for typically two variables for a set of data. The data are displayed as a collection of points each having the value of one variable determining the position on the horizontal axis and the value of the other variable determining the position on the vertical axis.



The points which are very far away from the general spread of data and have a very few neighbors are considered to be outliers.

Q11: What you do if there are outliers?

Following are the approaches to handle the outliers

- Drop the outlier records
- 2 Assign a new value If an outlier seems to be due to a mistake in your data you try imputing a value
- 3 If percentage-wise the number of outliers is less but when we see numbers there are several then in that case dropping them might cause a loss in insight We should group them in that case and run our analysis separately on them

Q12: What are the encoding techniques you have applied with Examples ?

In many practical data science activities the data set will contain categorical variables These variables are typically stored as text values" Since machine learning is based on mathematical equations it would cause a problem when we keep categorical variables as is

Let's consider the following dataset of fruit names and their weights

Some of the common encoding techniques are

Label encoding: In label encoding we map each category to a number or a label The labels chosen for the categories have no relationship So categories that have some ties or are close to each other lose such information after encoding

One - hot encoding: In this method we map each category to a vector that contains 1 and 0 denoting the presence of the feature or not The number of vectors depends on the categories which we want to keep For high cardinality features this method produces a lot of columns that slows down the learning significantly

Q13: Tradeoff between bias and variances, the relationship between them.


Whenever we discuss model prediction it's important to understand prediction errors bias and variance The prediction error for any machine learning algorithm can be broken down into three parts

- Bias Error
- Variance Error
- Irreducible Error

The irreducible error cannot be reduced regardless of what algorithm is used. It is the error introduced from the chosen framing of the problem and may be caused by factors like unknown variables that influence the mapping of the input variables to the output variable.

Bias: Bias means that the model favors one result more than the others. Bias is the simplifying assumptions made by a model to make the target function easier to learn. The model with high bias pays very little attention to the training data and oversimplifies the model. It always leads to a high error in training and test data.

Variance: Variance is the amount that the estimate of the target function will change if different training data was used. The model with high variance pays a lot of attention to training data and does not generalize on the data which it hasn't seen before. As a result, such models perform very well on training data but have high error rates on test data.



So the end goal is to come up with a model that balances both Bias and Variance. This is called *Bias Variance Trade-off*. To build a good model we need to find a good balance between bias and variance such that it minimizes the total error.

Q14: What is the difference between Type 1 and Type 2 error and severity of the error?

Type I Error

A Type I error is often referred to as a "false positive" and is the incorrect rejection of the true null hypothesis in favor of the alternative.

In the example above the null hypothesis refers to the natural state of things or the absence of the tested effect or phenomenon i.e. stating that the patient is HIV negative. The alternative hypothesis states that the patient is HIV positive. Many medical tests will have the disease they are testing for as the alternative hypothesis and the lack of that disease as the null hypothesis.

A Type I error would thus occur when the patient doesn't have the virus but the test shows that they do. In other words the test incorrectly rejects the true null hypothesis that the patient is HIV negative.

Type II Error

A Type II error is the inverse of a Type I error and is the false acceptance of a null hypothesis that is not true i.e. a false negative. A Type II error would entail the test telling the patient they are free of HIV when they are not.

Considering this HIV example which error type do you think is more acceptable? In other words would you rather have a test that was more prone to Type I or Type II error? With HIV the momentary stress of a false positive is likely better than feeling relieved at a false negative and then failing to take steps to treat the disease. Pregnancy tests blood tests and any diagnostic tool that has serious consequences for the health of a patient are usually overly sensitive for this reason they should err on the side of a false positive.

But in most fields of science Type II errors are seen as less serious than Type I errors. With the Type II error a chance to reject the null hypothesis was lost and no conclusion is inferred from a non-rejected null. But the Type I error is more serious because you have wrongly rejected the null hypothesis and ultimately made a claim that is not true. In science finding a phenomenon where there is none is more egregious than failing to find a phenomenon where there is.

Q15: What is binomial distribution and polynomial distribution?

Binomial Distribution: A binomial distribution can be thought of as simply the probability of a SUCCESS or FAILURE outcome in an experiment or survey that is repeated multiple times. The binomial is a type of distribution that has two possible outcomes the prefix bi means two or twice. For example a coin toss has only two possible outcomes heads or tails and taking a test could have two possible outcomes pass or fail.

Multimomial/Polynomial Distribution: Multi or Poly means many. In probability theory the multinomial distribution is a generalization of the binomial distribution. For example it models the probability of counts of each side for rolling a k-sided die n times. For n independent trials each of which leads to success for exactly one of k categories with each category having a given fixed success probability the multinomial distribution gives the probability of any particular combination of numbers of successes for the various categories.

Q16: What is the Mean Median Mode standard deviation for the sample and population?

Mean It is an important technique in statistics. Arithmetic Mean can also be called an average. It is the number of the quantity obtained by summing two or more numbers/variables and then dividing the sum by the number of numbers/variables.

Mode The mode is also one of the types for finding the average. A mode is a number that occurs most frequently in a group of numbers. Some series might not have any mode; some might have two modes which is called a bimodal series.

In the study of statistics the three most common averages in statistics are mean median and mode.

Median is also a way of finding the average of a group of data points. It's the middle number of a set of numbers. There are two possibilities the data points can be an odd number group or it can be an even number group.

If the group is odd arrange the numbers in the group from smallest to largest. The median will be the one which is exactly sitting in the middle with an equal number on either side of it. If the group is even arrange the numbers in order and pick the two middle numbers and add them then divide by 2. It will be the median number of that set.

Standard Deviation (Sigma) Standard Deviation is a measure of how much your data is spread out in statistics.

Q17: What is Mean Absolute Error ?

What is Absolute Error? Absolute Error is the amount of error in your measurements. It is the difference between the measured value and the true value. For example if a scale states 90 pounds but you know your true weight is 89 pounds then the scale has an absolute error of 90 lbs - 89 lbs = 1 lbs.

This can be caused by your scale not measuring the exact amount you are trying to measure. For example your scale may be accurate to the nearest pound. If you weigh 89.6 lbs the scale may round up and give you 90 lbs. In this case the absolute error is 90 lbs - 89.6 lbs = .4 lbs.

Mean Absolute Error The Mean Absolute Error MAE is the average of all absolute errors. The formula is mean absolute error

$$\text{MAE} = \frac{1}{n} \sum_{i=1}^n |x_i - \bar{x}|$$

Where

n = the number of errors Σ = summation symbol which means add them all up $|x_i - \bar{x}|$ = the absolute errors The formula may look a little daunting but the steps are easy

Find all of your absolute errors $x_i - \bar{x}$ Add them all up Divide by the number of errors For example if you had 0 measurements divide by 0

Q18: What is the difference between long data and wide data?

There are many different ways that you can present the same dataset to the world Let's take a look at one of the most important and fundamental distinctions whether a dataset is wide or long

The difference between wide and long datasets boils down to whether we prefer to have more columns in our dataset or more rows

Wide Data A dataset that emphasizes putting additional data about a single subject in columns is called a wide dataset because as we add more columns the dataset becomes wider

Long Data Similarly a dataset that emphasizes including additional data about a subject in rows is called a long dataset because as we add more rows the dataset becomes longer It's important to point out that there's nothing inherently good or bad about wide or long data

In the world of data wrangling we sometimes need to make a long dataset wider and we sometimes need to make a wide dataset longer However it is true that as a general rule data scientists who embrace the concept of tidy data usually prefer longer datasets over wider ones

Q19: What are the data normalization method you have applied, and why?

Normalization is a technique often applied as part of data preparation for machine learning The goal of normalization is to change the values of numeric columns in the dataset to a common scale without distorting differences in the ranges of values For machine learning every dataset does not require normalization It is required only when features have different ranges

In simple words when multiple attributes are there but attributes have values on different scales this may lead to poor data models while performing data mining operations So they are normalized to bring all the attributes on the same scale usually something between 0

It is not always a good idea to normalize the data since we might lose information about maximum and minimum values Sometimes it is a good idea to do so

For example, ML algorithms such as Linear Regression or Support Vector Machines typically converge faster on normalized data But on algorithms like K-means or K Nearest Neighbours normalization could

be a good choice or a bad depending on the use case since the distance between the points plays a key role here

person_name	Salary	Year_of_experience	Expected Position Level	
Aman	100000	10	2	The attributes salary and year_of_experience are on different scale and hence attribute salary can take high priority over attribute year_of_experience in the model.
Abhinav	78000	7	4	
Ashutosh	32000	5	8	
Dishi	55000	6	7	
Abhishek	92000	8	3	
Avantika	120000	15	1	
Ayushi	65750	7	5	

Types of Normalisation :

1 Min-Max Normalization: In most cases standardization is used feature-wise

$$\hat{X}[:, i] = \frac{X[:, i] - \min(X[:, i])}{\max(X[:, i]) - \min(X[:, i])}$$

2 Z-score normalization In this technique values are normalized based on a mean and standard deviation of the data

$$v' = \frac{v - \bar{A}}{\sigma_A}$$

v v' is new and old of each entry in data respectively σ_A A is the standard deviation and mean of A respectively

standardization or Z-score normalization is that the features will be rescaled so that they'll have the properties of a standard normal distribution with

$\mu=0$ and $\sigma=1$ where μ is the mean average and σ is the standard deviation from the mean; standard scores also called z scores of the samples are calculated as follows

$$z = \frac{x - \mu}{\sigma}$$

Q20: What is the difference between normalization and Standardization with example?

In ML every practitioner knows that feature scaling is an important issue. The two most discussed scaling methods are **Normalization** and **Standardization**. Normalization typically means it rescales the values into a range of [0 1].

It is an alternative approach to Z-score normalization or standardization is the so-called Min-Max scaling often also called normalization - a common cause for ambiguities. In this approach the data is scaled to a fixed range - **usually 0 to 1**. Scikit-Learn provides a transformer called **MinMaxScaler** for this. A Min-Max scaling is typically done via the following equation:

$$X_{\text{norm}} = \frac{X - X_{\text{min}}}{X_{\text{max}} - X_{\text{min}}}$$

Example with sample data: Before Normalization: Attribute Price in Dollars Storage Space Camera

- Attribute Price in Dollars Storage Space Camera
- Mobile 250 6 2
- Mobile 2 200 6 8
- Mobile 3 300 32 6
- Mobile 4 275 32 8
- Mobile 5 225 6 6

After Normalization: (Values ranges from 0-1 which is working as expected)

- Attribute Price in Dollars Storage Space Camera
- Mobile 0.5 0.05
- Mobile 2 0 0 0
- Mobile 3
- Mobile 4 0.75 0
- Mobile 5 0.25 0

Standardization or Z-score normalization typically means rescales data to have a mean of 0 and a standard deviation of 1 unit variance. Formula $Z \text{ or } X_{\text{new}} = \frac{(x - \mu)}{\sigma}$ where μ is the mean average and σ is the standard deviation from the mean; standard scores also called z scores. Scikit-Learn provides a transformer called **StandardScaler** for standardization. **Example:** Let's take an approximately normally distributed set of numbers 2 2 3 3 3 4 4 and 5. Its mean is 3 and its standard deviation is 2. Now let's subtract the mean from all data points we get a new data set of -2 -1 0 0 0 and 2. Now let's divide each data point by 2. As you can see in the picture below we get -0.82 -0.82 0 0 0.82 0.82 and 0.63.

Now let's subtract the mean from all data points we get a new data set of -2 -1 0 0 0 and 2. Now let's divide each data point by 2. As you can see in the picture below we get -0.82 -0.82 0 0 0.82 0.82 and 0.63.

**DATA SCIENCE
INTERVIEW PREPARATION
(30 Days of Interview
Preparation)**

DAY 04

Q1. What is upsampling and downsampling with examples?

The classification data set with skewed class proportions is called an imbalanced data set. Classes which make up a large proportion of the data sets are called majority classes. Those make up smaller proportions are minority classes.

Degree of imbalance Proportion of Minority Class

1>> Mild 20-40% of the data set

2>> Moderate 1-20% of the data set

3>> Extreme <1% of the data set

If we have an imbalanced data set, first try training on the true distribution. If the model works well and generalises, you are done! If not, try the following up sampling and down sampling technique.

1. Up-sampling

Upsampling is the process of randomly duplicating observations from the minority class to reinforce its signal.

First, we will import the resampling module from Scikit-Learn:

Module for resampling Python

1- From sklearn.utils import resample

Next, we will create a new Data Frame with an up-sampled minority class. Here are the steps:

1- First, we will separate observations from each class into different Data Frames.

2- Next, we will resample the minority class with replacement, setting the number of samples to match that of the majority class.

3- Finally, we'll combine the up-sampled minority class Data Frame with the original majority class Data Frame.

2-Down-sampling

Downsampling involves randomly removing observations from the majority class to prevent its signal from dominating the learning algorithm.

The process is similar to that of sampling. Here are the steps:

1-First, we will separate observations from each class into different Data Frames.

2-Next, we will resample the majority class without replacement, setting the number of samples to match that of the minority class.

3-Finally, we will combine the down-sampled majority class Data Frame with the original minority class Data Frame.

Q2. What is the statistical test for data validation with an example,

Chi-square, ANOVA test, Z statics, T statics, F statics,

Hypothesis Testing?

Before discussing the different statistical test, we need to get a clear understanding of what a null hypothesis is. A null hypothesis proposes that no significant difference exists in the set of a given observation.

Null: Two samples mean are equal. **Alternate:** Two samples mean are not equal.

For rejecting the null hypothesis, a test is calculated. Then the test statistic is compared with a critical value, and if found to be greater than the critical value, the hypothesis will be rejected.

Critical Value:-

Critical values are the point beyond which we reject the null hypothesis. Critical value tells us, what is the probability of N number of samples, belonging to the same distribution. Higher, the critical value which means lower the probability of N number of samples belonging to the same distribution.

Critical values can be used to do hypothesis testing in the following way.

1. Calculate test statistic
2. Calculate critical values based on the significance level alpha
3. Compare test statistics with critical values.

IMP-If the test statistic is lower than the critical value, accept the hypothesis or else reject the hypothesis.

Chi-Square Test:-

A chi-square test is used if there is a relationship between two categorical variables.

Chi-Square test is used to determine whether there is a significant difference between the expected frequency and the observed frequency in one or more categories. Chi-square is also called the non-parametric test as it will not use any parameter

2-Anova test:-

ANOVA, also called an analysis of variance, is used to compare multiples (three or more) samples with a single test.

Useful when there are more than three populations. Anova compares the variance within and between the groups of the population. If the variation is much larger than the within variation, the means of different samples will not be equal. If the between and within variations are approximately the same size, then there will be no significant difference between sample means. Assumptions of ANOVA: 1-All populations involved follow a normal distribution. 2-All populations have the same variance (or standard deviation). 3-The samples are randomly selected and independent of one another.

ANOVA uses the mean of the samples or the population to reject or support the null hypothesis. Hence it is called parametric testing.

3-Z Statics:-

In a z-test, the samples are assumed to be normal distributed. A z score is calculated with population parameters as "population mean" and "population standard deviation" and it is used to validate a hypothesis that the sample drawn belongs to the same population.

The statistics used for this hypothesis testing is called z-statistic, the score for which is calculated as $z = (x - \mu) / (\sigma / \sqrt{n})$, where x = sample mean μ = population mean σ / \sqrt{n} = population standard deviation If the test statistic is lower than the critical value, accept the hypothesis or else reject the hypothesis

4- T Statics:-

A t-test used to compare the mean of the given samples. Like z-test, t-test also assumed a normal distribution of the samples. A t-test is used when the population parameters (mean and standard deviation) are unknown.

There are three versions of t-test

1. Independent samples t-test which compare means for two groups
2. Paired sample t-test which compares mean from the same group at different times
3. Sample t-test, which tests the mean of the single group against the known mean. The statistic for hypothesis testing is called t-statistic, the score for which is calculated as $t = (x_1 - x_2) / (\sigma / \sqrt{n_1} + \sigma / \sqrt{n_2})$, where

x_1 = It is mean of sample A, x_2 = mean of sample B,

n_1 = size of sample 1 n_2 = size of sample 2

5- F Statistics:-

The F-test is designed to test if the two population variances are equal. It compares the ratio of the two variances. Therefore, if the variances are equal, then the ratio of the variances will be 1.

The F-distribution is the ratio of two independent chi-square variables divided by their respective degrees of freedom.

$F = s_1^2 / s_2^2$ and where $s_1^2 > s_2^2$.

If the null hypothesis is true, then the F test-statistic given above can be simplified. This ratio of sample variances will be tested statistic used. If the null hypothesis is false, then we will reject the null hypothesis that the ratio was equal to 1 and our assumption that they were equal.

Q3. What is the Central limit theorem?

Central Limit Theorem

Definition: The theorem states that as the size of the sample increases, the distribution of the mean across multiple samples will approximate a Gaussian distribution (Normal). Generally, sample sizes equal to or greater than 30 are considered sufficient for the CLT to hold. It means that the distribution of the sample means is normally distributed. The average of the

sample means will be equal to the population mean. This is the key aspect of the theorem.

Assumptions:

1. The data must follow the randomization condition. It must be sampled randomly
2. Samples should be independent of each other. One sample should not influence the other samples
3. Sample size should be no more than 10% of the population when sampling is done without replacement
4. The sample size should be sufficiently large. The mean of the sample means is denoted as:

$$\mu \bar{X} = \mu$$

Where,

$\mu \bar{X}$ = Mean of the sample means μ = Population mean and, the standard deviation of the sample mean is denoted as:

$$\sigma \bar{X} = \sigma / \sqrt{n}$$

Where,

$\sigma \bar{X}$ = Standard deviation of the sample mean σ = Population standard deviation n = sample size

A sufficiently large sample size can predict the characteristics of a population accurately. For Example, we shall take a uniformly distributed data:

Randomly distributed data: Even for a randomly (Exponential) distributed data the plot of the means is normally distributed.


The advantage of CLT is that we need not worry about the actual data since the means of it will always be normally distributed. With this, we can create component intervals, perform T-tests and ANOVA tests from the given samples.

Q4. What is the correlation and coefficient?

What is the Correlation Coefficient?

The correlation coefficient is a statistical measure that calculates the strength of the relationship between the relative movements of two

variables. We use it to measure both the strength and direction of a linear relationship between two variables the values range between -1.0 and 1.0. A calculated number greater than 1.0 or less than -1.0 means that there was an error in the correlation measurement. A correlation of -1.0 shows a perfect negative correlation, while a correlation of 1.0 shows a perfect positive correlation.



Correlation coefficient formulas are used to find how strong a relationship is between data. The formulas return a value between -1 and 1, where:

1 indicates a strong positive relationship. -1 indicates a strong negative relationship. A result of zero indicates no relationship at all.

Meaning


1. A correlation coefficient of 1 means that for every positive increase in one variable, there is a positive increase in a fixed proportion in the other. For example, shoe sizes go up in (almost) perfect correlation with foot length.
2. A correlation coefficient of -1 means that for every positive increase in one variable, there is a negative decrease of a fixed proportion in the other. For example, the amount of gas in a tank decreases in (almost) perfect correlation with speed.
3. Zero means that for every increase, there isn't a positive or negative increase. The two just aren't related.

What is a Negative Correlation?

Negative correlation is a relationship between two variables in which one variable increases as the other decreases, and vice versa. In statistics, a perfect negative correlation is represented by the value -1. Negative correlation or inverse correlation is a relationship between two variables whereby they move in opposite directions. If variables X and Y have a negative correlation (or are negatively correlated), as X increases in value, Y will decrease; similarly, if X decreases in value, Y will increase.

What Is Positive Correlation?

Positive correlation is a relationship between two variables in which both variables move in tandem—that is, in the same direction. A positive correlation exists when one variable decreases as the other variable decreases or one variable increases while the other increases.



We use the correlation coefficient to measure the strength and direction of the linear relationship between two numerical variables X and Y. The correlation coefficient for a sample of data is denoted by r .

Pearson Correlation Coefficient

Pearson is the most widely used correlation coefficient. Pearson correlation measures the linear association between continuous variables. In other words, this coefficient quantifies the degree to which a relationship between two variables can be described by a line. Formula developed by Karl Pearson over 120 years ago is still the most widely used today. The formula for the correlation (r) is

Correlation Coefficient Formula

$$r = \frac{n(\Sigma xy) - (\Sigma x)(\Sigma y)}{\sqrt{[n\Sigma x^2 - (\Sigma x)^2][n\Sigma y^2 - (\Sigma y)^2]}}$$

Where n is the number of pairs of data;

Are the sample means of all the x-values and all the y-values, respectively; and sx and sy are the sample standard deviations of all the x- and y-values, respectively.

1. Find the mean of all the x-values and mean of all y-values.
2. Find the standard deviation of all the x-values (call it sx) and the standard deviation of all the y-values (call it sy). For example, to find sx, you would use the following equation:
3. For each of the n pairs (x, y) in the data set, take
4. Add up the n results from Step 3.
5. Divide the sum by sx * sy.
6. Divide the result by n – 1, where n is the number of (x, y) pairs. (It's the same as multiplying by 1 over n – 1.) This gives you the correlation, r.


Q5: What is the difference between machine learning and deep learning?**Machine Learning | deep learning**

Machine Learning is a technique to learn from that data and then apply what has been learnt to make an informed decision | The main difference between deep and machine learning is, machine learning models become better progressively but the model still needs some guidance. If a machine-learning model returns an inaccurate prediction then the programmer needs to fix that problem explicitly but in the case of deep learning, the model does it by himself.

- > Machine Learning can perform well with small size data also | Deep Learning does not perform as good with smaller datasets.
- > Machine learning can work on some low-end machines also | Deep Learning involves many matrix multiplication operations which are better suited for GPUs
- > Features need to be identified and extracted as per the domain before pushing them to the algorithm | Deep learning algorithms try to learn high-level features from data.
- > It is generally recommended to break the problem into smaller chunks, solve them and then combine the results | It generally focusses on solving the problem end to end
- > Training time is comparatively less | Training time is comparatively more
- > Results are more interpretable | Results Maybe more accurate but less interpretable
 - > No use of Neural networks | uses neural networks
 - > Solves comparatively less complex problems | Solves more complex problems.

Q6: What is perceptron and how it is related to human neurons?

If we focus on the structure of a biological neuron, it has dendrites, which are used to receive inputs. These inputs are summed in the cell body and using the Axon it is passed on to the next biological neuron as shown below.




Dendrite: Receives signals from other neurons

Cell Body: Sums all the inputs


Axon: It is used to transmit signals to the other cells

Similarly, a perceptron receives multiple inputs, applies various transformations and functions and provides an output. A Perceptron is a linear model used for binary classification. It models a neuron, which has a set of inputs, each of which is given a specific weight. The neuron computes some function on these weighted inputs and gives the output.



Q7: Why deep learning is better than machine learning?

Though traditional ML algorithms solve a lot of our cases, they are not useful while working with high dimensional data that is where we have a large number of inputs and outputs. For example, in the case of handwriting recognition, we have a large amount of input where we will have different types of inputs associated with different types of handwriting.



The second major challenge is to tell the computer what are the features it should look for that will play an important role in predicting the outcome as well as to achieve better accuracy while doing so.

Q8: What kind of problem can be solved by using deep learning?

Deep Learning is a branch of Machine Learning, which is used to solve problems in a way that mimics the human way of solving problems.

Examples:

- Image recognition
- Object Detection
- Natural Language processing- Translation, Sentence formations, text to speech, speech to text
- understand the semantics of actions

Q9: List down all the activation function using mathematical

Expression and example. What is the activation function?

Activation functions are very important for an Artificial Neural Network to learn and make sense of something complicated and the Non-linear complex functional mappings between the inputs and response variable. They introduce non-linear properties to our Network. Their main purposes are to convert an input signal of a node in an A-NN to an output signal.


So why do we need Non-Linearities?

Non-linear functions are those, which have a degree more than one, and they have a curvature when we plot a Non-Linear function. Now we need a Neural Network Model to learn and represent almost anything and any arbitrary complex function, which maps inputs to outputs. Neural-Networks are considered Universal Function Approximations. It means that they can compute and learn any function at all.

Most popular types of Activation functions -


- Sigmoid or Logistic
- Tanh Hyperbolic tangent
- ReLu -Rectified linear units

Sigmoid Activation function: It is a activation function of form $f(x) = 1 / (1 + \exp(-x))$. Its Range is between 0 and 1. It is an S-shaped curve. It is easy to understand.




Hyperbolic Tangent function- Tanh : It's mathematical formula is $f(x) = \tanh(x) = (\exp(x) - \exp(-x)) / (1 + \exp(-x))$. Now it's the output is zero centred because its range in between -1 to 1 i.e. $-1 < \text{output} < 1$. Hence optimisation is easier in this method; Hence in practice, it is always preferred over Sigmoid function.

hyperbolic tangent function




ReLU- Rectified Linear units: It has become more popular in the past couple of years. It was recently proved that it has six times improvement in convergence from Tanh function. It's $R(x) = \max(0, x)$ i.e. if $x < 0$, $R(x) = 0$ and if $x \geq 0$, $R(x) = x$. Hence as seen that mathematical form of this function, we can see that it is very simple and efficient. Many times in Machine learning and computer science we notice that most simple and consistent techniques and methods are only preferred and are the best. Hence, it avoids and rectifies the vanishing gradient problem. Almost all the deep learning Models use ReLU nowadays.



Q10: Detail explanation about gradient decent using example and Mathematical expression?

Gradient descent is an optimisation algorithm used to minimize some function by iteratively moving in the direction of steepest descent as defined by negative of the gradient. In machine learning, we used gradient descent to update the parameters of our model. Parameters refer to coefficients in the Linear Regression and weights in neural networks.



The size of these steps called the learning rate. With the high learning rate, we can cover more ground each step, but we risk overshooting the lower point since the slope of the hill is constantly changing. With a very lower learning rate, we can confidently move in the direction of the negative gradient because we are recalculating it so frequently. The Lower learning rate is more precise, but calculating the gradient is time-consuming, so it will take a very large time to get to the bottom.

Math

Now let's run gradient descent using new cost function. There are two parameters in cost function we can control: m (weight) and b (bias). Since we need to consider that the impact each one has on the final prediction, we need to use partial derivatives. We calculate the partial derivative of the cost function concerning each parameter and store the results in a gradient.

Math

Given the cost function:

$$f(m, b) = \frac{1}{N} \sum_{i=1}^n (y_i - (mx_i + b))^2$$

The gradient can be calculated as:


$$f'(m, b) = \begin{bmatrix} \frac{df}{dm} \\ \frac{df}{db} \end{bmatrix} = \begin{bmatrix} \frac{1}{N} \sum -2x_i(y_i - (mx_i + b)) \\ \frac{1}{N} \sum -2(y_i - (mx_i + b)) \end{bmatrix}$$

To solve for the gradient, we iterate by our data points using our new m and b values and compute the partial derivatives. This new gradient tells us about the slope of the cost function at our current position (current parameter values) and the directions we should move to update our parameters. The learning rate controls the size of our update.

Q11: What is backward propagation?

Back-propagation is the essence of the neural net training and this method of fine-tuning the weights of a neural net based on the errors rate obtained in the previous epoch. Proper tuning of the weights allows us to reduce error rates and to make the model reliable by increasing its generalisation.

Backpropagation is a short form of "backward propagation of errors." This is the standard method of training artificial neural networks. This helps to calculate the gradient of a loss function with respects to all the weights in the network.



Most prominent advantages of Backpropagation are:

- Backpropagation is the fast, simple and easy to program.
- It has no parameters to tune apart from the numbers of input.
- It is the flexible method as it does not require prior knowledge about the network
- It is the standard method that generally works well.
- It does not need any special mentions of the features of the function to be learned.


The BackPropagation Algorithm

Main idea:

For each example in the training set:

- compute the output signal
- compute the error corresponding to the output level
- propagate the error back into the network and store the corresponding delta values for each layer
- adjust each weight by using the error signal and input signal for each layer

Computation of the error signal (BACKWARD)



Computation of the output signal (FORWARD)

Q12: How we assign weights in deep learning?

We already know that in a neural network, weights are usually initialised randomly and that kind of initialisation takes a fair/significant amount of repetitions to converge to the least loss and reach the ideal weight matrix. The problem is, that kind of initialisation is prone to vanishing or exploding gradient problems.

General ways to make it initialise better weights:

ReLU activation function in the deep nets.

1. Generate a random sample of weights from a Gaussian distribution having mean 0 and a standard deviation of 1.
2. Multiply the sample with the square root of $(2/n_i)$. Where n_i is the number of input units for that layer.

b) Likewise, if you're using Tanh activation function :

1. Generate a random sample of weights from a Gaussian distribution having mean 0 and a standard deviation of 1.
2. Multiply the sample with the square root of $(1/n_i)$ where n_i is several input units for that layer.

Q13: What is optimiser in deep learning, and which one is the best?

Deep learning is an iterative process. With so many hyperparameters to tune or methods to try, it is important to be able to train models fast, to quickly complete the iterative cycle. This is the key to increase the speed and efficiency of a machine learning team.

Hence the importance of optimisation algorithms such as stochastic gradient descent, min-batch gradient descent, gradient descent with momentum and the Adam optimiser.

Adam optimiser is the best one.

Given an algorithm $f(x)$, it helps in either minimisation or maximisation of the value of $f(x)$. In this context of deep learning, we use optimisation algorithms to train the neural network by optimising the cost function J .

The cost function is defined as:

$$J(W, b) = \sum_{i=1}^m L(y'^i, y^i)$$

The value of the cost function J is the mean of the loss L between the predicted value y' and actual value y . The value y' is obtained during the forward propagation step and makes use of the Weights W and biases b of the network. With the help of optimisation algorithms, we minimise the value of Cost Function J by updating the values of trainable parameters W and b .

Q14: What is gradient descent, mini-batch gradient descent, batch gradient decent, stochastic gradient decent and adam?

Gradient Descent

it is an iterative machine learning optimisation algorithm to reduce the cost function, and help models to make accurate predictions.

Gradient indicates the direction of increase. As we want to find the minimum points in the valley, we need to go in the opposite direction of the gradient. We update the parameters in the negative gradient direction to minimise the loss.

$$\theta = \theta - \eta \nabla J(\theta; x, y)$$

Where θ is the weight parameter, η is the learning rate, and $\nabla J(\theta; x, y)$ is the gradient of weight parameter θ

Types of Gradient Descent

Different types of Gradient descents are

- Batch Gradient Descent or Vanilla Gradient Descent
- Stochastic Gradient Descent

- Mini batch Gradient Descent

Batch Gradient Descent

In the batch gradient, we use the entire dataset to compute the gradient of the cost function for each iteration for gradient descent and then update the weights.

Stochastic Gradient descent

Stochastic gradient descent, we use a single data point or example to calculate the gradient and update the weights with every iteration.

We first need to shuffle the datasets so that we get a completely randomised dataset. As the datasets are random and weights, are updated for every single example, an update of the weights and the cost functions will be noisy jumping all over the place

Mini Batch Gradient descent

Mini-batch gradients is a variation of stochastic gradient descent where instead of a single training example, a mini-batch of samples are used.

Mini -batch gradient descent is widely used and converges faster and is more stable.

The batch size can vary depending upon the dataset.


As we take batches with different samples, it reduces the noise which is a variance of the weights updates, and that helps to have a more stable converge faster.

Q15: What are autoencoders?

An **autoencoder**, neural networks that have three layers:

An input layer, a hidden layer which is also known as encoding layer, and a decoding layer. This network is trained to reconstruct its inputs, which forces the hidden layer to try to learn good representations of the inputs.

An autoencoder neural network is an unsupervised Machine-learning algorithm that applies backpropagation, setting the target values to be equal to the inputs. An autoencoder is trained to attempt to copy its input to its output. Internally, it has a hidden layer which describes a code used to represent the input.



Autoencoder Components:

Autoencoders consist of 4 main parts:

- 1- Encoder: In this, the model learns how to reduce the input dimensions and compress the input data into an encoded representation.
- 2- Bottleneck: In this, the layer that contains the compressed representation of the input data. This is the lowest possible dimension of the input data.
- 3- Decoder: In this, the model learns how to reconstruct the data from the encoded representation to be as close to the original inputs as possible.
- 4- Reconstruction Loss: In this method that measures how well the decoder is performing and how close the output is related to the original input.

Types of Autoencoders :

1. Denoising auto encoder
2. Sparse auto encoder
3. Variational auto encoder (VAE)
4. Contractive auto encoder (CAE)

Q16: What is CNN?

This is the simple application of a filter to an input that results in inactivation. Repeated application of the same filter to input results in a map of activations called a feature map, indicating the locations and strength of a detected feature in input, such as an image.

Convolutional layers are the major building blocks which are used in convolutional neural networks.


A covnets is the sequence of layers, and every layer transforms one volume to another through differentiable functions.

Different types of layers in CNN:


Let's take an example by running a covnets on of image of dimensions **32 x 32 x 3**.

1. Input Layer: It holds the raw input of image with width 32, height 32 and depth 3.
2. Convolution Layer: It computes the output volume by computing dot products between all filters and image patches. Suppose we use a total of 12 filters for this layer we'll get output volume of dimension 32 x 32 x 12.
3. Activation Function Layer: This layer will apply the element-wise activation function to the output of the convolution layer. Some activation functions are RELU: $\max(0, x)$, Sigmoid: $1/(1+e^{-x})$, Tanh, Leaky RELU, etc. So the volume remains unchanged. Hence output volume will have dimensions 32 x 32 x 12.
4. Pool Layer: This layer is periodically inserted within the covnets, and its main function is to reduce the size of volume which makes the

computation fast reduces memory and also prevents overfitting. Two common types of pooling layers are max pooling and average pooling. If we use a max pool with 2×2 filters and stride 2, the resultant volume will be of dimension $16 \times 16 \times 12$.



- Fully-Connected Layer: This layer is a regular neural network layer that takes input from the previous layer and computes the class scores and outputs the 1-D array of size equal to the number of classes.




Q17: What is pooling, padding, filtering operations on CNN?


Pooling Layer

It is commonly used to periodically insert a Pooling layer in-between successive Conv layers in a ConvNet architecture. Its function is to progressively reduce the spatial size of the representation to reduce the number of parameters and computation in the network, and hence to also

control overfitting. The Pooling Layer operates independently on every depth slice of the input and resizes it spatially, using the MAX operation.




The most common form is a pooling layer with filters of size 2x2 applied with a stride of 2 downsamples every depth slice in the input by two along both width and height, discarding 75% of the activations. Every MAX operation would, in this case, be taking a max over four numbers (little 2x2 region in some depth slice). The depth dimension remains unchanged.



Q18: What is the Evolution technique of CNN?

It all started with LeNet in 1998 and eventually, after nearly 15 years, lead to groundbreaking models winning the ImageNet Large Scale Visual Recognition Challenge which includes AlexNet in 2012 to Google Net in 2014 to ResNet in 2015 to an ensemble of previous models in 2016. In the last two years, no significant progress has been made, and the new models are an ensemble of previous groundbreaking models.



LeNet in 1998

LeNet is a 7-level convolutional network by LeCun in 1998 that classifies digits and used by several banks to recognise the hand-written numbers on cheques digitised in 32x32 pixel greyscale input images.

AlexNet in 2012

AlexNet: It is considered to be the first paper/ model, which rose the interest in CNNs when it won the ImageNet challenge in the year 2012. It is a deep CNN trained on ImageNet and outperformed all the entries that year.

VGG in 2014

VGG was submitted in the year 2013, and it became a runner up in the ImageNet contest in 2014. It is widely used as a simple architecture compared to AlexNet.

GoogleNet in 2014

In 2014, several great models were developed like VGG, but the winner of the ImageNet contest was GoogleNet.

GoogLeNet proposed a module called the inception modules that includes skipping connections in the network, forming a mini-module, and this module is repeated throughout the network.

ResNet in 2015

There are 152 layers in the Microsoft ResNet. The authors showed empirically that if you keep on adding layers, the error rate should keep on decreasing in contrast to “plain nets” we’re adding a few layers resulted in higher training and test errors.

Q19: How to initialise biases in deep learning?

It is possible and common to initialise the biases to be zero since the random numbers in the weights provide the asymmetry breaking. For ReLU non-linearities, some people like to use small constant value such as 0.01 for all biases because this ensures that all ReLU units fire in the beginning, therefore obtain, and propagate some gradient. However, it is unclear if this provides a consistent improvement (in fact some results seem to indicate that this performs worst) and it is more commonly used to use 0 bias initialisation.

Q20: What is learning Rate?

Learning Rate

The learning rate controls how much we should adjust the weights concerning the loss gradient. Learning rates are randomly initialised.

Lower the values of the learning rate slower will be the convergence to global minima.

Higher values for the learning rate will not allow the gradient descent to converge

Since our goal is to minimise the function cost to find the optimised value for weights, we run multiples iteration with different weights and calculate the cost to arrive at a minimum cost

DATA SCIENCE INTERVIEW PREPARATION (30 Days of Interview Preparation) # Day-5

Q1: What are Epochs?

One Epoch is an ENTIRE dataset is passed forwards and backwards through the neural network

Since one epoch is too large to feed to the computer at once we divide it into several smaller batches

We always use more than one Epoch because ~~one epoch leads to underfitting~~

As the number of epochs increases several times the weight are changed in the neural network and the curve goes from underfitting up to optimal to overfitting curve

Q2. What is the batch size?

Batch Size

The total number of training and examples present in a single batch

Unlike the learning rate hyperparameter where its value doesn't affect computational time the batch sizes must be examined in conjunctions with the execution time of training. The batch size is limited by hardware's memory while the learning rate is not. Leslie recommends using a batch size that fits in hardware's memory and enables using larger learning rate.

If our server has multiple GPUs the total batch size is the batch size on a GPU multiplied by the numbers of GPU. If the architectures are small or your hardware permits very large batch sizes then you might compare the performance of different batch sizes. Also recall that small batch sizes add regularization while large batch sizes add less so utilize this while balancing the proper amount of regularization. It is often better to use large batch sizes so a larger learning rate can be used.

Q3: What is dropout in Neural network?

Dropout refers to ignoring units during the training phase of a certain set of neurons which is chosen randomly. These units are not considered during the particular forward or backward pass.

More technically at each training stage individual nodes are either dropped out of the net with probability $1-p$ or kept with probability p so that a reduced network is left; incoming and outgoing edges to a dropped-out node are also removed.

We need Dropout /~~Prevent overfitting~~

A dropout is an approach to regularization in neural networks which helps to reduce interdependent learning amongst the neurons

Where to use

Dropout is implemented per-layer in a neural network

It can be used with most types of layers such as dense fully connected layers convolutional layers and recurrent layers such as the long short-term memory network layer

Dropout may be implemented on any or all hidden layers in the network as well as the visible or input layer. It is not used on the output layer

Benefits:-

- 1 Dropout forces a neural network to learn more robust features that are very useful in conjunction with different random subsets of the other neurons
- 2 Dropout generally doubles the number of iterations required to converge. However the training time for each epoch is less

Q4: List down hyperparameter tuning in deep learning.

The process of setting the hyper-parameters requires expertise and extensive trial and error. There are no simple and easy ways to set hyper-parameters specifically learning rate batch size momentum and weight decay

Approaches to searching for the best configuration:

- Grid Search
- Random Search

Approach

- 1 Observe and understand the clues available during training by monitoring validation/test loss early in training tune your architecture and hyper-parameters with short runs of a few epochs
- 2 Signs of **underfitting** or **overfitting** of the test or validation loss early in the training process are useful for tuning the hyper-parameters.

Tools for Optimizing Hyperparameters

- Sage Maker
- Comet ml
- Weights & Biases
- Deep Cognition
- Azure ML

Q5: What do you understand by activation function and error functions?

Error functions

In most learning networks an error is calculated as the difference between the predicted output and the actual output

$$J(w) = p - \hat{p}$$

The function that is used to compute this error is known as Loss Function J) Different loss functions will give different errors for the same prediction and thus have a considerable effect on the performance of the model One of the most widely used loss function is mean square error which calculates the square of the difference between the actual values and predicted value Different loss functions are used to deals with a different type of tasks i e regression and classification.

Regressive loss functions:

Mean Square Error

Absolute error

Smooth Absolute Error

Classification loss functions:

- 1 Binary Cross-Entropy
- 2 Negative Log-Likelihood
- 3 Margin Classifier
- 4 Soft Margin Classifier

Activation functions decide whether a neuron should be activated or not by calculating a weighted sum and adding bias with it. The purpose of the activation function is to introduce non-linearity into the output of a neuron.

In a neural network we would update the weights and biases of the neurons based on the error at the outputs. This process is known as back-propagation. Activation function makes the back-propagation possible since the gradients are supplied along with the errors to update the weights and biases.

Q6: Why do we need Non-linear activation functions?

A neural network without activation functions is essentially a linear regression model. The activation functions do the non-linear transformation to the input making it capable of learning and performing more complex tasks.

- 1 Identity
- 2 Binary Step
- 3 Sigmoid
- 4 Tanh
- 5 ReLU
- 6 Leaky ReLU

7 Softmax

The activation functions do the non-linear transformation to the input making it capable of learning and performing more complex tasks


Q7: What do you understand by vanishing gradient problem and how can we solve that?

The problem:

As more layers using certain activation function are added to neural networks the gradients of the loss function approach zero making the networks tougher to train

Why:

Certain activation functions like the sigmoid function squishes a large input space into a small input space between 0 and 1. Therefore a large change in the input of the sigmoid function will cause a small change in the output. Hence the derivative becomes small.



For shallow networks with only a few layers that use these activations this isn't a big problem. However when more layers are used it can cause the gradient to be too small for training to work effectively.

However when n hidden layers use an activation like the sigmoid function small derivatives are multiplied together. Thus the gradient decreases exponentially as we propagate down to the initial layers.

Solutions:

The simplest solution is to use other activation functions such as ReLU which doesn't cause a small derivative

Residual networks are another solution as they provide residual connections straight to earlier layers

Finally batch normalization layers can also resolve the issue

Q8: What is Transfer learning in deep learning ?


Transfer learning: It is a machine learning method where a model is developed for the task is again used as the starting point for a model on a second task

It is a popular approach in deep learning where pre-trained models are used as the starting point on computer vision and natural language processing tasks given the vast compute and time resources required to develop neural network models on these problems

Transfer learning is a machine learning technique where a model trained on one task is re-purposed on a second related task


Transfer learning is an optimization that allows rapid progress or improved performance when modelling the second task

Transfer learning only works in deep learning if the model features learned from the first task are general



Q9: What is VGG16 and explain the architecture of VGG16?

VGG-16 is a simpler architecture model since it's not using many hyperparameters. It always uses 3×3 filters with the stride of 1 in convolution layer and uses SAME padding in pooling layers 2×2 with a stride of 2.



This architecture is from the VGG group Oxford. It improves AlexNet by replacing the large kernel-sized filter with multiple 3×3 kernel-sized filters one after another. With a given receptive field (the effective area size of input image on which output depends) multiple stacked smaller size kernel is better than the one with a larger size kernel because multiple non-linear layers increases the depth of the network which enables it to learn more complex features and that too at a lower cost.

Three fully connected layers follow the VGG convolutional layers. The width of the networks starts at the small value of 64 and increases by a factor of 2 after every sub-sampling/pooling layer. It achieves the top-5 accuracy of 92.3% on ImageNet.

Q10: What is RESNET?

The winner of ILSVRC 2015, it is also called as Residual Neural Network (ResNet) by Kaiming. This architecture introduced a concept called skip connections. Typically the input matrix calculates in two linear transformations with ReLU activation function. In Residual network, it directly copies the input matrix to the second transformation output and sums the output in final ReLU function.




Figure 2. Residual learning: a building block.

Experiments in paper four can judge the power of the residual network. The plain 34layer network had high validation error than the 18 layers plain network. This is where we realize the degradation problems. And the same 34 layers network when converted to the residual network has much less training error than the 18 layers residual network.

Q11: What is ImageNet?

ImageNet is a project aimed at (manually) labelling and categorizing images into almost 22 000 separate object categories for computer vision researches.

When we hear the about *ImageNet* in the context of deep learning and Convolutional Neural Network we are referring to **ImageNet Large Scale Visual Recognition Challenge**.

The main aim of this image classification challenge is to train the model that can correctly classify an input image into the 1 000 separate objects category.

Models are trained on the ~1 2 million training images with another 50 000 images for validation and 100 000 images for testing

These 1 000 image categories represent object classes that we encounter in our day-to-day lives such as species of dogs cats various household objects vehicle types and much more

When it comes to the image classification the ImageNet challenge is the de facto benchmark for computer vision classification algorithms and the leaderboard for this challenge has been dominated by Convolutional Neural Networks and Deep learning techniques since 2012



Q12: What is DarkNet?

DarkNet is a framework used to train neural networks; it is open source and written in C/CUDA and serves as the basis for YOLO. Darknet is also used as the framework for training YOLO meaning it sets the architecture of the network

Clone the repo locally and you have it To compile it run a make But first if you intend to use the GPU capability you need to edit the **Makefile** in the first two lines where you tell it to compile for GPU usage with CUDA drivers

Q13: What is YOLO and explain the architecture of YOLO (you only

Look Once). One use case?

YOLO v1

The first YOLO You only look once (YOLO) version came about May 2016 and sets the core of the algorithm the following versions are improvements that fix some drawbacks

In short YOLO is a network inspired by Google Net. It has **24** convolutional layers working as the feature extractors and two dense layers for making the predictions. The architecture works upon is called Darknet a neural network framework created by the first author of the YOLO paper.


Core Concept:-

The algorithm works off by dividing the image into the grid of the cells for each cell bounding boxes and their scores are predicted alongside class probabilities. The confidence is given in terms of IOU (*(Intersection over Union)*) metric which is measuring how much the detected object overlaps with the ground truth as a fraction of the total area spanned by the two together (the union).

YOLO v2

This improves on some of the shortcomings of the first version namely the fact that it is not very good at detecting objects that are very near and tends to make some of the mistakes on localization.

It introduces a few newer things: Which are **anchor boxes** (pre-determined sets of boxes such that the network moves from predicting the bounding boxes to predicting the offsets from these) and the use of features that are more fine-grained so smaller objects can be predicted better.



YOLO v3

YOLOv3 came about April 2018 and it adds small improvements including the fact that bounding boxes get predicted at the different scales. The underlying meaty part of the YOLO network Darknet is expanded in this version to have **53** convolutional layers.




**DATA SCIENCE
INTERVIEW
PREPARATION
(30 Days of Interview
Preparation)**

DAY 06

Q1. What is NLP?

Natural language processing NLP It is the branch of artificial intelligence that helps computers understand interpret and manipulate human language NLP draws from many disciplines including computer science and computational linguistics in its pursuit to fill the gap between human communication and computer understanding



Q2. What are the Libraries we used for NLP?

We usually use these libraries in NLP which are

NLTK Natural language Tool kit TextBlob CoreNLP Polyglot

Gensim SpaCy Scikit-learn

And the new one is Megatron library launched recently

Q3. What do you understand by tokenisation?

Tokenisation is the act of breaking a sequence of strings into pieces such as words keywords phrases symbols and other elements called tokens Tokens can be individual words phrases or even whole sentences In the process of tokenisation some characters like punctuation marks are discarded

Natural Language Processing

[Natural', 'Language', 'Processing']


Q4. What do you understand by stemming?

Stemming It is the process of reducing inflexions in words to their root forms such as mapping a group of words to the same stem even if stem itself is not a valid word in the Language

	words	stemmed words
0	connect	connect
1	connected	connect
2	connection	connect
3	connections	connect
4	connects	connect

Q5. What is lemmatisation?

Lemmatisation It is the process of grouping together the different inflected forms of the word so that they can be analysed as a single item. It is quite similar to stemming but it brings context to the words. So it links words with similar kind meaning to one word.



Q6. What is Bag-of-words model?

We need the way to represent text data for the machine learning algorithms and the bag-of-words model helps us to achieve the task. This model is very understandable and to implement. It is the way of extracting features from the text for the use in machine learning algorithms.

In this approach we use the tokenised words for each observation and find out the frequency of each token.

Let's do an example to understand this concept in depth.

It is going to rain today

Today I am not going outside

I am going to watch the season premiere

We treat each sentence as the separate document and we make the list of all words from all the three documents excluding the punctuation We get

It is going to rain today I am not outside watch the season premiere

The next step is the create vectors Vectors convert text that can be used by the machine learning algorithm

We take the first document “It is going to rain today”, and we check the frequency of words from the ten unique words

It =

is =

going =

to =

rain =

today =

I = 0

am = 0

not = 0

outside = 0

Rest of the documents will be

“It is going to rain today” = [1, 1, 1, 1, 1, 0, 0, 0, 0]

“Today I am not going outside” = [0, 0, 1, 0, 0, 1, 1, 1, 1]

“I am going to watch the season premiere” = [0, 0, 1, 1, 0, 0, 1, 1, 0, 0]

In this approach, each Word (a token) is called a “gram”. Creating the vocabulary of biWord pairs is called a bigram model.

The process of converting the NLP text into numbers is called **vectorisation** in ML. There are different ways to convert text into the vectors

- Counting the number of times that each Word appears in the document.
- I am calculating the frequency that each Word appears in a document out of all the Words in the document.

Q7.What do you understand by TF-IDF?

TF-IDF It stands for the term of frequency-inverse document frequency

TF-IDF weight It is a statistical measure used to evaluate how important a word is to a document in a collection or corpus. The importance increases proportionally to the number of times a word appears in the document but is offset by the frequency of the word in the corpus.

- **Term Frequency (TF)** is a scoring of the frequency of the word in the current document. Since every document is different in length it is possible that a term would appear much more times in long documents than shorter ones. The term frequency is often divided by the document length to normalise.

$$TF(t) = \frac{\text{Number of times term } t \text{ appears in a document}}{\text{Total number of terms in the document}}$$

- **Inverse Document Frequency (IDF)** It is a scoring of how rare the word is across the documents. It is a measure of how rare a term is. Rarer the term and more is the IDF score.

$$IDF(t) = \log_e\left(\frac{\text{Total number of documents}}{\text{Number of documents with term } t \text{ in it}}\right)$$

Thus

$$TF - IDF \text{ score} = TF * IDF$$

Q8. What is Word2vec?

Word2Vec is a shallow two-layer neural network which is trained to reconstruct linguistic contexts of words. It takes as its input a large corpus of words and produces a vector space typically of several hundred dimensions with each unique word in the corpus being assigned to the corresponding vector in space.

Word vectors are positioned in a vector space such that words which share common contexts in the corpus are located close to one another in the space.

Word2Vec is a particularly computationally-efficient predictive model for learning word embeddings from raw text.

Word2Vec is a group of models which helps derive relations between a word and its contextual words. Let's look at two important models inside Word2Vec Skip-grams and CBOW.

Skip-grams

Source Text	Training Samples
The quick brown fox jumps over the lazy dog.	(the, quick) (the, brown)
The quick brown fox jumps over the lazy dog.	(quick, the) (quick, brown) (quick, fox)
The quick brown fox jumps over the lazy dog.	(brown, the) (brown, quick) (brown, fox) (brown, jumps)
The quick brown fox jumps over the lazy dog.	(fox, quick) (fox, brown) (fox, jumps) (fox, over)

In Skip-gram model we take a centre word and a window of context neighbour words and we try to predict the context of words out to some window size for each centre word. So our model is going to define a probability distribution i.e. probability of a word appearing in the context given a centre word and we are going to choose our vector representations to maximise the probability.

Continuous Bag-of-Words (CBOW)

CBOW predicts target words e.g. mat from the surrounding context words the cat sits on the.

Statistically it affects that CBOW smoothes over a lot of distributional information by treating an entire context as one observation. For the most part this turns out to be a useful thing for smaller datasets.

1. I enjoy flying.
2. I like NLP.
3. I like deep learning.

The resulting counts matrix will then be:

$$X = \begin{matrix} & \begin{matrix} I & like & enjoy & deep & learning & NLP & flying & . \end{matrix} \\ \begin{matrix} I \\ like \\ enjoy \\ deep \\ learning \\ NLP \\ flying \\ . \end{matrix} & \left[\begin{matrix} 0 & 2 & 1 & 0 & 0 & 0 & 0 & 0 \\ 2 & 0 & 0 & 1 & 0 & 1 & 0 & 0 \\ 1 & 0 & 0 & 0 & 0 & 0 & 1 & 0 \\ 0 & 1 & 0 & 0 & 1 & 0 & 0 & 0 \\ 0 & 0 & 0 & 1 & 0 & 0 & 0 & 1 \\ 0 & 1 & 0 & 0 & 0 & 0 & 0 & 1 \\ 0 & 0 & 1 & 0 & 0 & 0 & 0 & 1 \\ 0 & 0 & 0 & 0 & 1 & 1 & 1 & 0 \end{matrix} \right] \end{matrix}$$

This was about converting words into vectors. But where does the learning happen? Essentially we begin with small random initialisation of word vectors. Our predictive model learns the vectors by minimising the loss function. In Word2vec this happens with feed-forward neural networks and optimisation techniques such as Stochastic gradient descent. There are also count-based models which make the co-occurrence count matrix of the words in our corpus; we have a very large matrix with each row for the words and columns for the context. The number of contexts is of course very large since it is very essentially combinatorial in size. To overcome this issue we apply SVD to a matrix. This reduces the dimensions of the matrix to retain maximum pieces of information.

Q9. What is Doc2vec?

Paragraph Vector more popularly known as **Doc2Vec** Distributed Memory **PV-D**


Paragraph Vector Doc2Vec is supposed to be an extension to Word2Vec such that *Word2Vec learns to project words into a latent d-dimensional space* whereas *Doc2Vec aims at learning how to project a document into a latent d-dimensional space*

The basic idea behind PV-DM is inspired by Word2Vec. In CBOW model of Word2Vec the model learns to predict a centre word based on the contexts. For example- given a sentence "The cat sat on the table" CBOW model would learn to predict the words "sat" given the context words "the cat" and "on" and "table". Similarly in PV-DM the main idea is randomly sample consecutive words from the paragraph and ***predict a centre word*** from the randomly sampled set of words by taking as the ***input the context words and the paragraph id***.

Let's have a look at the model diagram for some more clarity. In this given model we see Paragraph matrix Average/Concatenate and classifier sections.

Paragraph matrix It is the matrix where each column represents the vector of a paragraph.
Average/Concatenate It means that whether the word vectors and paragraph vector are averaged or concatenated.

Classifier In this it takes the hidden layer vector the one that was concatenated/averaged as input and predicts the Centre word.



In the matrix D It has the embeddings for seen paragraphs i.e arbitrary length documents the same way Word2Vec models learns embeddings for words For unseen paragraphs the model is again run through gradient descent 5 or so iterations to infer a document vector

Q9. What is Time-Series forecasting?

Time series forecasting is a technique for the prediction of events through a sequence of time. The technique is used across many fields of study from the geology to behaviour to economics. The techniques predict future events by analysing the trends of the past on the assumption that future trends will hold similar to historical trends.

Q10. What is the difference between in Time series and regression?

Time-series


- 1 Whenever data is recorded at regular intervals of time
- 2 Time-series forecast is Extrapolation
- 3 Time-series refers to an ordered series of data

Regression

- Whereas in regression whether data is recorded at regular or irregular intervals of time we can apply
- 2 Regression is Interpolation
- 3 Regression refer both ordered and unordered series of data


Q11. What is the difference between stationary and non-stationary data?

Stationary: A series is said to be "STRICTLY STATIONARY" if the Mean Variance & Covariance is constant over some time or time-invariant



Non-Stationary:

A series is said to be "STRICTLY STATIONARY" if the Mean Variance & Covariance is not constant over some time or time-invariant



Q12. Why you cannot take non-stationary data to solve time series Problem?

- Most models assume stationary of data In other words standard techniques are invalid if data is "NON-STATIONARY"
 - Autocorrelation may result due to "NON-STATIONARY"
 - Non-stationary processes are a random walk with or without a drift a slow steady change
 - Deterministic trends trends that are constant positive or negative independent of time for the whole life of the series
-

**DATA SCIENCE
INTERVIEW
PREPARATION
(30 Days of Interview
Preparation)**

DAY 07

Q1. What is the process to make data stationary from non-stationary in time series?**Ans:**

The two most common ways to make a non-stationary time series stationary are:

- **Differencing**
- **Transforming**

Let us look at some details for each of them:

Differencing:


To make your series stationary, you take a difference between the data points So let us say, your original time series was:

$X_1, X_2, X_3, \dots, X_n$

Your series with a difference of degree 1 becomes:


$(X_2 - X_1, X_3 - X_2, X_4 - X_3, \dots, X_n - X_{n-1})$

Once, you make the difference, plot the series and see if there is any improvement in the ACF curve If not, you can try a second or even a third-order differencing Remember, the more you difference, the more complicated your analysis is becoming



Transforming:


If we cannot make a time series stationary, you can try out transforming the variables Log transform is probably the most commonly used transformation if we see the diverging time series However, it is suggested that you use transformation only in case differencing is not working



Q2. What is the process to check stationary data ?

Ans:

Stationary series: It is one in which the properties mean, variance and covariance, do not vary with time




Let us get an idea with these three plots:

- In the first plot, we can see that the mean varies (increases) with time, which results in an upward trend This is the non-stationary series
For the series classification as stationary, it should not exhibit the trend
- Moving on to the second plot, we do not see a trend in the series, but the variance of the series is a function of time As mentioned previously, a stationary series must have a constant variance

- If we look at the third plot, the spread becomes closer, as the time increases, which implies that covariance is a function of time

These three plots refer to the non-stationary time series Now give your attention to fourth:



In this case, Mean, Variance and Covariance are constant with time This is how a stationary time series looks like

Most of the statistical models require the series to be stationary to make an effective and precise prediction

The various process you can use to find out your data is stationary or not by the following terms:

- 1 Visual Test
- 2 Statistical Test
- 3 ADF(Augmented Dickey-Fuller) Test
- 4 KPSS(Kwiatkowski-Phillips-Schmidt-Shin) Test


Q3. What are ACF and PACF?.

Ans:

ACF is a (complete) auto-correlation function which gives us the values of the auto-correlation of any series with lagged values We plot these values along with a confidence band We have an ACF plot In simple terms, it describes how well the present value of the series is related to its past values A time series can have components like the trend, seasonality, cyclic and residual ACF considers all the components while finding correlations; hence, it's a complete auto-correlation plot

PACF is a partial autocorrelation function Instead of finding correlations of present with lags like ACF, it finds the correlations of the residuals with the next lag value thus partial and not complete as we remove already found variations before we find next correlation So if there are any hidden pieces of information in the residual which can be modelled by next lag, we might get a good correlation, and we'll keep that next lag as a feature while modelling Remember, while

modelling we don't want to keep too many correlated features, as that it can create multicollinearity issues. Hence we need to retain only relevant features.




Q4. What do you understand by the trend of data?


Ans:

A general systematic linear or (most often) nonlinear component that changes over time and does not repeat

There are different approaches to understanding trend. A positive trend means it is likely that growth continues. Let's illustrate this with a simple example:



Hmm, this looks like there is a trend. To build up confidence, let's add a linear regression for this graph:



Great, now it's clear there's a trend in the graph by adding Linear Regression

Q5. What is the Augmented Dickey-Fuller Test?


Ans:

The Dickey-Fuller test: It is one of the most popular statistical tests. It is used to determine the presence of unit root in a series, and hence help us to understand if the series is stationary or not. The null and alternate hypothesis for this test is:

Null Hypothesis: The series has a unit root (value of $\alpha = 1$)

Alternate Hypothesis: The series has no unit root

If we fail to reject the null hypothesis, we can say that the series is non-stationary. This means that the series can be linear or difference stationary.



Q6. What is AIC and BIC into time series?

Ans:

Akaike's information criterion (AIC) compares the quality of a set of statistical models to each other. For example, you might be interested in what variables contribute to low socioeconomic status and how the variables contribute to that status. Let's say you create several regression models for various factors like education, family size, or disability status; The AIC will take each model and rank them from best to worst. The best model will be the one that neither under-fits nor over-fits.

-
- AIC
 - K = number of estimated parameters in the model
 - L = Maximized likelihood function for the estimated model

$$AIC = 2k - 2 \ln(L)$$

The Bayesian Information Criterion (BIC) can be defined as:

$$k \log(n) - 2\log(\hat{L}(\hat{\theta}))$$

Here n is the sample size

K is the number of parameters which your model estimates

is the set of all parameter

$\hat{L}(\cdot)$ represents the likelihood of the model tested, when evaluated at maximum likelihood values of

Q7. What are the components of the Time -Series?

Ans:

Time series analysis: It provides a body of techniques to understand a dataset better. The most useful one is the decomposition of the time series into four constituent parts-

- 1 Level- The baseline value for the series if it were a straight line
- 2 Trend - The optional and linear, increasing or decreasing behaviour of series over time
- 3 Seasonality - Optional repeated patterns /cycles of behaviour over time
- 4 Noise - The optional variability in the observations that cannot be explained by the model

Q8. What is Time Series Analysis?

Ans:

Time series analysis: It involves developing models that best capture or describe an observed time series to understand the underlying cause. This study seeks the "why" behind the time-series datasets. This involves making assumptions about the form of data and decomposing time-series into the constitution component

Quality of descriptive model is determined by how well it describes all available data and the interpretation it provides to inform the problem domain better

Q9. Give some examples of the Time-Series forecast?**Ans:**

There is almost an endless supply of the time series forecasting problems. Below are ten examples from a range of industries to make the notions of time series analysis and forecasting more concrete.

- 1 Forecasting the corn yield in tons by the state each year
- 2 Forecasting whether an EEG trace in seconds indicates a patient is having a seizure or not
- 3 Forecasting the closing price of stocks every day
- 4 Forecasting the birth rates at all hospitals in the city every year
- 5 Forecasting product sales in the units sold each day for the store
- 6 Forecasting the number of passengers through the train station each day
- 7 Forecasting unemployment for a state each quarter
- 8 Forecasting the utilisation demand on the server every hour
- 9 Forecasting the size of the rabbit populations in the state each breeding season
- 10 Forecasting the average price of gasoline in a city each day

Q10. What are the techniques of Forecasting?**Ans:**

There are so many statistical techniques available for time series forecast however we have found a few effective ones which are listed below:


- Simple Moving Average (SMA)
- Exponential Smoothing (SES)
- Autoregressive Integration Moving Average (ARIMA)

Q11. What is the Moving Average?**Ans:**

The moving average model is probably the most naive approach to time series modelling. This model states that the next observation is the mean of all past observations.

Although simple, this model might be surprisingly good, and it represents a good starting point.

Otherwise, the moving average can be used to identify interesting trends in the data. We can define a window to apply the moving average model to smooth the time series and highlight different trends.




Example of a moving average on a 24h window

In the plot above, we applied the moving average model to a 24h window. The green line smoothed the time series, and we can see that there are two peaks in the 24h period.

The longer the window, the smoother the trend will be

Below is an example of moving average on a smaller window



Example of a moving average on a 12h window


Q12. What is Exponential smoothing?**Ans:**

Exponential smoothing uses similar logic to moving average, but this time, different decreasing weight is assigned to each observation. We can also say, less importance is given to the observations as we move further from the present.

Mathematically, exponential smoothing is expressed as:

$$y = \alpha x_t + (1 - \alpha)y_{t-1}, t > 0$$

Here, alpha is the smoothing factor which takes values between 0 to 1. It determines how fast the weight will decrease for the previous observations.



From the above plot, the dark blue line represents the exponential smoothing of the time series using a smoothing factor of 0.3, and the orange line uses a smoothing factor of 0.05. As we can see, the smaller the smoothing factor, the smoother the time series will be. Because as smoothing factor approaches 0, we approach to the moving average model.

**DATA SCIENCE
INTERVIEW
PREPARATION
(30 Days of Interview
Preparation)**

DAY 08

Q1. What is Tensorflow?

Ans:

TensorFlow: TensorFlow is an open-source software library released in 2015 by Google to make it easier for the developers to design, build, and train deep learning models. TensorFlow originated as an internal library that the Google developers used to build the models in house, and we expect additional functionality to be added in the open-source version as they are tested and vetted in internal flavour. Although TensorFlow is the only one of several options available to the developers and we choose to use it here because of thoughtful design and ease of use.

At a high level, TensorFlow is a Python library that allows users to express arbitrary computation as a graph of *data flows*. Nodes in this graph represent mathematical operations, whereas edges represent data that is communicated from one node to another. Data in TensorFlow are represented as tensors, which are multidimensional arrays. Although this framework for thinking about computation is valuable in many different fields, TensorFlow is primarily used for deep learning in practice and research.

TensorFlow 2.0




Q2. What are Tensors?

Ans:

Tensor: In mathematics, it is an algebraic object that describes the linear mapping from one set of algebraic objects to the another. Objects that the tensors may map between include, but are not limited to the vectors, scalars and recursively, even other tensors (for example, a matrix is the map between vectors and thus a tensor. Therefore the linear map between matrices is also the tensor). Tensors are inherently related to the vector spaces and their dual spaces and can take several different forms. For


example, a scalar, a vector, a dual vector at a point, or a multi-linear map between vector spaces. Euclidean vectors and scalars are simple tensors. While tensors are defined as independent of any basis. The literature on physics, often referred by their components on a basis related to a particular coordinate system.



Q3. What is TensorBoard?

Ans:

TensorBoard, a suite of visualising tools, is an easy solution to Tensorflow offered by the creators that lets you visualise the graphs, plot quantitative metrics about the graph with additional data like images to pass through it.



This one is some example of how the TensorBoard is working.

Q4. What are the features of TensorFlow?

Ans:

- One of the main features of TensorFlow is its ability to build neural networks.
- By using these neural networks, machines can perform logical thinking and learn similar to humans.
- There are other tensors for processing, such as data loading, preprocessing, calculation, state and outputs.
- It is considered not only as deep learning but also as the library for performing tensor calculations, and it is the most excellent library when considered as the deep learning framework that can also describe basic calculation processing.
- TensorFlow describes all calculation processes by calculation graph, no matter how simple the calculation is.

Q5. What are the advantages of TensorFlow?

Ans:

- It allows Deep Learning.
- It is open-source and free.
- It is reliable (and without major bugs)
- It is backed by Google and a good community.
- It is a skill recognised by many employers.
- It is easy to implement.

Q6. List a few limitations of Tensorflow.

Ans:

- Has the GPU memory conflicts with Theano if imported in the same scope.
- It has dependencies with other libraries.
- Requires prior knowledge of the advanced calculus and linear algebra along with the pretty good understanding of machine learning.

Q7. What are the use cases of Tensorflow?

Ans:

Tensorflow is an important tool of deep learning, it has mainly five use cases, and they are:

- Time Series
- Image recognition
- Sound Recognition
- Video detection
- Text-based Applications

Q8. What are the very important steps of Tensorflow architecture?

Ans:

There are three main steps in the Tensorflow architecture are:

- Pre-process the Data
- Build a Model
- Train and estimate the model





Image Recognition

Classification using Softmax Regressions and Convolutional Neural Networks

Q9. What is Keras?

Ans:


Keras: It is an Open Source Neural Network library written in Python that runs on the top of Theano or Tensorflow. It is designed to be the modular, fast and easy to use. It was developed by François Chollet, a Google engineer.



Q10. What is a pooling layer?

Ans:

Pooling layer: It is generally used in reducing the spatial dimensions and not depth, on a convolutional neural network model.



Q11. What is the difference between CNN and RNN?

Ans:

CNN (Convolutional Neural Network)

- Best suited for spatial data like images
- CNN is powerful compared to RNN
- This network takes a fixed type of inputs and outputs
- These are the ideal for video and image processing

RNN (Recurrent Neural Network)

- Best suited for sequential data
- RNN supports less feature set than CNN.
- This network can manage the arbitrary input and output lengths.
- It is ideal for text and speech analysis.

Q12. What are the benefits of Tensorflow over other libraries?

Ans:

The following benefits are:

- Scalability
 - Visualisation of Data
 - Debugging facility
 - Pipelining
-

**DATA SCIENCE
INTERVIEW
PREPARATION
(30 Days of Interview
Preparation)**


DAY 09

Q1: How would you define Machine Learning?

Ans:

Machine learning: It is an application of artificial intelligence (AI) that provides systems the ability to learn automatically and to improve from experiences without being programmed. It focuses on the development of computer applications that can access the data and use it to learn for themselves.


The process of learning starts with the observations or data such as examples, direct experience or instruction to look for the patterns in data and to make better decisions in the future based on examples that we provide. The primary aim is to allow the computers to learn automatically without human intervention or assistance and adjust actions accordingly.



Q2. What is a labeled training set?

Ans:

Machine learning is derived from the availability of the labeled data in the form of a **training set** and **test set** that is used by the learning algorithm. The separation of data into the training portion and a test portion is the way the algorithm learns. We split up the data containing known response variable values into two pieces. The training set is used to train the algorithm and then you use the trained model on the test set to predict the variable response values that are already known. The final step is to compare with the predicted responses against actual (observed) responses to see how close they are. The difference is the test error metric. Depending on the test error, you can go back to refine the model and repeat the process until you're satisfied with the accuracy.




Q3. What are the two common supervised tasks?

Ans:

The two common supervised tasks are regression and classification


Regression-

The regression problem is when the output variable is the real or continuous value such as salary or weight. Many different models can be used and the simplest is linear regression. It tries to fit the data with the best hyper-plane which goes through the points.



Classification

It is the type of supervised learning. It specifies the class to which the data elements belong to and is best used when the output has finite and discrete values. It predicts a class for an input variable as well.




Q4. Can you name four common unsupervised tasks?

Ans:

The common unsupervised tasks include clustering, visualization, dimensionality reduction, and association rule learning.


Clustering

It is a Machine Learning technique that involves the grouping of the data points. Given a set of data points and we can use a clustering algorithm to classify each data point into the specific group. In theory, data points that lie in the same group should have similar properties and/or features and data points in the different groups should have high dissimilar properties and/or features. Clustering is the method of unsupervised learning and is a common technique for statistical data analysis used in many fields.



Visualization

Data visualization is the technique that uses an array of static and interactive visuals within the specific context to help people to understand and make sense of the large amounts of data. The data is often displayed in the story format that visualizes patterns, trends, and correlations that may go otherwise unnoticed. It is regularly used as an avenue to monetize data as the product. An example of using monetization and data visualization is Uber. The app combines visualization with real-time data so that customers can request a ride.



Q5. What type of Machine Learning algorithm we use to allow a robot to walk in various unknown terrains?


Ans:

Reinforcement Learning is likely to perform the best if we want a robot to learn how to walk in the various unknown terrains since this is typically the type of problem that the reinforcement learning

tackles It may be possible to express the problem as a supervised or semisupervised learning problem but it would be less natural

Reinforcement Learning-

It's about to take suitable actions to maximize rewards in a particular situation. It is employed by the various software and machines to find out the best possible behavior/path it should take in specific situations. Reinforcement learning is different from the supervised learning in a way that in supervised learning training data has answer key with it so that the model is trained with the correct answer itself but in reinforcement learning there is no answer and the reinforcement agent decides what to do to perform the given task. In the absence of the training dataset it is bound to learn from its experience.



Q6. What type of algorithm would we use to segment your customers into multiple groups?

Ans:


If we don't know how to define the groups then we can use the clustering algorithm (unsupervised learning) to segment our customers into clusters of similar customers. However if we know what groups we would like to have then we can feed many examples of each group to a classification algorithm (supervised learning) and it will classify all your customers into these groups.

Q7: What is an online machine learning?

Ans:

Online machine learning: It is a method of machine learning in which data becomes available in sequential order and to update our best predictor for the future data at each step as opposed to batch learning techniques that generate the best predictor by learning on entire training data set at once. Online learning is a common technique and used in the areas of machine learning where it is computationally infeasible to train over the datasets requiring the need for Out-of-Core algorithms. It is also used in situations where the algorithm must adapt to new patterns in the data dynamically or when the data itself is generated as the function of time for example stock

price prediction Online learning algorithms might be prone to catastrophic interference and problem that can be addressed by the incremental learning approaches




Q8: What is out-of-core learning?

Ans:

Out-of-core: It refers to the processing data that is too large to fit into the computer's main memory. Typically, when the dataset fits neatly into the computer's main memory, randomly accessing sections of data has a (relatively) small performance penalty.

When data must be stored in a medium like a large spinning hard drive or an external computer network, it becomes very expensive to seek an arbitrary section of data randomly or to process the same data multiple times. In such a case, an out-of-core algorithm will try to access all the relevant data in a sequence.

However, modern computers have deep memory hierarchy, and replacing random access with the sequential access can increase the performance even on datasets that fit within memory.



Q9. What is the Model Parameter?

Ans:

Model parameter: It is a configuration variable that is internal to a model and whose value can be predicted from the data

- While making predictions the model parameter is needed
- The values define the skill of a model on problems
- It is estimated or learned from data
- It is often not set manually by the practitioner
- It is often saved as part of the learned model

Parameters are key to machine learning algorithms. They are part of the model that is learned from historical training data.


Q11: What is Model Hyperparameter?

Ans:

Model hyperparameter: It is a configuration that is external to a model and whose values cannot be estimated from the data

- It is often used in processes to help estimate model parameters
- The practitioner often specifies them
- It can often be set using heuristics
- It is tuned for the given predictive modeling problems

We cannot know the best value for the model hyperparameter on the given problem. We may use the rules of thumb, copy values used on other problems, or search for the best value by trial and error.



Q12. What is cross-validation?


Ans:

Cross-validation: It is a technique for evaluating Machine Learning models by training several Machine Learning models on subsets of available input data and evaluating them on the complementary subset of data. Use cross-validation to detect overfitting, i.e., failing to generalize a pattern.

There are three steps involved in cross-validation as follows :

- Reserve some portion of the sample dataset

- Using the rest dataset and train models
- Test the model using a reserve portion of the data-set




DATA SCIENCE INTERVIEW PREPARATION (30 Days of Interview Preparation)

DAY 10

Q1. What is a Recommender System?

Answer:

A recommender system is today widely deployed in multiple fields like movie recommendations music preferences social tags research articles search queries and so on. The recommender systems work as per collaborative and content-based filtering or by deploying a personality-based approach. This type of system works based on a person's past behavior in order to build a model for the future. This will predict the future product buying movie viewing or book reading by people. It also creates a filtering approach using the discrete characteristics of items while recommending additional items.




Q2. Compare SAS, R and Python programming?

Answer:

SAS: it is one of the most widely used analytics tools used by some of the biggest companies on earth. It has some of the best statistical functions graphical user interface but can come with a price tag and hence it cannot be readily adopted by smaller enterprises.

R: The best part about R is that it is an Open Source tool and hence used generously by academia and the research community. It is a robust tool for statistical computation, graphical representation and reporting. Due to its open source nature it is always being updated with the latest features and then readily available to everybody.

Python: Python is a powerful open source programming language that is easy to learn, works well with most other tools and technologies. The best part about Python is that it has innumerable libraries and community created modules making it very robust. It has functions for statistical operation, model building and more.



Q3. Why is important in data analysis?

Answer:

With data coming in from multiple sources it is important to ensure that data is good enough for analysis. This is where data cleansing becomes extremely vital. Data cleansing extensively deals with the process of detecting and correcting of data records ensuring that data is complete and accurate and the components of data that are irrelevant are deleted or modified as per the needs. This process can be deployed in concurrence with data wrangling or batch processing.

Once the data is cleaned it confirms with the rules of the data sets in the system. Data cleansing is an essential part of the data science because the data can be prone to error due to human negligence or corruption during transmission or storage among other things. Data cleansing takes a huge chunk of time and effort of a Data Scientist because of the multiple sources from which data emanates and the speed at which it comes.



Q4. What are the various aspects of a Machine Learning process?

Answer:

Here we will discuss the components involved in solving a problem using machine learning

Domain knowledge

This is the first step wherein we need to understand how to extract the various features from the data and learn more about the data that we are dealing with. It has got more to do with the type of domain that we are dealing with and familiarizing the system to learn more about it.

Feature Selection

This step has got more to do with the feature that we are selecting from the set of features that we have. Sometimes it happens that there are a lot of features and we have to make an intelligent decision regarding the type of feature that we want to select to go ahead with our machine learning endeavor.

Algorithm

This is a vital step since the algorithms that we choose will have a very major impact on the entire process of machine learning. You can choose between the linear and nonlinear algorithm. Some of the algorithms used are Support Vector Machines, Decision Trees, Naïve Bayes, K-Means Clustering, etc.

Training

This is the most important part of the machine learning technique and this is where it differs from the traditional programming. The training is done based on the data that we have and providing more real world experiences. With each consequent training step the machine gets better and smarter and able to take improved decisions.

Evaluation

In this step we actually evaluate the decisions taken by the machine in order to decide whether it is up to the mark or not. There are various metrics that are involved in this process and we have to closed deploy each of these to decide on the efficacy of the whole machine learning endeavor.


Optimization

This process involves improving the performance of the machine learning process using various optimization techniques. Optimization of machine learning is one of the most vital components wherein the performance of the algorithm is vastly improved. The best part of optimization techniques is that machine learning is not just a consumer of optimization techniques but it also provides new ideas for optimization too.

Testing

Here various tests are carried out and some these are unseen set of test cases. The data is partitioned into test and training set. There are various testing techniques like cross-validation in order to deal with multiple situations.

The Machine Learning Process




Q4. What is Interpolation and Extrapolation?

Answer:

The terms of interpolation and extrapolation are extremely important in any statistical analysis. Extrapolation is the determination or estimation using a known set of values or facts by extending it and taking it to an area or region that is unknown. It is the technique of inferring something using data that is available.

Interpolation on the other hand is the method of determining a certain value which falls between a certain set of values or the sequence of values. This is especially useful when you have data at the two extremities of a certain region but you don't have enough data points at the specific point. This is when you deploy interpolation to determine the value that you need.




Q5. What does P-value signify about the statistical data?

Answer:

P-value is used to determine the significance of results after a hypothesis test in statistics. P-value helps the readers to draw conclusions and is always between 0 and 1.

- P-Value > 0.05 denotes weak evidence against the null hypothesis which means the null hypothesis cannot be rejected.
- P-value <= 0.05 denotes strong evidence against the null hypothesis which means the null hypothesis can be rejected.
- P-value = 0.05 is the marginal value indicating it is possible to go either way.



Q6. During analysis, how do you treat missing values?

Answer:

The extent of the missing values is identified after identifying the variables with missing values. If any patterns are identified the analyst has to concentrate on them as it could lead to interesting and meaningful business insights. If there are no patterns identified then the missing values can be substituted with mean or median values (imputation) or they can simply be ignored.

There are various factors to be considered when answering this question-

Understand the problem statement understand the data and then give the answer Assigning a default value which can be mean minimum or maximum value Getting into the data is important

If it is a categorical variable the default value is assigned The missing value is assigned a default value

If you have a distribution of data coming for normal distribution give the mean value

Should we even treat missing values is another important point to consider? If 80% of the values for a variable are missing then you can answer that you would be dropping the variable instead of treating the missing values

Q7. Explain the difference between a Test Set and a Validation Set?

Answer:

Validation set can be considered as a part of the training set as it is used for parameter selection and to avoid Overfitting of the model being built On the other hand test set is used for testing or evaluating the performance of a trained machine learning model

In simple terms the differences can be summarized as-

Training Set is to fit the parameters i e weights

Test Set is to assess the performance of the model i e evaluating the predictive power and generalization

Validation set is to tune the parameters




Q8. What is the curse of dimensionality? Can you list some ways to deal with it?

Answer:

The curse of dimensionality is when the training data has a high feature count but the dataset does not have enough samples for a model to learn correctly from so many features. For example a training dataset of 100 samples with 100 features will be very hard to learn from because the model will find random relations between the features and the target. However if we had a dataset of 100k samples with 100 features the model could probably learn the correct relationships between the features and the target.

There are different options to fight the curse of dimensionality:

- **Feature selection.** Instead of using all the features we can train on a smaller subset of features
- **Dimensionality reduction.** There are many techniques that allow to reduce the dimensionality of the features. Principal component analysis (PCA) and using autoencoders are examples of dimensionality reduction techniques
- **L1 regularization.** Because it produces sparse parameters L1 helps to deal with high-dimensionality input
- **Feature engineering.** It's possible to create new features that sum up multiple existing features. For example we can get statistics such as the mean or median.



Q9. What is data augmentation? Can you give some examples?


Answer:

Data augmentation is a technique for synthesizing new data by modifying existing data in such a way that the target is not changed or it is changed in a known way

Computer vision is one of fields where data augmentation is very useful. There are many modifications that we can do to images:

- Resize
- Horizontal or vertical flip
- Rotate
- Add noise
- Deform
- Modify colors

Each problem needs a customized data augmentation pipeline. For example on OCR doing flips will change the text and won't be beneficial; however resizes and small rotations may help



Q10. What is stratified cross-validation and when should we use it?

Answer:

Cross-validation is a technique for dividing data between training and validation sets. On typical cross-validation this split is done randomly. But in *stratified* cross-validation the split preserves the ratio of the categories on both the training and validation datasets

For example if we have a dataset with 10% of category A and 90% of category B and we use stratified cross-validation we will have the same proportions in training and validation. In contrast if we use simple cross-validation in the worst case we may find that there are no samples of category A in the validation set.

Stratified cross-validation may be applied in the following scenarios:

- **On a dataset with multiple categories.** The smaller the dataset and the more imbalanced the categories the more important it will be to use stratified cross-validation
- **On a dataset with data of different distributions.** For example in a dataset for autonomous driving we may have images taken during the day and at night. If we do not ensure that both types are present in training and validation we will have generalization problems



**DATA SCIENCE
INTERVIEW PREPARATION
(30 Days of Interview
Preparation)**


DAY 11

Q1. What are tensors?

Answer:

The tensors are no more than a method of presenting the data in deep learning. If put in the simple term, tensors are just multidimensional arrays that allow developers to represent the data in a layer, which means deep learning you are using contains high-level data sets where each dimension represents a different feature.


The foremost benefit of using tensors is it provides the much-needed platform-flexibility and is easy to trainable on CPU. Apart from this, tensors have the auto differentiation capabilities, advanced support system for queues, threads, and asynchronous computation. All these features also make it customizable.



Q2. Define the concept of RNN?

Answer:


RNN is the artificial neural which were created to analyze and recognize the patterns in the sequences of the data. Due to their internal memory, **RNN** can certainly remember the things about the inputs they receive.



Most common issues faced with RNN

Although RNN is around for a while and uses backpropagation, there are some common issues faced by developers who work it. Out of all, some of the most common issues are:

- Exploding gradients
- Vanishing gradients



Q3. What is a ResNet, and where would you use it? Is it efficient?


Answer:

Among the various neural networks that are used for computer vision, ResNet (Residual Neural Networks), is one of the most popular ones. It allows us to train extremely deep neural networks, which is the prime reason for its huge usage and popularity. Before the invention of this network, training extremely deep neural networks was almost impossible.

To understand why we must look at the vanishing gradient problem which is an issue that arises when the gradient is backpropagated to all the layers. As a large number of multiplications are performed, the size of the network keeps decreasing till it becomes extremely small, and thus, the network starts performing badly. ResNet helps to counter the vanishing gradient problem.

The efficiency of this network is highly dependent on the concept of skip connections. Skip connections are a method of allowing a shortcut path through which the gradient can flow, which in effect helps counter the vanishing gradient problem.

An example of a skip connection is shown below:



In general, a skip connection allows us to skip the training of a few layers. Skip connections are also called identity shortcut connections as they allow us to directly compute an identity function by just relying on these connections and not having to look at the whole network.

The skipping of these layers makes ResNet an extremely efficient network.

Q4. Transfer learning is one of the most useful concepts today. Where can it be used?

Answer:

Pre-trained models are probably one of the most common use cases for transfer learning

For anyone who does not have access to huge computational power, training complex models is always a challenge. Transfer learning aims to help by both improving the performance and speeding up your network.

In layman terms, transfer learning is a technique in which a model that has already been trained to do one task is used for another without much change. This type of learning is also called multi-task learning.

Many models that are pre-trained are available online. Any of these models can be used as a starting point in the creation of the new model required. After just using the weights, the model must be refined and adapted on the required data by tuning the parameters of the model.

Model name	Speed (ms)	COCO mAP[^1]	Outputs
ssd_mobilenet_v1_coco	30	21	Boxes
ssd_mobilenet_v1_0.75_depth_coco ☆	26	18	Boxes
ssd_mobilenet_v1_quantized_coco ☆	29	18	Boxes
ssd_mobilenet_v1_0.75_depth_quantized_coco ☆	29	16	Boxes
<u>ssd_mobilenet_v1_ppn_coco ☆</u>	26	20	Boxes
ssd_mobilenet_v1_fpn_coco ☆	56	32	Boxes
ssd_resnet_50_fpn_coco ☆	76	35	Boxes
ssd_mobilenet_v2_coco	31	22	Boxes
ssd_mobilenet_v2_quantized_coco	29	22	Boxes
ssdlite_mobilenet_v2_coco	27	22	Boxes
ssd_inception_v2_coco	42	24	Boxes
faster_rcnn_inception_v2_coco	58	28	Boxes

The general idea behind transfer learning is to transfer knowledge not data. For humans, this task is easy – we can generalize models that we have mentally created a long time ago for a different purpose. One or two samples is almost always enough. However, in the case of neural networks, a huge amount of data and computational power are required.

Transfer learning should generally be used when we don't have a lot of labeled training data, or if there already exists a network for the task you are trying to achieve, probably trained on a much more massive dataset. Note, however, that the input of the model must have the same size during training. Also, this works only if the tasks are fairly similar to each other, and the features learned can be generalized. For example, something like learning how to recognize vehicles can probably be extended to learn how to recognize airplanes and helicopters.

Q5. What does tuning of hyperparameters signify? Explain with examples.

Answer:

A hyperparameter is just a variable that defines the structure of the network. Let's go through some hyperparameters and see the effect of tuning them.


- 1 **A number of hidden layers** Most times, the presence or absence of a large number of hidden layers may determine the output, accuracy and training time of the neural network. Having a large number of these layers may sometimes cause an increase in accuracy.
- 2 **Learning rate** This is simply a measure of how fast the neural network will change its parameters. A large learning rate may lead to the network not being able to converge, but might also speed up learning. On the other hand, a smaller value for the learning rate will probably slow down the network but might lead to the network being able to converge.
- 3 **Number of epochs** This is the number of times the entire training data is run through the network. Increasing the number of epochs leads to better accuracy.
- 4 **Momentum** Momentum is a measure of how and where the network will go while taking into account all of its past actions. A proper measure of momentum can lead to a better network.
- 5 **Batch Size** Batch size determines the number of subsamples that are inputs to the network before every parameter update.

Q6. Why are deep learning models referred as black boxes?

Answer:

Lately, the concept of deep learning being a black box has been floating around. A black box is a system whose functioning cannot be properly grasped, but the output produced can be understood and utilized.

Now, since most models are mathematically sound and are created based on legit equations, how is it possible that we do not know how the system works?



First, it is almost impossible to visualize the functions that are generated by a system. Most machine learning models end up with such complex output that a human can't make sense of it.

Second, there are networks with millions of hyperparameters. As a human, we can grasp around 10 to 15 parameters. But analysing a million of them seems out of the question.

Third and most important, it becomes very hard, if not impossible, to trace back why the system made the decisions it did. This may not sound like a huge problem to worry about but consider the case of a self driving car. If the car hits someone on the road, we need to understand why that happened and prevent it. But this isn't possible if we do not understand how the system works.

To make a deep learning model not be a black box, a new field called Explainable Artificial Intelligence or simply, Explainable AI is emerging. This field aims to be able to create intermediate results and trace back the decision-making process of a system.

Q7. Why do we have gates in neural networks?

Answer:

To understand gates, we must first understand recurrent neural networks.

Recurrent neural networks allow information to be stored as a memory using loops. Thus, the output of a recurrent neural network is not only based on the current input but also the past inputs which are stored in the memory of the network. Backpropagation is done through time, but in general, the truncated version of this is used for longer sequences.

Gates are generally used in networks that are dependent on time. In effect, any network which would require memory, so to speak, would benefit from the use of gates. These gates are generally used to keep track of any information that is required by the network without leading to a state of either vanishing or exploding gradients. Such a network can also preserve the error through time. Since a sense of constant error is maintained, the network can learn better.

Logic Gates


Name	NOT	AND	NAND	OR	NOR	XOR	XNOR																																																																																																																																																																																																																																																																									
Alg. Expr.	\bar{A}	AB	\overline{AB}	$A+B$	$\overline{A+B}$	$A \oplus B$	$\overline{A \oplus B}$																																																																																																																																																																																																																																																																									
Symbol																																																																																																																																																																																																																																																																																
Truth Table	<table border="1"> <tr> <th>A</th><th>X</th><th>B</th><th>A</th><th>X</th><th>B</th><th>A</th><th>X</th><th>B</th><th>A</th><th>X</th><th>B</th><th>A</th><th>X</th><th>B</th><th>A</th><th>X</th> </tr> <tr> <td>0</td><td>1</td><td>0</td><td>0</td><td>0</td><td>0</td><td>0</td><td>1</td><td>0</td><td>0</td><td>0</td><td>0</td><td>0</td><td>1</td><td>0</td><td>0</td><td>0</td><td>1</td> </tr> <tr> <td>1</td><td>0</td><td>0</td><td>1</td><td>0</td><td>0</td><td>1</td><td>1</td><td>0</td><td>1</td><td>1</td><td>0</td><td>1</td><td>0</td><td>0</td><td>1</td><td>0</td><td>0</td> </tr> <tr> <td></td><td></td><td>1</td><td>0</td><td>0</td><td>1</td><td>1</td><td>0</td><td>1</td><td>0</td><td>1</td><td>1</td><td>0</td><td>0</td><td>1</td><td>0</td><td>1</td><td>0</td> </tr> <tr> <td></td><td></td><td>1</td><td>1</td><td>1</td><td>1</td><td>1</td><td>1</td><td>1</td><td>1</td><td>1</td><td>1</td><td>1</td><td>0</td><td>1</td><td>1</td><td>1</td><td>1</td> </tr> </table>	A	X	B	A	X	B	A	X	B	A	X	B	A	X	B	A	X	0	1	0	0	0	0	0	1	0	0	0	0	0	1	0	0	0	1	1	0	0	1	0	0	1	1	0	1	1	0	1	0	0	1	0	0			1	0	0	1	1	0	1	0	1	1	0	0	1	0	1	0			1	1	1	1	1	1	1	1	1	1	1	0	1	1	1	1	<table border="1"> <tr> <th>B</th><th>A</th><th>X</th><th>B</th><th>A</th><th>X</th><th>B</th><th>A</th><th>X</th><th>B</th><th>A</th><th>X</th><th>B</th><th>A</th><th>X</th><th>B</th><th>A</th><th>X</th> </tr> <tr> <td>0</td><td>0</td><td>0</td><td>0</td><td>0</td><td>1</td><td>0</td><td>0</td><td>0</td><td>0</td><td>0</td><td>1</td><td>0</td><td>0</td><td>0</td><td>0</td><td>0</td><td>1</td> </tr> <tr> <td>0</td><td>1</td><td>0</td><td>0</td><td>1</td><td>1</td><td>0</td><td>1</td><td>1</td><td>0</td><td>1</td><td>0</td><td>0</td><td>1</td><td>1</td><td>0</td><td>1</td><td>0</td> </tr> <tr> <td>1</td><td>0</td><td>0</td><td>1</td><td>0</td><td>1</td><td>1</td><td>0</td><td>1</td><td>1</td><td>0</td><td>0</td><td>1</td><td>0</td><td>1</td><td>1</td><td>0</td><td>0</td> </tr> <tr> <td>1</td><td>1</td><td>1</td><td>1</td><td>1</td><td>0</td><td>1</td><td>1</td><td>1</td><td>1</td><td>1</td><td>0</td><td>1</td><td>1</td><td>0</td><td>1</td><td>1</td><td>1</td> </tr> </table>	B	A	X	B	A	X	B	A	X	B	A	X	B	A	X	B	A	X	0	0	0	0	0	1	0	0	0	0	0	1	0	0	0	0	0	1	0	1	0	0	1	1	0	1	1	0	1	0	0	1	1	0	1	0	1	0	0	1	0	1	1	0	1	1	0	0	1	0	1	1	0	0	1	1	1	1	1	0	1	1	1	1	1	0	1	1	0	1	1	1	<table border="1"> <tr> <th>B</th><th>A</th><th>X</th><th>B</th><th>A</th><th>X</th><th>B</th><th>A</th><th>X</th><th>B</th><th>A</th><th>X</th><th>B</th><th>A</th><th>X</th><th>B</th><th>A</th><th>X</th> </tr> <tr> <td>0</td><td>0</td><td>0</td><td>0</td><td>0</td><td>1</td><td>0</td><td>0</td><td>1</td><td>0</td><td>1</td><td>0</td><td>0</td><td>0</td><td>1</td><td>0</td><td>0</td><td>1</td> </tr> <tr> <td>0</td><td>1</td><td>1</td><td>0</td><td>1</td><td>0</td><td>0</td><td>1</td><td>0</td><td>1</td><td>0</td><td>1</td><td>1</td><td>0</td><td>1</td><td>0</td><td>1</td><td>0</td> </tr> <tr> <td>1</td><td>0</td><td>1</td><td>1</td><td>0</td><td>0</td><td>1</td><td>0</td><td>1</td><td>1</td><td>0</td><td>0</td><td>1</td><td>0</td><td>1</td><td>1</td><td>0</td><td>0</td> </tr> <tr> <td>1</td><td>1</td><td>0</td><td>1</td><td>1</td><td>1</td><td>1</td><td>1</td><td>0</td><td>1</td><td>1</td><td>0</td><td>1</td><td>1</td><td>0</td><td>1</td><td>1</td><td>1</td> </tr> </table>	B	A	X	B	A	X	B	A	X	B	A	X	B	A	X	B	A	X	0	0	0	0	0	1	0	0	1	0	1	0	0	0	1	0	0	1	0	1	1	0	1	0	0	1	0	1	0	1	1	0	1	0	1	0	1	0	1	1	0	0	1	0	1	1	0	0	1	0	1	1	0	0	1	1	0	1	1	1	1	1	0	1	1	0	1	1	0	1	1	1
A	X	B	A	X	B	A	X	B	A	X	B	A	X	B	A	X																																																																																																																																																																																																																																																																
0	1	0	0	0	0	0	1	0	0	0	0	0	1	0	0	0	1																																																																																																																																																																																																																																																															
1	0	0	1	0	0	1	1	0	1	1	0	1	0	0	1	0	0																																																																																																																																																																																																																																																															
		1	0	0	1	1	0	1	0	1	1	0	0	1	0	1	0																																																																																																																																																																																																																																																															
		1	1	1	1	1	1	1	1	1	1	1	0	1	1	1	1																																																																																																																																																																																																																																																															
B	A	X	B	A	X	B	A	X	B	A	X	B	A	X	B	A	X																																																																																																																																																																																																																																																															
0	0	0	0	0	1	0	0	0	0	0	1	0	0	0	0	0	1																																																																																																																																																																																																																																																															
0	1	0	0	1	1	0	1	1	0	1	0	0	1	1	0	1	0																																																																																																																																																																																																																																																															
1	0	0	1	0	1	1	0	1	1	0	0	1	0	1	1	0	0																																																																																																																																																																																																																																																															
1	1	1	1	1	0	1	1	1	1	1	0	1	1	0	1	1	1																																																																																																																																																																																																																																																															
B	A	X	B	A	X	B	A	X	B	A	X	B	A	X	B	A	X																																																																																																																																																																																																																																																															
0	0	0	0	0	1	0	0	1	0	1	0	0	0	1	0	0	1																																																																																																																																																																																																																																																															
0	1	1	0	1	0	0	1	0	1	0	1	1	0	1	0	1	0																																																																																																																																																																																																																																																															
1	0	1	1	0	0	1	0	1	1	0	0	1	0	1	1	0	0																																																																																																																																																																																																																																																															
1	1	0	1	1	1	1	1	0	1	1	0	1	1	0	1	1	1																																																																																																																																																																																																																																																															

These gated units can be considered as units with recurrent connections. They also contain additional neurons, which are gates. If you relate this process to a signal processing system, the gate is used to

regulate which part of the signal passes through. A sigmoid activation function is used which means that the values taken are from 0 to 1.

An advantage of using gates is that it enables the network to either forget information that it has already learned or to selectively ignore information either based on the state of the network or the input the gate receives.

Gates are extensively used in recurrent neural networks, especially in Long Short-Term Memory (LSTM) networks. A general LSTM network will have 3 to 5 gates, typically an input gate, output gate, hidden gate, and activation gate.



Q8. What is a Sobel filter?

Answer:

The Sobel filter performs a two-dimensional spatial gradient measurement on a given image, which then emphasizes regions that have a high spatial frequency. In effect, this means finding edges.

In most cases, Sobel filters are used to find the approximate absolute gradient magnitude for every point in a grayscale image. The operator consists of a pair of 3×3 convolution kernels. One of these kernels is rotated by 90 degrees.

-1	0	+1
-2	0	+2
-1	0	+1

x filter

+1	+2	+1
0	0	0
-1	-2	-1

y filter

These kernels respond to edges that run horizontal or vertical with respect to the pixel grid, one kernel for each orientation. A point to note is that these kernels can be applied either separately or can be combined to find the absolute magnitude of the gradient at every point.

The Sobel operator has a large convolution kernel, which ends up smoothing the image to a greater extent, and thus, the operator becomes less sensitive to noise. It also produces higher output values for similar edges compared to other methods.


To overcome the problem of output values from the operator overflowing the maximum allowed pixel value per image type, avoid using image types that support pixel values

Q9. What is the purpose of a Boltzmann Machine?

Answer:

Boltzmann machines are algorithms that are based on physics, specifically thermal equilibrium. A special and more well-known case of Boltzmann machines is the Restricted Boltzmann machine, which is a type of Boltzmann machine where there are no connections between hidden layers of the network.

The concept was coined by Geoff Hinton, who most recently won the Turing award. In general, the algorithm uses the laws of thermodynamics and tries to optimize a global distribution of energy in the system.



In discrete mathematical terms, a restricted Boltzmann machine can be called a symmetric bipartite graph, i.e. two symmetric layers. These machines are a form of unsupervised learning, which means that there are no labels provided with data. It uses stochastic binary units to reach this state.

Boltzmann machines are derived from Markov state machines. A Markov State Machine is a model that can be used to represent almost any computable function. The restricted Boltzmann machine can be regarded as an undirected graphical model. It is used in dimensionality reduction, collaborative filtering, learning features as well as modeling. It can also be used for classification and regression. In general, restricted Boltzmann machines are composed of a two-layer network, which can then be extended further.

Note that these models are probabilistic since each of the nodes present in the system learns low-level features from items in the dataset. For example, if we take a grayscale image, each node that is responsible for the visible layer will take just one-pixel value from the image.

A part of the process of creating such a machine is a feature hierarchy where sequences of activations are grouped in terms of features. In thermodynamics principles, simulated annealing is a process that the machine follows to separate signal and noise.

Q10. What are the types of weight initialization?

Answer:

There are two major types of weight initialization:- zero initialization and random initialization

Zero initialization: In this process, biases and weights are initialised to 0. If the weights are set to 0, all derivatives with respect to the loss functions in the weight matrix become equal. Hence, none of the weights change during subsequent iterations. Setting the bias to 0 cancels out any effect it may have.

All hidden units become symmetric due to zero initialization. In general, zero initialization is not very useful or accurate for classification and thus must be avoided when any classification task is required.

Random initialization: As compared to 0 initialization, this involves setting random values for the weights. The only disadvantage is that setting very high values will increase the learning time as the sigmoid activation function maps close to 1. Likewise, if low values are set, the learning time increases as the activation function is mapped close to 0.

Setting too high or too low values thus generally leads to the exploding or vanishing gradient problem.

New types of weight initialization like **He initialization** and **Xavier initialization** have also emerged. These are based on specific equations and are not mentioned here due to their sheer complexity.

**DATA SCIENCE
INTERVIEW
PREPARATION
(30 Days of Interview
Preparation)**

DAY 12

Q1. Where is the confusion matrix used? Which module would you use to show it?

Answer:

In machine learning confusion matrix is one of the easiest ways to summarize the performance of your algorithm

At times it is difficult to judge the accuracy of a model by just looking at the accuracy because of problems like unequal distribution So a better way to check how good your model is is to use a confusion matrix

First let's look at some key terms

Classification accuracy This is the ratio of the number of correct predictions to the number of predictions made

True positives Correct predictions of true events

False positives Incorrect predictions of true events

True negatives Correct predictions of false events

False negatives Incorrect predictions of false events

The confusion matrix is now simply a matrix containing true positives false positives true negatives false negatives

		Predicted Class		
		Positive	Negative	
Actual Class	Positive	True Positive (TP)	False Negative (FN) <i>Type II Error</i>	Sensitivity $\frac{TP}{(TP + FN)}$
	Negative	False Positive (FP) <i>Type I Error</i>	True Negative (TN)	Specificity $\frac{TN}{(TN + FP)}$
	Precision $\frac{TP}{(TP + FP)}$	Negative Predictive Value $\frac{TN}{(TN + FN)}$	Accuracy $\frac{TP + TN}{(TP + TN + FP + FN)}$	

Q2: What is Accuracy?

Answer:

It is the most intuitive performance measure and it simply a ratio of correctly predicted to the total observations. We can say as if we have high accuracy then our model is best. Yes we could say that accuracy is a great measure but only when you have symmetric datasets where false positives and false negatives are almost same.

Accuracy = True Positive + True Negative / (True Positive + False Positive + False Negative + True Negative)

		Condition Absent	Condition Present
Negative Result	True Negative	False Negative	
	False Positive	True Positive	
Positive Result			

Q3: What is Precision?

Answer:

It is also called as the positive predictive value Number of correct positives in your model that predicts compared to the total number of positives it predicts.

Precision = True Positives / (True Positives + False Positives)

Precision = True Positives / Total predicted positive

It is the number of positive elements predicted properly divided by the total number of positive elements predicted.

We can say Precision is a measure of exactness quality or accuracy High precision

Means that more or all of the positive results you predicted are correct

Q4: What is Recall?

Answer:

Recall we can also called as sensitivity or true positive rate

It is several positives that our model predicts compared to the actual number of positives in our data

$$\text{Recall} = \frac{\text{True Positives}}{\text{True Positives} + \text{False Positives}}$$

$$\text{Recall} = \frac{\text{True Positives}}{\text{True Positives} + \text{False Negatives}}$$

Recall is a measure of completeness High recall which means that our model classified most or all of the possible positive elements as positive


Q5: What is F1 Score?

Answer:

We use Precision and recall together because they complement each other in how they describe the effectiveness of a model The F1 score that combines these two as the weighted harmonic mean of precision and recall

$$\text{F1 Score} = \frac{2 * (\text{Precision} * \text{Recall})}{\text{Precision} + \text{Recall}}$$

$$\begin{aligned}\text{Precision} &= \frac{\text{True Positive}}{\text{Actual Results}} \quad \text{or} \quad \frac{\text{True Positive}}{\text{True Positive} + \text{False Positive}} \\ \text{Recall} &= \frac{\text{True Positive}}{\text{Predicted Results}} \quad \text{or} \quad \frac{\text{True Positive}}{\text{True Positive} + \text{False Negative}} \\ \text{Accuracy} &= \frac{\text{True Positive} + \text{True Negative}}{\text{Total}}\end{aligned}$$



Q6: What is Bias and Variance trade-off?

Answer:

Bias

Bias means it's how far are the predicted values from the actual values. If the average predicted values are far off from the actual values then we call this one as having high bias.


When our model has a high bias, then it means that our model is too simple and does not capture the complexity of data, thus underfitting the data.

Variance


It occurs when our model performs well on the trained dataset but does not do well on a dataset that it is not trained on like a test dataset or validation dataset. It tells us that actual value is how much scattered from the predicted value.

Because of High variance it causes overfitting that implies that the algorithm models random noise present in the training data.

When model has high variance, then model becomes very flexible and tunes itself to the data points of the training set.



Bias-variance: It decomposition essentially decomposes the learning error from any algorithm by adding bias the variance and a bit of irreducible error due to noise in the underlying dataset. Essentially if we make the model more complex and add more variables We ll lose bias but gain some variance to get the optimally reduced amount of error you ll have to tradeoff bias and variance. We don t want either high bias or high variance in your model.



Bias and variance using bulls-eye diagram

Q7. What is data wrangling? Mention three points to consider in the process.

Answer:

Data wrangling is a process by which we convert and map data. This changes data from its raw form to a format that is a lot more valuable.

Data wrangling is the first step for machine learning and deep learning. The end goal is to provide data that is actionable and to provide it as fast as possible.

There are three major things to focus on while talking about data wrangling

1. Acquiring data

The first and probably the most important step in data science is the acquiring, sorting and cleaning of data. This is an extremely tedious process and requires the most amount of time.

One needs to:

- Check if the data is valid and up-to-date
- Check if the data acquired is relevant for the problem at hand

Sources for data collection Data is publicly available on various websites like

kaggle.com [data.gov](#) [World Bank](#) [Five Thirty Eight Datasets](#) AWS Datasets Google Datasets

2. Data cleaning

Data cleaning is an essential component of data wrangling and requires a lot of patience. To make the job easier it is first essential to format the data make the data readable for humans at first.

The essentials involved are:

- Format the data to make it more readable
- Find outliers (data points that do not match the rest of the dataset) in data
- Find missing values and remove them from the data set (without this any model being trained becomes incomplete and useless)

3. Data Computation

At times your machine not have enough resources to run your algorithm e.g. you might not have a GPU. In these cases you can use publicly available APIs to run your algorithm. These are standard end points found on the web which allow you to use computing power over the web and process data without having to rely on your own system. An example would be the Google Colab Platform.



Q8. Why is normalization required before applying any machine learning model? What module can you use to perform normalization?

Answer:

Normalization is a process that is required when an algorithm uses something like distance measures. Examples would be clustering data, finding cosine similarities, creating recommender systems.

Normalization is not always required and is done to prevent variables that are on higher scale from affecting outcomes that are on lower levels. For example, consider a dataset of employees' income. This data won't be on the same scale if you try to cluster it. Hence, we would have to normalize the data to prevent incorrect clustering.

A key point to note is that normalization does not distort the differences in the range of values.

A problem we might face if we don't normalize data is that gradients would take a very long time to descend and reach the global maxima/minima.

For numerical data, normalization is generally done between the range of 0 to 1.

The general formula is:

$$X_{\text{new}} = \frac{(x - x_{\text{min}})}{(x_{\text{max}} - x_{\text{min}})}$$

Normalization Formula

$$X_{\text{normalized}} = \frac{(x - X_{\text{minimum}})}{(X_{\text{maximum}} - X_{\text{minimum}})}$$



Q9. What is the difference between feature selection and feature extraction?

Feature selection and feature extraction are two major ways of fixing the curse of dimensionality

1. Feature selection:

Feature selection is used to filter a subset of input variables on which the attention should focus. Every other variable is ignored. This is something which we as humans tend to do subconsciously.


Many domains have tens of thousands of variables out of which most are irrelevant and redundant. Feature selection limits the training data and reduces the amount of computational resources used. It can significantly improve a learning algorithms performance.

In summary we can say that the goal of feature selection is to find out an optimal feature subset. This might not be entirely accurate however methods of understanding the importance of features also exist. Some modules in python such as Xgboost help achieve the same.

2. Feature extraction

Feature extraction involves transformation of features so that we can extract features to improve the process of feature selection. For example in an unsupervised learning problem the extraction of bigrams from a text or the extraction of contours from an image are examples of feature extraction.

The general workflow involves applying feature extraction on given data to extract features and then apply feature selection with respect to the target variable to select a subset of data. In effect this helps improve the accuracy of a model.



Q10. Why is polarity and subjectivity an issue?

Polarity and subjectivity are terms which are generally used in sentiment analysis

Polarity is the variation of emotions in a sentence. Since sentiment analysis is widely dependent on emotions and their intensity, polarity turns out to be an extremely important factor.

In most cases, opinions and sentiment analysis are evaluations. They fall under the categories of emotional and rational evaluations.

Rational evaluations, as the name suggests, are based on facts and rationality while emotional evaluations are based on non-tangible responses, which are not always easy to detect.


Subjectivity in sentiment analysis is a matter of personal feelings and beliefs which may or may not be based on any fact. When there is a lot of subjectivity in a text, it must be explained and analysed in context. On the contrary, if there was a lot of polarity in the text, it could be expressed as a positive, negative or neutral emotion.

Q11. When would you use ARIMA?

Answer:

ARIMA is a widely used statistical method which stands for Auto Regressive Integrated Moving Average. It is generally used for analyzing time series data and time series forecasting. Let's take a quick look at the terms involved.

Auto Regression is a model that uses the relationship between the observation and some numbers of lagging observations.



Integrated means use of differences in raw observations which help make the time series stationary

Moving Averages is a model that uses the relationship and dependency between the observation and residual error from the models being applied to the lagging observations

Note that each of these components are used as parameters. After the construction of the model a linear regression model is constructed

Data is prepared by:

- Finding out the differences
- Removing trends and structures that will negatively affect the model
- Finally making the model stationary

**DATA SCIENCE
INTERVIEW
PREPARATION
(30 Days of Interview
Preparation)
Day13**

Q1. What is Autoregression?

Answer:

The autoregressive (AR) model is commonly used to model time-varying processes and solve problems in the fields of natural science, economics and finance, and others. The models have always been discussed in the context of random process and are often perceived as statistical tools for time series data.

A regression model, like linear regression, models an output value which are based on a linear combination of input values

Example: $\hat{y} = b_0 + b_1 * X_1$

Where \hat{y} is the prediction, b_0 and b_1 are coefficients found by optimising the model on training data, and X is an input value

This model technique can be used on the time series where input variables are taken as observations at previous time steps, called lag variables


For example, we can predict the value for the next time step ($t+1$) given the observations at the last two time steps ($t-1$ and $t-2$). As a regression model, this would look as follows:

$$X(t+1) = b_0 + b_1 * X(t-1) + b_2 * X(t-2) -$$

Because the regression model uses the data from the same input variable at previous time steps, it is referred to as an autoregression

The notation AR(p) refers to the autoregressive model of order p . The AR(p) model is written

$$X_t = c + \sum_{i=1}^p \varphi_i X_{t-i} + \varepsilon_t.$$



Q2. What is Moving Average?


Answer:

Moving average: From a dataset, we will get an overall idea of trends by this technique; it is an average of any subset of numbers. For forecasting long-term trends, the moving average is extremely useful for it. We can calculate it for any period. For example: if we have sales data for twenty years, we can calculate the five-year moving average, a four-year moving average, a three-year moving average and so on. Stock market analysts will often use a 50 or 200-day moving average to help them see trends in the stock market and (hopefully) forecast where the stocks are headed.

The notation $\text{MA}(q)$ refers to the moving average model of order q :

$$X_t = \mu + \varepsilon_t + \sum_{i=1}^q \theta_i \varepsilon_{t-i}$$

where the $\theta_1, \dots, \theta_q$ are the parameters of the model, μ is the expectation of X_t (often assumed to equal 0), and the $\varepsilon_t, \varepsilon_{t-1}, \dots$ are again, white noise error terms.



The notation $\text{MA}(q)$ refers to the moving average model of order q :

Q3. What is Autoregressive Moving Average (ARMA)?

Answer:

ARMA: It is a model of forecasting in which the methods of autoregression (AR) analysis and moving average (MA) are both applied to time-series data that is well behaved. In ARMA it is assumed that the time series is stationary and when it fluctuates, it does so uniformly around a particular time.

AR (Autoregression model)-

Autoregression (AR) model is commonly used in current spectrum estimation

The following is the procedure for using ARMA

- Selecting the AR model and then equalizing the output to equal the signal being studied if the input is an impulse function or the white noise It should at least be good approximation of signal
- Finding a model s parameters number using the known autocorrelation function or the data
- Using the derived model parameters to estimate the power spectrum of the signal

Moving Average (MA) model-


It is a commonly used model in the modern spectrum estimation and is also one of the methods of the model parametric spectrum analysis The procedure for estimating MA model s signal spectrum is as follows

- Selecting the MA model and then equalising the output to equal the signal under study in the case where the input is an impulse function or white noise It should be at least a good approximation of the signal
- Finding the model s parameters using the known autocorrelation function
- Estimating the signal s power spectrum using the derived model parameters

In the estimation of the ARMA parameter spectrum, the AR parameters are first estimated, and then the MA parameters are estimated based on these AR parameters The spectral estimates of the ARMA model are then obtained The parameter estimation of the MA model is, therefore often calculated as a process of ARMA parameter spectrum association

The notation ARMA(p, q) refers to the model with p autoregressive terms and q moving-average terms This model contains the AR(p) and MA(q) models,

$$X_t = c + \varepsilon_t + \sum_{i=1}^p \varphi_i X_{t-i} + \sum_{i=1}^q \theta_i \varepsilon_{t-i}.$$



Q4. What is Autoregressive Integrated Moving Average (ARIMA)?

Answer:

ARIMA: It is a statistical analysis model that uses time-series data to either better understand the data set or to predict future trends

An ARIMA model can be understood by the outlining each of its components as follows-

- **Autoregression (AR):** It refers to a model that shows a changing variable that regresses on its own lagged, or prior, values
- **Integrated (I):** It represents the differencing of raw observations to allow for the time series to become stationary, i.e., data values are replaced by the difference between the data values and the previous values
- **Moving average (MA):** It incorporates the dependency between an observation and the residual error from the moving average model applied to the lagged observations

Each component functions as the parameter with a standard notation. For ARIMA models, the standard notation would be the ARIMA with p, d, and q, where integer values substitute for the parameters to indicate the type of the ARIMA model used. The parameters can be defined as-

- *p*: It is the number of lag observations in the model; also known as the lag order
- *d*: It is the number of times that the raw observations are differenced; also known as the degree of differencing
- *q*: It is the size of the moving average window; also known as the order of the moving average

ARIMA

Autoregressive Moving
Averages

$ARIMA(p,d,q)(P,D,Q)m$

- *p* = non-seasonal AR order
- *d* = non-seasonal differencing
- *q* = non-seasonal MA order
- *P* = seasonal AR order
- *D* = seasonal differencing
- *Q* = seasonal MA order
- *m* = number of periods/season

Forecast
Actual



$ARIMA(1,0,1)(4, 0, 7, 24)$

Q5.What is SARIMA (Seasonal Autoregressive Integrated Moving-Average)?

Answer:

Seasonal ARIMA: It is an extension of ARIMA that explicitly supports the univariate time series data with the seasonal component

It adds three new hyper-parameters to specify the autoregression (AR), differencing (I) and the moving average (MA) for the seasonal component of the series, as well as an additional parameter for the period of the seasonality

Configuring the SARIMA requires selecting hyperparameters for both the trend and seasonal elements of the series

Trend Elements

Three trend elements requires the configuration

They are same as the ARIMA model, specifically-

p: It is Trend autoregression order

d: It is Trend difference order

Q: It is Trend moving average order

Seasonal Elements-

Four seasonal elements are not the part of the ARIMA that must be configured, they are-

P: It is Seasonal autoregressive order

D: It is Seasonal difference order


Q: It is Seasonal moving average order

m: It is the number of time steps for the single seasonal period

Together, the notation for the SARIMA model is specified as-

SARIMA(p,d,Q)(P,D,Q)m

The elements can be chosen through careful analysis of the ACF and PACF plots looking at the correlations of recent time steps



Q6. What is Seasonal Autoregressive Integrated Moving-Average with Exogenous Regressors (SARIMAX) ?


Answer:

SARIMAX: It is an extension of the SARIMA model that also includes the modelling of the exogenous variables

Exogenous variables are also called the covariates and can be thought of as parallel input sequences that have observations at the same time steps as the original series. The primary series may be referred as endogenous data to contrast it from exogenous sequence(s). The observations for exogenous variables are included in the model directly at each time step and are not modeled in the same way as the primary endogenous sequence (e.g. as an AR, MA, etc. process)

The SARIMAX method can also be used to model the subsumed models with exogenous variables, such as ARX, MAX, ARMAX, and ARIMAX

The method is suitable for univariate time series with trend and/or seasonal components and exogenous variables



Q7. What is Vector autoregression (VAR)?

Answer:

VAR: It is a stochastic process model used to capture the linear interdependencies among multiple time series. VAR models generalise the univariate autoregressive model (AR model) by allowing for more than one evolving variable. All variables in the VAR enter the model in the same way: each variable has an equation explaining its evolution based on its own lagged values, the lagged values of the other model variables, and an error term. VAR modelling does not require as much knowledge about the forces influencing the variable as do structural models with simultaneous equations. The only prior knowledge required is a list of variables which can be hypothesised to affect each other intertemporally.

A VAR model describes the evolution of the set of k variables over the same sample period ($t = 1, \dots, T$) as the linear function of only their past values. The variables are collected in the k -vector ($(k \times 1)$ -matrix) y_t , which has as the (i^{th}) element, $y_{i,t}$, the observation at time t of the (i^{th}) variable. Example: if the (i^{th}) variable is the GDP, then $y_{i,t}$ is the value of GDP at time t .

$$y_t = c + A_1 y_{t-1} + A_2 y_{t-2} + \dots + A_p y_{t-p} + e_t,$$

where the observation y_{t-i} is called the (i -th) **lag** of y , c is the k -vector of constants (intercepts), A_i is a time-invariant ($k \times k$)-matrix, and e_t is a k -vector of error terms satisfying



Q8. What is Vector Autoregression Moving-Average (VARMA)?

Answer:

VARMA: It is a method that models the next step in each time series using an ARMA model. It is the generalisation of ARMA to multiple parallel time series. Example- multivariate time series

The notation for a model involves specifying the order for the AR(p) and the MA(q) models as parameters to the VARMA function, e.g. VARMA (p, q). The VARMA model can also be used to develop VAR or VMA models.

This method is suitable for multivariate time series without trend and seasonal components.



Q9. What is Vector Autoregression Moving-Average with Exogenous Regressors (VARMAX)?

Answer:

VARMAX: It is an extension of the VARMA model that also includes the modelling of the exogenous variables. It is the multivariate version of the ARMAX method.

Exogenous variables are also called the covariates and can be thought of as parallel input sequences that have observations at the same time steps as the original series. The primary series(es) are referred as the endogenous data to contrast it from the exogenous sequence(s). The observations for the exogenous variables are included in the model directly at each time step and are not modeled in the same way as the primary endogenous sequence (Example- as an AR, MA, etc.)

This method can also be used to model subsumed models with exogenous variables, such as VARX and the VMAX.

This method is suitable for multivariate time series without trend and seasonal components and exogenous variables.

Q10. What is Simple Exponential Smoothing (SES)?

Answer:

SES: It method models the next time step as an exponentially weighted linear function of observations at prior time steps

This method is suitable for univariate time series without trend and seasonal components

Exponential smoothing is the rule of thumb technique for smoothing time series data using the exponential window function. Whereas in the simple moving average, the past observations are weighted equally, exponential functions are used to assign exponentially decreasing weights over time. It is easily learned and easily applied procedure for making some determination based on prior assumptions by the user, such as seasonality. Exponential smoothing is often used for analysis of time-series data.


Exponential smoothing is one of many window functions commonly applied to smooth data in signal processing, acting as low-pass filters to remove high-frequency noise

The raw data sequence is often represented by $\{x_t\}$ beginning at time $t = 0$, and the output of the exponential smoothing algorithm is commonly written as $\{s_t\}$ which may be regarded as a best estimate of what the next value of x will be. When the sequence of observations begins at time $t=0$, the simplest form of exponential smoothing is given by the formulas:

$$s_0 = x_0$$

$$s_t = \alpha x_t + (1 - \alpha)s_{t-1}, t > 0$$

where α is the *smoothing factor*, and $0 < \alpha < 1$.



**DATA SCIENCE
INTERVIEW
PREPARATION
(30 Days of Interview
Preparation)**

DAY 14


Q1. What is Alexnet?

Answer:

The Alex Krizhevsky, Geoffrey Hinton and Ilya Sutskever created the neural network architecture called AlexNet and won Image Classification Challenge (ILSVRC) in 2012. They trained their network on 12 million high-resolution images into 1000 different classes with 60 million parameters and 650,000 neurons. The training was done on two GPUs with split layer concept because GPUs were a little bit slow at that time.

AlexNet is the name of convolutional neural network which has had a large impact on the field of machine learning, specifically in the application of deep learning to machine vision. The network had very similar architecture as the LeNet by Yann LeCun et al but was deeper with more filters per layer, and with the stacked convolutional layers. It consists of (11x11, 5x5, 3x3, convolutions), max pooling, dropout, data augmentation, ReLU activations and SGD with the momentum. It attached with ReLU activations after every convolutional and fully connected layer. AlexNet was trained for six days simultaneously on two Nvidia Geforce GTX 580 GPUs, which is the reason for why their network is split into the two pipelines.

Architecture



AlexNet contains eight layers with weights, first five are convolutional, and the remaining three are fully connected. The output of last fully-connected layer is fed to a 1000-way softmax which produces a distribution over the 1000 class labels. The network maximises the multinomial logistic regression objective, which is equivalent to maximising the average across training cases of the log-probability of the correct label under the prediction distribution. The kernels of second, fourth, and the fifth convolutional layers are connected only with those kernel maps in the previous layer which reside on the same GPU. The kernels of third convolutional layer are connected to all the kernel maps in second layer. The neurons in fully connected layers are connected to all the neurons in the previous layers.


In short, AlexNet contains five convolutional layers and three fully connected layers. ReLU is applied after the very convolutional and the fully connected layer. Dropout is applied before the first and second fully connected layer. The network has 62.3 million parameters and needs 1.1 billion computation units in a forward pass. We can also see convolution layers, which accounts for 6% of all the parameters, consumes 95% of the computation.

Q2. What is VGGNet?

Answer:


VGGNet consists of 16 convolutional layers and is very appealing because of its very uniform architecture. Similar to AlexNet, only 3x3 convolutions, but lots of filters. Trained on 4 GPUs for 2-3 weeks. It is currently the most preferred choice in the community for extracting features from images. The weight configuration of the VGGNet is publicly available and has been used in many other applications and challenges as a baseline feature extractor. However, VGGNet consists of 138 million parameters, which can be a bit challenging to handle.

There are multiple variants of the VGGNet (VGG16, VGG19 etc.) which differ only in total number of layers in the networks. The structural details of the VGG16 network has been shown:



The idea behind having the fixed size kernels is that all the variable size convolutional kernels used in the Alexnet (11x11, 5x5, 3x3) can be replicated by making use of multiple 3x3 kernels as the building blocks. The replication is in term of the receptive field covered by kernels.

Let's consider the example. Say we have an input layer of the size $5 \times 5 \times 1$. Implementing the conv layer with kernel size of 5×5 and stride one will result in a feature map of (1×1) . The same output feature map can be obtained by implementing the two (3×3) Conv layers with stride of 1 as below:




Now, let's look at the number of variables needed to be trained. For a 5×5 Conv layer filter, the number of variables is 25. On the other hand, two conv layers of kernel size 3×3 have a total of $3 \times 3 \times 2 = 18$ variables (a reduction of 28%)

Q3. What is VGG16?


Answer:

VGG16: It is a convolutional neural network model proposed by the K. Simonyan and A. Zisserman from the University of Oxford in the paper Very Deep Convolutional Networks for the Large-Scale Image Recognition. The model achieves 92.7% top 5 test accuracy in ImageNet, which is the dataset of over 14 million images belonging to the 1000 classes. It was one of famous model submitted to ILSVRC-2014. It improves AlexNet by replacing the large kernel-sized filters (11 and 5 in the first and second convolutional layer, respectively) with multiple 3×3 kernel-sized filters one after another. VGG16 was trained for weeks and was using NVIDIA Titan Black GPU's.



The Architecture

The architecture depicted below is VGG16



The input to the Cov1 layer is of fixed size of 224×224 RGB image. The image is passed through the stack of convolutional (conv) layers, where the filters were used with a very small receptive field: 3×3 (which is the smallest size to capture the notion of left/right, up/down, centre). In one of the configurations, it also utilises the 1×1 convolution filters, which can be seen as the linear transformation of the input channels. The convolution stride is fixed to the 1 pixel, the spatial padding of the Conv layer input is such that, the spatial resolution is preserved after the convolution, i.e. the

padding is 1-pixel for 3×3 Conv layers. Spatial pooling is carried out by the five max-pooling layers, which follows some of the Conv Layers. Max-pooling is performed over the 2×2 pixel window, with stride 2.


Three Fully-Connected (FC) layers follow the stack of convolutional layers (which has the different depth in different architectures): the first two have 4096 channels each, the third performs 1000-way ILSVRC classification and thus contains 1000 channels. The final layer is softmax layer. The configurations of the fully connected layers is same in all the networks.

All hidden layers are equipped with rectification (ReLU) non-linearity. It is also noted that none of the networks (except for one) contain the Local Response Normalisation (LRN), such normalisation does not improve the performance on the ILSVRC dataset, but leads to increased memory consumption and computation time.

Q4. What is ResNet?

Answer:

At the ILSVRC 2015, so-called Residual Neural Network (ResNet) by the Kaiming He et al introduced the novel architecture with skip connections and features heavy batch normalisation. Such skip connections are also known as the gated units or gated recurrent units and have the strong similarity to recent successful elements applied in RNNs. Thanks to this technique as they were able to train the NN with 152 layers while still having lower complexity than the VGGNet. It achieves the top-5 error rate of 3.57%, which beats human-level performance on this dataset.



Q5. What is HAAR CASCADE?

Answer:


Haar Cascade: It is the machine learning object detection algorithm used to identify the objects in an image or the video and based on the concept of features proposed by Paul Viola and Michael Jones in their paper "Rapid Object Detection using a Boosted Cascade of Simple Features" in 2001.

It is a machine learning-based approach where the cascade function is trained from the lot of positive and negative images. It is then used to detect the objects in other images.

The algorithm has four stages:

- Haar Feature Selection
- Creating Integral Images
- Adaboost Training
- Cascading Classifiers

It is well known for being able to detect faces and body parts in an image but can be trained to identify almost any object




Q6. What is Transfer Learning?

Answer:

Transfer learning: It is the machine learning method where the model developed for a task is reused as the starting point for the model on the second task

Transfer Learning differs from the traditional Machine Learning in that it is the use of pre-trained models that have been used for another task to jump-start the development process on a new task or problem



The benefits of the Transfer Learning are that it can speed up the time as it takes to develop and train the model by reusing these pieces or modules of already developed models. This helps to speed up the model training process and accelerate results.


Q7. What is Faster, R-CNN?

Answer:

Faster R-CNN: It has two networks: region proposal network (RPN) for generating region proposals and a network using these proposals to detect objects. The main difference here with the Fast R-CNN is that the later uses selective search to generate the region proposals. The time cost of generating the region proposals is much smaller in the RPN than selective search, when RPN shares the most computation with object detection network. In brief, RPN ranks region boxes (called anchors) and proposes the ones most likely containing objects.


Anchors

Anchors play an very important role in Faster R-CNN. An anchor is the box. In default configuration of Faster R-CNN, there are nine anchors at the position of an image. The graphs shown 9 anchors at the position (320, 320) of an image with size (600, 800).




Region Proposal Network:

The output of the region proposal network is the bunch of boxes/proposals that will be examined by a classifier and regressor to check the occurrence of objects eventually. To be more precise, RPN predicts the possibility of an anchor being background or foreground, and refine the anchor.

**Q8. What is RCNN?****Answer:**

To bypass the problem of selecting the huge number of regions, Ross Girshick et al proposed a method where we use the selective search to extract just 2000 regions from the image, and he called them as region proposals. Therefore, instead of trying to classify the huge number of regions, you can work with 2000 regions.

R-CNN: Regions with CNN features



Problems with R-CNN:


- It still takes the huge amount of time to train the network as we would have to classify 2000 region proposals per image
- It cannot be implemented real-time as it takes around 47 seconds for each test image
- The selective search algorithm is the fixed algorithm. Therefore, no learning is happening at that stage. This leads to the generation of the bad candidate region proposals

Q9.What is GoogLeNet/Inception?

Answer:

The winner of the ILSVRC 2014 competition was GoogLeNet from Google. It achieved a top-5 error rate of 6.67%. This was very close to human-level performance which the organisers of the challenge were now forced to evaluate. As it turns out, this was rather hard to do and required some human training to beat GoogLeNet's accuracy. After the few days of training, the human expert (Andrej Karpathy) was able to achieve the top-5 error rate of 5.1% (single model) and 3.6% (ensemble). The network used the CNN inspired by LeNet but implemented a novel element which is dubbed an inception module. It used batch normalisation, image distortions and RMSprop. This module is based on several very small convolutions to reduce the number of parameters drastically. Their architecture consisted of the 22-layer deep CNN but reduced the number of parameters from 60 million (AlexNet) to 4 million.


It contains 1×1 Convolution at the middle of network, and global average pooling is used at the end of the network instead of using the fully connected layers. These two techniques are from another paper Network In-Network (NIN). Another technique, called inception module, is to have different sizes/types of convolutions for the same input and to stack all the outputs.



Q10. What is LeNet-5?

Answer:

LeNet-5, a pioneering 7-level convolutional network by the LeCun et al in 1998, that classifies digits, was applied by several banks to recognise hand-written numbers on checks (cheques) digitised in 32x32 pixel greyscale input images. The ability to process higher-resolution images requires larger and more convolutional layers, so the availability of computing resources constrains this technique.



LeNet-5 is a very simple network. It only has seven layers, among which there are three convolutional layers (C1, C3 and C5), two sub-sampling (pooling) layers (S2 and S4), and one fully connected layer (F6), that are followed by output layers. Convolutional layers use 5 by 5 convolutions with stride 1. Sub-sampling layers are 2 by 2 average pooling layers. Tanh sigmoid activations are used throughout the network. Several interesting architectural choices were made in LeNet-5 that are not very common in the modern era of deep learning.

DATA SCIENCE INTERVIEW PREPARATION


**(30 Days of Interview
Preparation)**

DAY 15

Q1. What is Autoencoder?

Answer:

Autoencoder neural network: It is an unsupervised Machine learning algorithm that applies backpropagation setting the target values to be equal to the inputs. It is trained to attempt to copy its input to its output. Internally it has the hidden layer that describes a code used to represent the input.



It is trying to learn the approximation to the identity function to output \hat{x} that is similar to the x . Autoencoders belongs to the neural network family but they are also closely related to PCA principal components analysis.


Auto encoders although it is quite similar to PCA but its Autoencoders are much more flexible than PCA. Autoencoders can represent both liners and non-linear transformation in encoding but PCA can perform linear transformation. Autoencoders can be layered to form deep learning network due to its Network representation.

Types of Autoencoders:

1 Denoising autoencoder


Autoencoders are Neural Networks which are used for feature selection and extraction. However when there are more nodes in hidden layer than there are inputs the Network is risking to learn so-called Identity Function also called Null Function meaning that output equals the input marking the Autoencoder useless.

Denoising Autoencoders solve this problem by corrupting the data on purpose by randomly turning some of the input values to zero. In general, the percentage of input nodes which are being set to zero is about 50%. Other sources suggest a lower count such as 30%. It depends on the amount of data and input nodes you have.



2 Sparse autoencoder

An autoencoder takes the input image or vector and learns code dictionary that changes the raw input from one representation to another. Where in sparse autoencoders with a sparsity enforcer that directs a single-layer network to learn code dictionary which in turn minimizes the error in reproducing the input while restricting number of code words for reconstruction. The sparse autoencoder consists a single hidden layer which is connected to the input vector by a weight matrix forming the encoding step. The hidden layer then outputs to a reconstruction vector using a tied weight matrix to form the decoder.



Q2. What Is Text Similarity?


Answer:

When talking about text similarity, different people have a slightly different notion on what text similarity means. In essence, the goal is to compute how close two pieces of text are in 1 meaning or 2 surface closeness. The first is referred to as **semantic similarity** and the latter is referred to as **lexical similarity**. Although the methods for *lexical similarity* are often used to achieve *semantic similarity* to a certain extent, achieving true semantic similarity is often much more involved.

Lexical or Word Level Similarity


When referring to text similarity people refer to how similar the two pieces of text are at the surface level Example- how similar are the phrases *the cat ate the mouse* with *the mouse ate the cat food* by just looking at the words? On the surface if you consider only word-level similarity these two phrases with determiners disregarded appear very similar as 3 of the 4 unique words are an exact overlap

$\hookrightarrow \text{Overlap} = \text{'cat ate mouse'} \cap \text{'mouse ate cat food'} = 3$



Semantic Similarity:

Another notion of similarity mostly explored by NLP research community is how similar in meaning are any two phrases? If we look at the phrases *the cat ate the mouse* and *the mouse ate the cat food* As we know that while the words significantly overlaps these two phrases have different meaning Meaning out of the phrases is often the more difficult task as it requires deeper level of analysis Example we can actually look at the simple aspects like order of words: *cat = ate = mouse* and *mouse = ate = cat food* Words overlap in this case the order of the occurrence is different and we can tell that these two phrases have different meaning This is just the one example Most people use the syntactic parsing to help with the semantic similarity Let s have a look at the parse trees for these two phrases What can you get from it?



Q3. What is dropout in neural networks?


Answer:

When we training our neural network or model by updating each of its weights it might become too dependent on the dataset we are using. Therefore when this model has to make a prediction or classification it will not give satisfactory results. This is known as over-fitting. We might understand this problem through a real-world example: If a student of science learns *only* one chapter of a book and then takes a test on the *whole* syllabus he will probably fail.


To overcome this problem we use a technique that was introduced by Geoffrey Hinton in 2012. This technique is known as **dropout**.

Dropout refers to ignoring units i.e. neurons during the training phase of certain set of neurons which is chosen at random. By ignoring I mean these units are not considered during a particular forward or backward pass.

At each training stage individual nodes are either dropped out of the net with probability $1-p$ or kept with probability p so that a reduced network is left; incoming and outgoing edges to a dropped-out node are also removed.



(a) Standard Neural Network




(b) Network after Dropout

Q4. What is Forward Propagation?

Answer:

Input X provides the information that then propagates to hidden units at each layer and then finally produce the output y . The architecture of network entails determining its depth width and the activation functions used on each layer. **Depth** is the number of the hidden layers. **Width** is the number of units/nodes on each hidden layer since we don't control neither input layer nor output layer dimensions. There are quite a few set of activation functions such *Rectified Linear Unit*, *Sigmoid*, *Hyperbolic tangent*, etc. Research has proven that deeper networks outperform networks with more hidden units. Therefore, it's always better and won't hurt to train a deeper network.



Q5. What is Text Mining?

Answer:

Text mining: It is also referred as **text data mining** roughly equivalent to **text analytics** is the process of deriving high-quality information from text. High-quality information is typically derived through the devising of patterns and trends through means such as statistical pattern learning. Text mining usually involves the process of structuring the input text usually parsing along with the addition of some derived linguistic features and the removal of others and subsequent insertion into a database deriving patterns within the structured data and finally evaluation and interpretation of the output. 'High quality' in text mining usually refers to some combination of relevance, novelty, and interest. Typical text mining tasks include text categorization, text clustering, concept/entity extraction, production of granular taxonomies, sentiment analysis, document summarization, and entity relation modeling, i.e., learning relations between named entities.

Sources of Data




Q6. What is Information Extraction?

Answer:

Information extraction IE : It is the task of automatically extracting structured information from the unstructured and/or semi-structured machine-readable documents. In most of the cases this activity concerns processing human language texts using natural language processing NLP

Information extraction depends on named entity recognition **NER** a sub-tool used to find targeted information to extract. NER recognizes entities first as one of several categories such as location **LOC** persons **PER** or organizations **ORG**. Once the information category is recognized an information extraction utility extracts the named entity's related information and constructs a machine-readable document from it which algorithms can further process to extract meaning. IE finds meaning by way of other subtasks including co-reference resolution relationship extraction language and vocabulary analysis and sometimes audio extraction



Q7. What is Text Generation?


Answer:

Text Generation: It is a type of the Language Modelling problem. **Language Modelling** is the core problem for several of natural language processing tasks such as speech to text conversational system and the text summarization. The trained language model learns the likelihood of occurrence of the word based on the previous sequence of words used in the text. Language models can be operated at the character level, n-gram level, sentence level or even paragraph level.

A language model is at the core of many NLP tasks and is simply a probability distribution over a sequence of words:

$$p(w_1, \dots, w_n)$$

It can also be used to estimate the conditional probability of the next word in a sequence:



Q8. What is Text Summarization?

Answer:

We all interact with the applications which uses the text summarization. Many of the applications are for the platform which publishes articles on the daily news, entertainment, sports. With our busy schedule, we like to read the summary of those articles before we decide to jump in for reading entire article. Reading a summary helps us to identify the interest area, gives a brief context of the story.

Text summarization is a subdomain of Natural Language Processing (NLP) that deals with extracting summaries from huge chunks of texts. There are two main types of techniques used for text summarization: NLP-based techniques and deep learning-based techniques.

Text summarization: It refers to the technique of shortening long pieces of text. The intention is to create the coherent and fluent summary having only the main points outlined in the document.

How text summarization works:

The two types of summarization abstractive and the extractive summarization

- 1 **Abstractive Summarization:** It selects words based on the semantic understanding; even those words did not appear in the source documents. It aims at producing important material in the new way. They interprets and examines the text using advanced natural language techniques to generate the new shorter text that conveys the most critical information from the original text.


It can be correlated in the way human reads the text article or blog post and then summarizes in their word.

Input document → understand context → semantics → create own summary.

- 2 **Extractive Summarization:** It attempts to summarize articles by selecting the subset of words that retain the most important points.

This approach weights the most important part of sentences and uses the same to form the summary. Different algorithm and the techniques are used to define the weights for the sentences and further rank them based on importance and similarity among each other.

Input document → sentences similarity → weight sentences → select sentences with higher rank.



Q9. What is Topic Modelling?

Answer:

Topic Modelling is the task of using unsupervised learning to extract the main topics represented as a set of words that occur in a collection of documents

Topic modeling in the context of Natural Language Processing is described as a method of uncovering hidden structure in a collection of texts

Dimensionality Reduction:


Topic modeling is the form of dimensionality reduction. Rather than representing the text T in its feature space as $\{Word_i: count(Word_i \in T) \text{ for } Word_i \in V\}$ we can represent the text in its topic space as $\{Topic_i: weight(Topic_i \in T) \text{ for } Topic_i \in Topics\}$

Unsupervised learning:

Topic modeling can be compared to the clustering. As in the case of clustering, the number of topics like the number of clusters is the hyperparameter. By doing the topic modeling, we build clusters of words rather than clusters of texts. A text is thus a mixture of all the topics each having a certain weight.

A Form of Tagging

If document classification is assigning a single category to a text, topic modeling is assigning multiple tags to a text. A human expert can label the resulting topics with human-readable labels and use different heuristics to convert the weighted topics to a set of tags.




Q10.What is Hidden Markov Models?

Answer:

Hidden Markov Models HMMs are the class of probabilistic graphical model that allow us to predict the sequence of unknown hidden variables from the set of observed variables. The simple example of an HMM is predicting the weather hidden variable based on the type of clothes that someone wears observed. An HMM can be viewed as the Bayes Net unrolled through time with observations made at the sequence of time steps being used to predict the best sequence of the hidden states.


The below diagram from Wikipedia shows that HMM and its transitions. The scenario is the room that contains urns X1 X2 and X3 each of which contains a known mix of balls each ball labeled y1 y2 y3 and y4. The sequence of four balls is randomly drawn. In this particular case the user observes the sequence of balls y1 y2 y3 and y4 and is attempting to discern the hidden state which is the right sequence of three urns that these four balls were pulled from.



Why Hidden Markov Model?

The reason it is called the Hidden Markov Model is because we are constructing an inference model based on the assumptions of a Markov process. The Markov process assumption is simply that the future is independent of the past given the present.

To make this point clear let us consider the scenario below where the weather the hidden variable can be hot mild or cold and the observed variables are the type of clothing worn. The arrows represent transitions from a hidden state to another hidden state or from a hidden state to an observed variable.



iNeuron

**DATA SCIENCE
INTERVIEW
PREPARATION
(30 Days of Interview
Preparation)
Day-16**

Q1. What is Statistics Learning?

Answer:

Statistical learning: It is the framework for understanding data based on the statistics which can be classified as the supervised or unsupervised. Supervised statistical learning involves building the statistical model for predicting or estimating an output based on one or more inputs while in unsupervised statistical learning there are inputs but no supervising output but we can learn relationships and structure from such data.

$$Y = f(X) + \epsilon \quad X = X_1 \ X_2 \ \dots \ X_p$$

f : It is an unknown function & ϵ is random error reducible & irreducible


Prediction & Inference:

In the situations where the set of inputs X are readily available but the output Y is not known we often treat f as the black box not concerned with the exact form of f as long as it yields the accurate predictions for Y . This is the *prediction*.

There are the situations where we are interested in understanding the way that Y is affected as X change. In this type of situation we wish to estimate f but our goal is not necessarily to make the predictions for Y . Here we are more interested in understanding the relationship between the X and Y . Now f cannot be treated as the black box because we need to know its exact form. This is *inference*.

Machine Learning

Statistics




Parametric & Non-parametric methods

Parametric statistics: This statistical tests based on underlying the assumptions about data's distribution. In other words It is based on the parameters of the normal curve. Because parametric statistics are based on the normal curve data must meet certain assumptions or parametric statistics cannot be calculated. Before running any parametric statistics you should always be sure to test the assumptions for the tests that you are planning to run.

$$fX = \beta_0 + \beta_1 X_1 + \beta_2 X_2 + \dots + \beta_p X_p$$

As by the name nonparametric statistics are not based on parameters of the normal curve. Therefore if our data violate the assumptions of a usual parametric and nonparametric statistics might better define the data try running the nonparametric equivalent of the parametric test. We should also consider using nonparametric equivalent tests when we have limited sample sizes e.g. $n < 30$. Though the nonparametric statistical tests have more flexibility than do parametric statistical tests nonparametric tests are not as robust; therefore most statisticians recommend that when appropriate parametric statistics are preferred.



Prediction Accuracy and Model Interpretability:

Out of many methods that we use for the statistical learning some are less flexible and more restrictive. When inference is the goal then there are clear advantages of using the simple and relatively inflexible statistical learning methods. When we are only interested in the prediction we use flexible models available.




Q2. What is ANOVA?

Answer:

ANOVA: it stands for Analysis of Variance is an extremely important tool for analysis of data both One Way and Two Way ANOVA is used It is a statistical method to compare the population means of two or more groups by analyzing variance The variance would differ only when the means are significantly different

ANOVA test is the way to find out if survey or experiment results are significant In other words It helps us to figure out if we need to reject the null hypothesis or accept the alternate hypothesis We are testing groups to see if there s a difference between them Examples of when we might want to test different groups:


- The group of psychiatric patients are trying three different therapies: counseling medication and biofeedback We want to see if one therapy is better than the others
- The manufacturer has two different processes to make light bulbs if they want to know which one is better
- Students from the different colleges take the same exam We want to see if one college outperforms the other



Types of ANOVA:

- One-way ANOVA
- Two-way ANOVA

One-way ANOVA is the hypothesis test in which only one categorical variable or the single factor is taken into consideration With the help of F-distribution it enables us to compare means of three or more samples The Null hypothesis H_0 is the equity in all population means while an Alternative hypothesis is the difference in at least one mean



There are two-ways ANOVA examines the effect of two independent factors on a dependent variable. It also studies the inter-relationship between independent variables influencing the values of the dependent variable if any.



Q3. What is ANCOVA?

Answer:

Analysis of Covariance ANCOVA : It is the inclusion of the continuous variable in addition to the variables of interest – the dependent and independent variable – as means for the control. Because the ANCOVA is the extension of the ANOVA, the researcher can still assess main effects and the interactions to answer their research hypotheses. The difference between ANCOVA and an ANOVA is that an ANCOVA model includes the covariate that is correlated with dependent variable and means on dependent variable are adjusted due to effects the covariate has on it. Covariates can also

be used in many ANOVA based designs: such as between-subjects within-subjects repeated measures mixed between and within designs etc. Thus this technique answers the question

In simple terms The difference between ANOVA and the ANCOVA is the letter "C" which stands for 'covariance' Like ANOVA "Analysis of Covariance" ANCOVA has the single continuous response variable Unlike ANOVA ANCOVA compares the response variable by both the factor and a continuous independent variable example comparing test score by both 'level of education' and the 'number of hours spent in studying' The terms for the continuous independent variable IV used in the ANCOVA is "covariate"

Example of ANCOVA

ANCOVA EXAMPLE

Independent Variables

(Factor)

Level of Education
(High School, College Degree,
or Graduate Degree)


(Covariate)

Number of Hours
Spent Studying

Dependent Variable

(Response)

Test Score




Q4. What is MANOVA?

Answer:


MANOVA multivariate analysis of variance : It is a type of multivariate analysis used to analyze data that involves more than one dependent variable at a time. MANOVA allows us to test hypotheses regarding the effect of one or more independent variables on two or more dependent variables.

The obvious difference between ANOVA and the "Multivariate Analysis of Variance" MANOVA is the M which stands for multivariate. In basic terms MANOVA is an ANOVA with two or more continuous response variables. Like ANOVA, MANOVA has both the one-way flavor and a two-way flavor. The number of factor variables involved distinguish the one-way MANOVA from a two-way MANOVA.

ONE-WAY MANOVA EXAMPLE



TWO-WAY MANOVA EXAMPLE



When comparing the two or more continuous response variables by the single factor a one-way MANOVA is appropriate e.g. comparing test score and annual income together by level of

education. The two-way MANOVA also entails two or more continuous response variables but compares them by at least two factors e.g. comparing test score and annual income together by both level of education and zodiac sign.

Q5. What is MANCOVA?

Answer:

Multivariate analysis of covariance MANCOVA : It is a statistical technique that is the extension of analysis of covariance ANCOVA. It is the multivariate analysis of variance MANOVA with a covariate(s). In MANCOVA we assess for statistical differences on multiple continuous dependent variables by an independent grouping variable while controlling for a third variable called the covariate; multiple covariates can be used depending on the sample size. Covariates are added so that it can reduce error terms and so that the analysis eliminates the covariates effect on the relationship between the independent grouping variable and the continuous dependent variables.

ANOVA and ANCOVA the main difference between the MANOVA and MANCOVA is the C which again stands for the covariance. Both the MANOVA and MANCOVA feature two or more response variables but the key difference between the two is the nature of the IVs. While the MANOVA can include only factors an analysis evolves from MANOVA to MANCOVA when one or more covariates are added to the mix.

MANCOVA EXAMPLE

Independent Variables

Dependent Variables

(Factor)

(Response)

Level of Education
(High School, College Degree,
or Graduate Degree)

Test Score

(Covariate)

(Response)

Number of Hours
Spent Studying

Annual Income


Q6. Explain the differences between KNN classifier and KNN regression methods.

Answer:

They are quite similar. Given a value for K and a prediction point x_0 , KNN regression first identifies the K training observations that are closest to x_0 , represented by N_0 . It then estimates $f(x_0)$ using the average of all the training responses in N_0 . In other words,

$$\hat{f}(x_0) = \frac{1}{K} \sum_{x_i \in N_0} y_i$$

So the main difference is the fact that for the classifier approach, the algorithm assumes the outcome as the class of more presence, and on the regression approach, the response is the average value of the nearest neighbors.



Q7. What is t-test?

Answer:

To understand T-Test Distribution, consider the situation you want to compare the performance of two workers of your company by checking the average sales done by each of them or to compare the performance of a worker by comparing the average sales done by him with the standard value. In such situations of daily life, t-distribution is applicable.

A t-test is the type of inferential statistic used to determine if there is a significant difference between the means of two groups which may be related in certain features. It is mostly used when the data sets like the data set recorded as the outcome from flipping a coin 100 times would follow a normal distribution and may have unknown variances. A t-test is used as a hypothesis testing tool which allows testing of an assumption applicable to a population.

Understand t-test with Example: Let's say you have a cold and you try a naturopathic remedy. Your cold lasts a couple of days. The next time when you have a cold you buy an over-the-counter pharmaceutical and the cold lasts a week. You survey your friends and they all tell you that their colds were of a shorter duration, an average of 3 days, when they took the homeopathic remedy. What you want to know is, are these results repeatable? A t-test can tell you by comparing the means of the two groups and letting you know the probability of those results happening by chance.

Type	T-statistic	Degrees of freedom
------	-------------	--------------------

One-sample t-test $t = \frac{\bar{x} - \mu_0}{s/\sqrt{n}}$ $df = n - 1$

Paired t-test $t = \frac{\bar{X}_D - \mu_0}{s_D/\sqrt{n}}$. $df = n - 1$

OVERVIEW OF T-TESTS

T-test

Used to compare two samples to determine if they came from the same population.



Q8. What is Z-test?

Answer:

z-test: It is a statistical test used to determine whether the two population means are different when the variances are known and the sample size is large. The test statistic is assumed to have the normal distribution and nuisance parameters such as standard deviation should be known for an accurate z-test to be performed.

Another definition of Z-test: A Z-test is a type of hypothesis test. Hypothesis testing is just the way for you to figure out if results from a test are valid or repeatable. Example if someone said they had found the new drug that cures cancer you would want to be sure it was probably true. Hypothesis test will tell you if it's probably true or probably not true. A Z test is used when your data is approximately normally distributed.

Z-Tests Working :

Tests that can be conducted as the z-tests include one-sample location test a two-sample location test a paired difference test and a maximum likelihood estimate. Z-tests are related to t-tests but t-tests are best performed when an experiment has the small sample size. Also T-tests assumes the standard deviation is unknown while z-tests assumes that it is known. If the standard deviation of the population is unknown then the assumption of the sample variance equaling the population variance is made.

When we can run the Z-test :

Different types of tests are used in the statistics i.e f test chi-square test t-test. You would use a Z test if:

- Your sample size is greater than 30. Otherwise use a t-test.
- Data points should be independent from each other. Some other words one data point is not related or doesn't affect another data point.
- Your data should be normally distributed. However for large sample sizes over 30 this doesn't always matter.
- Your data should be randomly selected from a population where each item has an equal chance of being selected.
- Sample sizes should be equal if at all possible.

Z-TEST

◆ Formula to find the value of Z (z-test) is:

$$Z = \frac{\bar{x} - \mu_0}{\sigma / \sqrt{n}}$$

- ◆ \bar{x} = mean of sample
- ◆ μ_0 = mean of population
- ◆ σ = standard deviation of population
- ◆ n = no. of observations

Q9. What is Chi-Square test?


Answer:

Chi-square χ^2 statistic: It is a test that measures how expectations compare to actual observed data or model results. The data used in calculating a chi-square statistic must be random, raw, mutually exclusive, drawn from independent variables, and drawn from a large enough sample. For example, the results of tossing a coin 100 times meet these criteria.

Chi-square test is intended to test how it is that an observed distribution is due to chance. It is also called the "**goodness of fit**" statistic because it measures how well the observed distribution of the data fits with the distribution that is expected if the variables are independent.

Chi-square test is designed to analyze the **categorical** data. That means that the data has been counted and divided into categories. It will not work with parametric or continuous data such as height in inches. For example, if you want to test whether attending class influences how students perform on an exam using test scores from 0-100 as data would not be appropriate for a Chi-square test. However, arranging students into the categories "Pass" and "Fail" would. Additionally, the data in a Chi-square grid should not be in the form of percentages or anything other than frequency count data.

$$\chi^2_c = \sum \frac{(O_i - E_i)^2}{E_i}$$



Q10. What is correlation and the covariance in the statistics?

Answer:

The Covariance and Correlation are two mathematical concepts; these two approaches are widely used in the statistics. Both Correlation and the Covariance establish the relationship and also measures the dependency between the two random variables. The work is similar between these two in the mathematical terms they are different from each other.

Correlation: It is the statistical technique that can show whether and how strongly pairs of variables are related. For example height and weight are related; taller people tend to be heavier than shorter people. The relationship isn't perfect. People of the same height vary in weight and you can easily think of two people you know where the shorter one is heavier than the taller one. Nonetheless the average weight of people 5'5" is less than the average weight of people 5'6" and their average weight is less than that of people 5'7" etc. Correlation can tell you just how much of the variation in peoples' weights is related to their heights.

Correlation Formula


$$\rho_{xy} = \frac{\text{Cov}(r_x, r_y)}{\sigma_x \sigma_y}$$
 

Covariance: It measures the directional relationship between the returns on two assets. The positive covariance means that asset returns move together while a negative covariance means they move inversely. Covariance is calculated by analyzing at-return surprises standard deviations from the expected return or by multiplying the correlation between the two variables by the standard deviation of each variable.

Covariance Formula

For Population

$$\text{Cov}(x,y) = \frac{\sum (x_i - \bar{x}) * (y_i - \bar{y})}{N}$$

For Sample

$$\text{Cov}(x,y) = \frac{\sum (x_i - \bar{x}) * (y_i - \bar{y})}{(N - 1)}$$

**DATA SCIENCE
INTERVIEW
PREPARATION
(30 Days of Interview
Preparation)**

DAY 17

Q1. What is ERM (Empirical Risk Minimization)?

Answer:

Empirical risk minimization (ERM): It is a principle in statistical learning theory which defines a family of learning algorithms and is used to give theoretical bounds on their performance. The idea is that we don't know exactly how well an algorithm will work in practice (the true "risk") because we don't know the true distribution of data that the algorithm will work on but as an alternative we can measure its performance on a known set of training data.

We assumed that our samples come from this distribution and use our dataset as an approximation. If we compute the loss using the data points in our dataset it's called empirical risk. It is empirical and not true because we are using a dataset that's a subset of the whole population.


When our learning model is built we have to pick a function that minimizes the empirical risk that is the delta between predicted output and actual output for data points in the dataset. This process of finding this function is called empirical risk minimization (ERM). We want to minimize the true risk. We don't have information that allows us to achieve that so we hope that this empirical risk will almost be the same as the true empirical risk.

Let's get a better understanding by Example

We would want to build a model that can differentiate between a male and a female based on specific features. If we select 150 random people where women are really short and men are really tall then the model might incorrectly assume that height is the differentiating feature. For building a truly accurate model we have to gather all the women and men in the world to extract differentiating features. Unfortunately that is not possible! So we select a small number of people and hope that this sample is representative of the whole population.

$$R_{emp}[f] = \sum_{x \in X} \sum_{j=1}^2 c(x, y_j, f(x)) p_{emp}(y_j, x)$$

$$= \frac{1}{n} \sum_{i=1}^n c(x_i, y_i, f(x_i))$$





Q2. What is PAC (Probably Approximately Correct)?

Answer:

PAC: In computational learning theory probably approximately correct (PAC) learning is a framework for mathematical analysis of machine learning.

The learner receives samples and must have to pick a generalization function (called the *hypothesis*) from a specific class of possible functions. Our goal is that with high probability the selected function will have low generalization error. The learner must be able to learn the concept given any arbitrary approximation ratio probability of success or distribution of the samples.

Hypothesis class is PAC(Probably Approximately Correct) learnable if there exists a function **m_H** and algorithm that for any labeling function **f** distribution **D** over the domain of inputs **X** **delta** and **epsilon** that with **m ≥ m_H** produces a hypothesis **h** like that with probability **1-delta** it returns a **true error** lower than **epsilon**. Labeling function is nothing other than saying that we have a specific function **f** that labels the data in the domain.




Q3. What is ELMo?

Answer:

ELMo is a novel way to represent words in vectors or embeddings. These word embeddings help achieve state-of-the-art (SOTA) results in several NLP tasks:

Task	Previous SOTA	ELMo + Baseline
SQuAD	SAN	84.4
SNLI	Chen et al (2017)	88.6
SRL	He et al (2017)	81.7
Coref	Lee et al (2017)	70.4
NER	Peters et al (2017)	91.93 +/- 0.19
Sentiment (5-class)	McCann et al (2017)	53.7
		54.7 +/- 0.5

It is a deep contextualized word representation that models both complex characteristics of word use (e.g. syntax and semantics) and how these uses vary across linguistic contexts. These word vectors are learned functions of internal states of a deep biLM(bidirectional language model) which is pre-trained on large text corpus. They could be easily added to existing models and significantly improve state of the art across a broad range of challenging NLP problems including question answering, textual entailment and sentiment analysis.



Q4. What is Pragmatic Analysis in NLP?

Answer:

Pragmatic Analysis(PA): It deals with outside word knowledge which means understanding i.e external to documents and queries. PA that focuses on what was described is reinterpreted by what it actually meant deriving the various aspects of language that require real-world knowledge.

It deals with overall communicative and social content and its effect on interpretation. It means abstracting the meaningful use of language in situations. In this analysis the main focus always on what was said in reinterpreted on what is intended.

It helps users to discover this intended effect by applying a set of rules that characterize cooperative dialogues.

E.g. "close the window?" should be interpreted as a request instead of an order.


Personal	Organizational devices (Calls/Vocatives)
Request	Questions
Action	Answers/Responses
Permission	Repetition/Imitation
Offering/showing	Elicited identification
Descriptions	Routines
Statements (Internal reports)	Exclamations
Acknowledgements	Unclassified
Performatives	Double coded

Q5. What is Syntactic Parsing?

Answer:

Syntactic Parsing or Dependency Parsing: It is a task of recognizing a sentence and assigning a syntactic structure to it. Most Widely we used syntactic structure is the parse tree which can be generated using some parsing algorithms. These parse trees are useful in various applications like grammar checking or more importantly it plays a critical role in the semantic analysis stage. For example to answer the question *Who is the point guard for the LA Laker in the next game ?* we need to figure out its subject objects attributes to help us figure out that the user wants the point guard of the LA Lakers specifically for the next game.

Example:



Q6. What is ULMFiT?

Answer:


Transfer Learning in **NLP(Natural language Processing)** is an area that had not been explored with great success. But in May 2018 **Jeremy Howard** and **Sebastian Ruder** came up with the paper **Universal Language Model Fine-tuning for Text Classification(ULMFiT)** which explores the benefits of using a pre trained model on text classification. It proposes **ULMFiT(Universal Language Model Fine-tuning for Text Classification)** a transfer learning method that could be applied to any task in NLP. In this method outperforms the state-of-the-art on six text classification tasks.

ULMFiT uses a **regular LSTM** which is the state-of-the-art language model architecture (**AWD-LSTM**). The LSTM network has three layers. Single architecture is used throughout for pre-training as well as for fine-tuning.

ULMFiT achieves the state-of-the-art result using novel techniques like:


- Discriminative fine-tuning
- Slanted triangular learning rates
- Gradual unfreezing

Discriminative Fine-Tuning



Different layers of a neural network capture different types of information so they should be fine-tuned to varying extents. Instead of using the same learning rates for all layers of the model discriminative fine-tuning allows us to tune each layer with different learning rates.

Slanted triangular learning



The model should quickly converge to a suitable region of the parameter space in the beginning of training and then later refine its parameters. Using a constant learning rate throughout training is not the best way to achieve this behaviour. Instead Slanted Triangular Learning Rates (STLR) linearly increases the learning rate at first and then linearly decays it.

Gradual Unfreezing

Gradual unfreezing is the concept of unfreezing the layers gradually which avoids the catastrophic loss of knowledge possessed by the model. It first unfreezes the top layer and fine-tunes all the unfrozen layers for 1 epoch. It then unfreezes the next lower frozen layer and repeats until all the layers have been fine-tuned until convergence at the last iteration.

Q7. What is BERT?


Answer:

BERT (Bidirectional Encoder Representations from Transformers) is an open-sourced NLP pre-training model developed by researchers at Google in 2018. A direct descendant to GPT (Generalized Language Models) BERT has outperformed several models in NLP and provided top results in Question Answering Natural Language Inference (MNLI) and other frameworks.

What makes it unique from the rest of the model is that it is the first deeply bidirectional unsupervised language representation pre-trained using only a plain text corpus. Since it's open-sourced anyone with machine learning knowledge can easily build an NLP model without the need for sourcing massive datasets for training the model thus saving time energy knowledge and resources.

How does it work?

Traditional context-free models (like word2vec or GloVe) generate a single word embedding representation for each word in the vocabulary which means the word **right** would have the same context-free representation in **I m sure I m right** and **Take a right turn.** However BERT would represent based on both previous and next context making it bidirectional. While the concept of bidirectional was around for a long time BERT was first on its kind to successfully pre-train bidirectional in a deep neural network.




Q8.What is XLNet?

Answer:


XLNet is a BERT-like model instead of a totally different one. But it is an auspicious and potential one. In one word **XLNet is a generalized autoregressive pretraining method.**

Autoregressive (AR) language model: It is a kind of model that uses the context word to predict the next word. But here the context word is constrained to two directions either forward or backwards.



The advantages of AR language model are good at generative Natural language Process(NLP) tasks. Because when generating context usually is the forward direction. AR language model naturally works well on such NLP tasks.

But Autoregressive language model has some disadvantages and it only can use forward context or backward context which means it can't use forward and backward context at the same time.



The conceptual difference between BERT and XLNet. Transparent words are masked out so the model cannot rely on them. XLNet learns to predict the words in an arbitrary order but in an autoregressive, sequential manner (not necessarily left-to-right). BERT predicts all masked words simultaneously.

Q9. What is the transformer?

Answer:

Transformer: It is a deep machine learning model introduced in 2017 used primarily in the field of natural language processing (NLP). Like recurrent neural networks(RNN) It is designed to handle ordered sequences of data such as natural language for various tasks like machine translation and text summarization. However Unlike recurrent neural networks(RNN) Transformers do not require that the sequence be processed in the order. So if the data in question is a natural language the Transformer does not need to process the beginning of a sentence before it processes the end. Due to this feature the Transformer allows for much more parallelization than RNNs during training.

Transformers are developed to solve the problem of sequence transduction current neural networks. It means any task that transforms an input sequence to an output sequence. This includes speech recognition text-to-speech transformation etc.

For models to perform a sequence transduction it is necessary to have some sort of memory. example let us say that we are translating the following sentence to another language (French):

The Transformers is a Japanese band. That band was formed in 1968 during the height of the Japanese music history.

In the above example the word the band in the second sentence refers to the band The Transformers introduced in the first sentence. When you read about the band in the second sentence you know that it is referencing to the The Transformers band. That may be important for translation.

For translating other sentences like that a model needs to figure out these sort of dependencies and connections. Recurrent Neural Networks (RNNs) and Convolutional Neural Networks (CNNs) have been used to deal with this problem because of their properties.





Figure 1: The Transformer - model architecture.




Q10. What is Text summarization?

Answer:

Text summarization: It is the process of shortening a text document to create a summary of the significant points of the original document.

Types of Text Summarization Methods :

Text summarization methods can be classified into different types.




Example:

Source Text: Peter and Elizabeth took a taxi to attend the night party in the city.

While in the party, Elizabeth collapsed and was rushed to the hospital.

Summary: Elizabeth was hospitalized after attending a party with Peter.



**DATA SCIENCE
INTERVIEW
PREPARATION
(30 Days of Interview
Preparation)
Day-18**

Q1. What is Levenshtein Algorithm?

Answer:

Levenshtein distance is a string metric for measuring the difference between two sequences. The Levenshtein distance between two words is the minimum number of single-character edits (i.e. insertions, deletions or substitutions) required to change one word into the other.

Mathematically the Levenshtein distance between the two strings a and b (of length $|a|$ and $|b|$ respectively) is given by the formula $\text{lev}_a b(|a|, |b|)$ where :

$$\text{lev}_{a,b}(i,j) = \begin{cases} \max(i,j) & \text{if } \min(i,j) = 0, \\ \min \begin{cases} \text{lev}_{a,b}(i-1, j) + 1 \\ \text{lev}_{a,b}(i, j-1) + 1 \\ \text{lev}_{a,b}(i-1, j-1) + 1_{(a_i \neq b_j)} \end{cases} & \text{otherwise.} \end{cases}$$

Where $1_{(a_i \neq b_j)}$: This is the indicator function equal to zero when $a_i \neq b_j$ and equal to 1 otherwise and $\text{lev}_a b(i, j)$ is the distance between the first i characters of a and the first j characters of b .

Example:

The Levenshtein distance between "HONDA" and "HYUNDAI" is 3 since the following three edits change one into the other and there is no way to do it with fewer than three edits:

insertion
substitution
deletion

H		O	N	D	A	
H	Y	U	N	D	A	I

H	O		N	D	A	
H	Y	U	N	D	A	I

Q2. What is Soundex?

Answer:

Soundex attempts to find similar names or homophones using phonetic notation. The program retains letters according to detailed equations to match individual titles for purposes of ample volume research.

Soundex phonetic algorithm: Its indexes strings depend on their English pronunciation. The algorithm is used to describe homophones words that are pronounced the same but spelt differently.

Suppose we have the following sourceDF.

word1	word2
to	two
brake	break
here	hear
tree	free

Let's run below code and see how the soundex algorithm encodes the above words.

```
val actualDF = sourceDF.withColumn(  
    "w1_soundex",  
    soundex(col("word1"))  
)  
.withColumn(  
    "w2_soundex",  
    soundex(col("word2"))  
)  
  
actualDF.show()
```

word1	word2	w1_soundex	w2_soundex
to	two	T000	T000
brake	break	B620	B620
here	hear	H600	H600
tree	free	T600	F600

Let's summarize the above results:


- "two" and "to" both are encoded as T000
- "break" and "brake" both are encoded as B620
- "hear" and "here" both are encoded as H600
- "free" is encoded as F600 and "tree" is encoded as T600: Encodings are similar but word is different

The Soundex algorithm was often used to compare first names that were spelt differently.

Q3. What is Constituency parse?

Answer:

A constituency parse tree breaks a text into sub-phrases. Non-terminals in the tree are types of phrases the terminals are the words in the sentence and the edges are unlabeled. For a simple sentence "John sees Bill" a constituency parse would be:



Above approaches convert the parse tree into a sequence following a depth-first traversal to be able to apply sequence-to-sequence models to it. The linearized version of the above parse tree looks as follows: (S (N) (VP V N)).

Q4. What is LDA(Latent Dirichlet Allocation)?

Answer:

LDA: It is used to classify text in the document to a specific topic. LDA builds a topic per document model and words per topic model modelled as Dirichlet distributions.

- Each document is modeled as a distribution of topics and each topic is modelled as multinomial distribution of words.
- LDA assumes that every chunk of text we feed into it will contain words that are somehow related. Therefore choosing the right corpus of data is crucial.

- It also assumes documents are produced from a mixture of topics. Those topics then generate words based on their probability distribution.


The Bayesian version of PLSA is LDA. It uses Dirichlet priors for the word-topic and document-topic distributions lending itself to better generalization.

What LDA give us?

It is a probabilistic method. For every document the results give us a mixture of topics that make up the document. To be precise we can get probability distribution over the k topics for every document. Every word in the document is attributed to the particular topic with probability given by distribution.

These topics themselves were defined as probability distributions over vocabulary. Our results are two sets of probability distributions:

- The collection of distributions of topics for each document
- The collection of distributions of words for each topic.



Q5.What is LSA?

Answer:

Latent Semantic Analysis (LSA): It is a theory and the method for extract and represents the contextual usage meaning of words by statistical computation applied to large corpus of texts.


It is an information retrieval technique which analyzes and identifies the pattern in an unstructured collection of text and relationship between them.

Latent Semantic Analysis itself is an unsupervised way of uncovering synonyms in a collection of documents.

Why LSA(Latent Semantic Analysis)?

LSA is a technique for creating vector representation of the document. Having a vector representation of the document gives us a way to compare documents for their similarity by calculating the distance between vectors. In turn means we can do handy things such as classify documents to find out which of a set knows topics they most likely reside to.

Classification implies we have some known topics that we want to group documents into and that you have some labelled training data. If you're going to identify natural groupings of the documents without any labelled data you can use clustering




Q6. What is PLSA?

Answer:

PLSA stands for Probabilistic Latent Semantic Analysis uses a probabilistic method instead of SVD to tackle problem. The main idea is to find the probabilistic model with latent topics that we can *generate* data we observe in our document term matrix. Specifically we want a model $P(D|W)$ such that for any document d and word w $P(d|w)$ corresponds to that entry in document-term matrix.

Each document is found in the mixture of topics and each topic consists of the collection of words. PLSA adds the probabilistic spin to these assumptions:

- Given document d topic z is available in that document with the probability $P(z|d)$
- Given the topic z word w is drawn from z with probability $P(w|z)$



The joint probability of seeing the given document and word together is:

$$P(D, W) = P(D) \sum_Z P(Z|D)P(W|Z)$$

In the above case $P(D)$, $P(Z|D)$ and $P(W|Z)$ are the parameters of our models. $P(D)$ can be determined directly from corpus. $P(Z|D)$ and the $P(W|Z)$ are modelled as multinomial distributions and can be trained using the expectation-maximisation algorithm (EM).

Q7. What is LDA2Vec?

Answer:

It is inspired by LDA word2vec model is expanded to simultaneously learn word, document, topic and paragraph topic vectors.

Lda2vec is obtained by modifying the skip-gram word2vec variant. In the original skip-gram method the model is trained to predict context words based on a pivot word. In lda2vec the pivot word vector and a document vector are added to obtain a context vector. This context vector is then used to predict context words.

At the document level we know how to represent the text as mixtures of topics. At the word-level we typically used something like word2vec to obtain vector representations. It is an extension of word2vec and LDA that jointly learns word document and topic vectors.

How does it work?


It correctly builds on top of the skip-gram model of word2vec to generate word vectors. Neural net that learns word embedding by trying to use input word to predict enclosing context words.

With Lda2vec other than using the word vector directly to predict context words you leverage a context vector to make the predictions. Context vector is created as the sum of two other vectors: the word vector and the document vector.

The same skip-gram word2vec model generates the word vector. The document vector is most impressive. It is a really weighted combination of two other components:

- the document weight vector representing the weights of each topic in a document
- Topic matrix represents each topic and its corresponding vector embedding.

Together a document vector and word vector generate context vectors for each word in a document. Lda2vec power lies in the fact that it not only learns word embeddings for words; it simultaneously learns topic representations and document representations as well.



Q8. What is Expectation-Maximization Algorithm(EM)?

Answer:

The Expectation-Maximization Algorithm in short EM algorithm is an approach for maximum likelihood estimation in the presence of latent variables.


This algorithm is an iterative approach that cycles between two modes. The first mode attempts to predict the missing or latent variables called the estimation-step or E-step. The second mode attempts to optimise the parameters of the model to explain the data best called the maximization-step or M-step.

- **E-Step.** Estimate the missing variables in the dataset.
- **M-Step.** Maximize the parameters of the model in the presence of the data.

The EM algorithm can be applied quite widely although it is perhaps most well known in machine learning for use in unsupervised learning problems such as density estimation and clustering.

For detail explanation of EM let us first consider this example. Say that we are in a school and interested to learn the height distribution of female and male students in the school. The most sensible thing to do as we probably would agree with me is to randomly take a sample of N students of both genders collect their height information and estimate the mean and standard deviation for male and female separately by way of maximum likelihood method.

Now say that you are not able to know the gender of student while we collect their height information and so there are two things you have to guess/estimate: (1) whether the individual sample of height information belongs to a male or a female and (2) the parameters () for each gender which is now unobservable. This is tricky because only with the knowledge of who belongs to which group can we make reasonable estimates of the group parameters separately. Similarly only if we know the parameters that define the groups can we assign a subject properly. How do you break out of this infinite loop? Well EM algorithm just says to start with initial random guesses.



Q9.What is Text classification in NLP?


Answer:

Text classification is also known as text tagging or text categorization is a process of categorizing text into organized groups. By using NLP text classification can automatically analyze text and then assign a set of pre-defined tags or categories based on content.

Unstructured text is everywhere on the internet such as emails chat conversations websites and the social media but it's hard to extract value from given data unless it's organized in a certain way. Doing so used to be a difficult and expensive process since it required spending time and resources to manually sort the data or creating handcrafted rules that are difficult to maintain. Text classifiers with NLP have proven to be a great alternative to structure textual data in a fast cost-effective and scalable way.

Text classification is becoming an increasingly important part of businesses as it allows us to get insights from data and automate business processes quickly. Some of the most common examples and the use cases for automatic text classification include the following:

- **Sentiment Analysis:** It is the process of understanding if a given text is talking positively or negatively about a given subject (e.g. for brand monitoring purposes).
- **Topic Detection:** In this the task of identifying the theme or topic of a piece of text (e.g. know if a product review is about Ease of Use Customer Support or Pricing when analysing customer feedback).
- **Language Detection:** the procedure of detecting the language of a given text (e.g. know if an incoming support ticket is written in English or Spanish for automatically routing tickets to the appropriate team).



Q10. What is Word Sense Disambiguation (WSD)?

Answer:

WSD (Word Sense Disambiguation) is a solution to the ambiguity which arises due to different meaning of words in a different context.

In natural language processing **word sense disambiguation** (WSD) is the problem of determining which "sense" (meaning) of a word is activated by the use of the word in a particular context, a process which appears to be mostly unconscious in people. WSD is the natural classification problem: Given a word and its possible senses as defined by the dictionary classify an occurrence of the word in the context into one or more of its sense classes. The features of the context (such as the neighbouring words) provide the evidence for classification.

For example consider these two below sentences.


The **bank** will not be accepting the cash on Saturdays.

The river overflowed the **bank**.

The word **bank** in the given sentence refers to commercial (finance) banks while in the second sentence it refers to a riverbank. The uncertainty that arises due to this is tough for the machine to detect and resolve. Detection of change is the first issue and fixing it and displaying the correct output is the second issue.

Word Sense disambiguation

I need new batteries for my mouse.



**DATA SCIENCE
INTERVIEW
PREPARATION
(30 Days of Interview
Preparation)**

DAY 19

Q1. What is LSI(Latent Semantic Indexing)?

Answer:


Latent Semantic Indexing (LSI): It is an indexing and retrieval method that uses a mathematical technique called SVD(Singular value decomposition) to find patterns in relationships between terms and concepts contained in an unstructured collection of text. It is based on the principle that words that are used in the same contexts tend to have similar meanings.

For example Tiger and Woods are associated with men instead of an animal and a Wood Parris and Hilton are associated with the singer

Example:

If you use LSI to index a collection of articles and the words fan and regulator appear together frequently enough the search algorithm would notice that the two terms are semantically close. A search for fan will therefore return a set of items containing that phrase but also items that contain just the word regulator. It doesn't understand word distance but by examining a sufficient number of documents it only knows the two terms are interrelated. It then uses that information to provide an expanded set of results with better recall than an understandable keyword search.

The diagram below describes the effect between LSI and keyword searches. W stands for a document.





Q2. What is Named Entity Recognition? And tell some use cases of NER?

Answer:

Named-entity recognition (NER): It is also known as entity extraction and entity identification is a subtask of information extraction that explores to locate and classify atomic elements in text into predefined categories like the names of persons organizations places expressions of times quantities monetary values percentages and more

In each text document particular terms represent specific entities that are more informative and have a different context. These entities are called named entities which more accurately refer to conditions that represent real-world objects like people places organizations or institutions and so on which are often expressed by proper names. The naive approach could be to find these by having a look at the noun phrases in text documents. It also is known as entity chunking/extraction which is a popular technique used in information extraction to analyze and segment the named entities and categorize or classify them under various predefined classes

Named Entity Recognition use-case

- **Classifying content for news providers-**

NER can automatically scan entire articles and reveal which are the significant people organizations and places discussed in them. Knowing the relevant tags for each item helps in automatically categorizing the articles in defined hierarchies and enable smooth content discovery

- **Customer Support:**

Let's say we are handling the customer support department of an electronics store with multiple branches worldwide; we go through a number of mentions in our customers' feedback. Such as this for instance

Now if we pass it through the Named Entity Recognition API it pulls out the entities Bangalore (location) and Fitbit (Product). This can be then used to categorize the complaint and assign it to the relevant department within the organization that should be handling this.



Figure 1: An example of NER application on an example text

Q3. What is perplexity?

Answer:

Perplexity: It is a measurement of how well a probability model predicts a sample. In the context of NLP, perplexity (Confusion) is one way to evaluate language models.

The term perplexity has three closely related meanings. It is a measure of how easy a probability distribution is to predict. It is a measure of how variable a prediction model is. And it is a measure of prediction error. The third meaning of perplexity is calculated slightly differently, but all three have the same fundamental idea.

Dan Jurafsky
Perplexity

The best language model is one that best predicts an unseen test set

- Gives the highest $P(\text{sentence})$

Perplexity is the inverse probability of the test set, normalized by the number of words:

$$\text{PP}(W) = P(w_1 w_2 \dots w_N)^{\frac{1}{N}}$$

$$= \sqrt[N]{\frac{1}{P(w_1 w_2 \dots w_N)}}$$

Chain rule:

$$\text{PP}(W) = \sqrt[N]{\prod_{i=1}^N \frac{1}{P(w_i | w_1 \dots w_{i-1})}}$$

For bigrams:

$$\text{PP}(W) = \sqrt[N]{\prod_{i=1}^N \frac{1}{P(w_i | w_{i-1})}}$$

Minimizing perplexity is the same as maximizing probability

Q4. What is the language model?

Answer:

Language Modelling (LM): It is one of the essential parts of modern NLP. There are many sorts of applications for Language Modelling like Machine Translation, Spell Correction, Speech Recognition, Summarization, Question Answering, Sentiment analysis etc. Each of those tasks requires the use of the language model. The language model is needed to represent the text to a form understandable from the machine point of view.

The statistical language model is a probability distribution over a series of words. Given such a series say of length m , it assigns a probability to the whole series.

It provides context to distinguish between phrases and words that sound similar. For example in American English, the phrases "wreck a nice beach" and "recognize speech" sound alike but mean different things.

Data sparsity is a significant problem in building language models. Most possible word sequences are not noticed in training. One solution is to make the inference that the probability of a word only depends on the previous n words. This is called as an n -gram model or unigram model when $n = 1$. The unigram model is also known as the bag of words model.

How does this Language Model help in NLP Tasks?

The probabilities restoration by a language model is most useful to compare the likelihood that different sentences are "good sentences". This was useful in many practical tasks, for example:

Spell checking: You observe a word that is not identified as a known word as part of a sentence. Using the edit distance algorithm, we find the closest known words to the unknown words. These are the candidate corrections. For example, we observe the word "wurd" in the context of the sentence "I like to write this wurd". The candidate corrections are ["word", "weird", "wind"]. How can we select among these candidates the most likely correction for the suspected error "weird"?

Automatic Speech Recognition: we receive as input a string of phonemes; a first model predicts for sub-sequences of the stream of phonemes candidate words; the language model helps in ranking the most likely sequence of words compatible with the candidate words produced by the acoustic model.

Machine Translation: each word from the source language is mapped to multiple candidate words in the target language; the language model in the target language can rank the most likely sequence of candidate target words.


Q5. What is Word Embedding?

Answer:

A word embedding is a learned representation for text where words that have the same meaning have a similar observation

It is basically a form of word representation that bridges the human understanding of language to that of a machine. Word embeddings divide representations of text in an n-dimensional space. These are essential for solving most NLP problems.

And the other point worth considering is how we obtain word embeddings as no two sets of word embeddings are similar. Word embeddings aren't random; they're developed by training the neural network. A recent powerful word embedding usage comes from Google named Word2Vec which is trained by predicting several words that appear next to other words in a language. For example, the word "cat" the neural network would predict the words like "kitten" and "feline". This intuition of words coming out "near" each other allows us to place them in vector space.



Q6. Do you have an idea about fastText?

Answer:

fastText: It is another word embedding method that is an extension of the word2vec model. Alternatively learning vectors for words directly. It represents each word as an n-gram of characters. So for example take the word `artificial` with $n=3$ the fastText representation of this word is `<ar art rti tif ifi fic ici ical al>` where the angular brackets indicate the beginning and end of the word.

This helps to capture the meaning of shorter words and grant the embeddings to understand prefixes and suffixes. Once the word has been showed using character skip-grams a n-gram model is trained to learn the embeddings. This model is acknowledged to be a bag of words model with a sliding

window over a word because no internal structure of the word is taken into account. As long as the characters are within this window, the order of the n-grams doesn't matter.

fastText works well with rare words. So even if a word wasn't seen during training, it can be broken down into n-grams to get its embeddings.

Word2vec and GloVe both fail to provide any vector representation for words that are not in the model dictionary. This is a huge advantage of this method.



Q7. What is GloVe?

Answer:

GloVe(global vectors) is for word representation. GloVe is an unsupervised learning algorithm developed by Stanford for achieving word embeddings by aggregating a global word-word co-occurrence matrix from a corpus. The resulting embeddings show interesting linear substructures of the word in vector space.

The GloVe model produces a vector space with meaningful substructure as evidenced by its performance of 75% on a new word analogy task. It also outperforms related models on similarity tasks and named entity recognition.

How GloVe find meaning in statistics?

Produces a vector space with meaningful substructure as evidenced by its performance of 75% on a new word analogy task. It also outperforms related models on similarity tasks and named entity recognition.


GloVe aims to achieve two goals:

- (1) Create word vectors that **capture meaning in vector space**
- (2) Takes advantage of **global count statistics** instead of only local information

Unlike word2vec which learns by streaming sentences GloVe determines based on a **co-occurrence matrix** and trains word vectors so their differences predict **co-occurrence ratios**

GloVe weights the loss based on word frequency

Somewhat surprisingly word2vec and GloVe turn out to be remarkably similar despite starting off from entirely different starting points



Q8. Explain Gensim?

Answer:


Gensim: It is billed as a Natural Language Processing package that does Topic Modeling for Humans But its practically much more than that

If you are unfamiliar with topic modeling it is a technique to extract the underlying topics from large volumes of text Gensim provides algorithms like LDA and LSI (which we already seen in previous interview questions) and the necessary sophistication to built high-quality topic models

It is an excellent library package for processing texts working with word vector models (such as FastText Word2Vec etc) and for building the topic models. Another significant advantage with gensim is: it lets us handle large text files without having to load the entire file in memory.


We can also tell as It is an open-source library for unsupervised topic modeling and natural language processing using modern statistical machine learning.

Gensim is implemented in Python and Cython. Gensim is designed to handle extensive text collections using data streaming and incremental online algorithms which differentiates it from most other machine learning software packages that target only in-memory processing.



Q9. What is Encoder-Decoder Architecture?

Answer:



The encoder-decoder architecture consists of two main parts :

- **Encoder:**

Encoder simply takes the input data and trains on it then it passes the final state of its recurrent layer as an initial state to the first recurrent layer of the decoder part

Encoder input : English sentences

Encoder initial state : It depends on the initializer we use


- **Decoder :**


The decoder takes the final state of encoder's final recurrent layer and uses it as an initial state to its initial recurrent layer the input of the decoder is sequences that we want to get French sentences

Decoder input : French sentences

Decoder initial state : The last state of encoder's last recurrent layer

Some more example for better understanding:






Q10. What is Context2Vec?

Answer:

Assume a case where you have a sentence like I can't find May. Word May maybe refers to a month's name or a person's name. You use the words surround it (context) to help yourself to determine the best suitable option. Actually this problem refers to the Word Sense Disambiguation task on which you investigate the actual semantics of the word based on several semantic and linguistic techniques. The Context2Vec idea is taken from the original CBOW Word2Vec model but instead of relying on averaging the embedding of the words it relies on a much more complex parametric model that is based on one layer of Bi-LSTM. Figure 1 shows the architecture of the CBOW model.

Figure 1



Context2Vec applied the same concept of windowing but instead of using a simple average function it uses 3 stages to learn complex parametric networks

- A Bi-LSTM layer that takes left-to-right and right-to-left representations
- A feedforward network that takes the concatenated hidden representation and produces a hidden representation through learning the network parameters
- Finally we apply the objective function to the network output




Figure 1: *word2vec* and *context2vec* architectures.

We used the Word2Vec negative sampling idea to get better performance while calculating the loss value

The following are some samples of the closest words to a given context

Sentential Context	Closest target words
This [] is due	item, fact-sheet, offer, pack, card
This [] is due not just to mere luck	offer, suggestion, announcement, item, prize
This [] is due not just to mere luck, but to outstanding work and dedication	award, prize, turnabout, offer, gift
[] is due not just to mere luck, but to outstanding work and dedication	it, success, this, victory, prize-money

Table 1: Closest target words to various sentential contexts, illustrating *context2vec*'s sensitivity to long range dependencies, and both sides of the target word.

**DATA SCIENCE
INTERVIEW
PREPARATION
(30 Days of Interview
Preparation)**

DAY 20

Q1. Do you have any idea about Event2Mind in NLP?


Answer:

Yes it is based on NLP research paper to understand the common-sense inference from sentences

Event2Mind: Common-sense Inference on Events, Intents, and Reactions

The study of Commonsense Reasoning in NLP deals with teaching computers how to gain and employ common sense knowledge NLP systems require common sense to adapt quickly and understand humans as we talk to each other in a natural environment

This paper proposes a new task to teach systems commonsense reasoning: given an event described in a short event phrase (e.g PersonX drinks coffee in the morning) the researchers teach a system to reason about the likely intents (PersonX wants to stay awake) and reactions (PersonX feels alert) of the event's participants



Understanding a narrative requires common-sense reasoning about the mental states of people in relation to events. For example if Robert is dragging his feet at work pragmatic implications about Robert's intent are that Robert wants to avoid doing things (Above Fig). You can also infer that Robert's emotional reaction might be feeling bored or lazy. Furthermore while not explicitly mentioned you can assume that people other than Robert are affected by the situation and these people are likely to feel impatient or frustrated.

This type of pragmatic inference can likely be useful for a wide range of NLP applications that require accurate anticipation of people's intents and emotional reactions even when they are not expressly mentioned. For example an ideal dialogue system should react in empathetic ways by reasoning about the human user's mental state based on the events the user has experienced without the user explicitly stating how they are feeling. Furthermore advertisement systems on social media should be able to reason about the emotional reactions of people after events such as mass shootings and remove ads for guns which might increase social distress. Also the pragmatic inference is a necessary step toward automatic narrative understanding and generation. However this type of commonsense social reasoning goes far beyond the widely studied entailment tasks and thus falls outside the scope of existing benchmarks.

Q2. What is SWAG in NLP?

Answer:

SWAG stands for **Situations with Adversarial Generations** is a dataset consisting of 113k multiple-choice questions about a rich spectrum of grounded situations.

Swag: A Large Scale Adversarial Dataset for Grounded Commonsense Inference

According to NLP research paper on SWAG is Given a partial description like he opened the hood of the car humans can reason about the situation and anticipate what might come next (then he examined the engine) In this paper you introduce the task of grounded commonsense inference unifying natural language inference(NLI) and common-sense reasoning

We present SWAG a dataset with 113k multiple-choice questions about the rich spectrum of grounded positions To address recurring challenges of annotation artifacts and human biases found in many existing datasets we propose AF(Adversarial Filtering) a novel procedure that constructs a de-biased dataset by iteratively training an ensemble of stylistic classifiers and using them to filter the data To account for the aggressive adversarial filtering we use state-of-the-art language models to oversample a diverse set of potential counterfactuals massively Empirical results present that while humans can solve the resulting inference problems with high accuracy (88%) various competitive models make an effort on our task We provide a comprehensive analysis that indicates significant opportunities for future research

When we read a tale we bring to it a large body of implied knowledge about the physical world For instance given the context on stage a man takes a seat at the piano we can easily infer what the situation might look like: a man is giving a piano performance with a crowd watching him. We can furthermore infer his likely next action: he will most likely set his fingers on the piano key and start playing

This type of natural language inference(NLI) requires common-sense reasoning substantially broadening the scope of prior work that focused primarily on linguistic entailment Whereas the dominant entailment paradigm asks if 2 natural language sentences (the premise and the hypothesis) describe the same set of possible worlds here we focus on whether a (multiple-choice) ending represents a possible (*future*) world that can a from the situation described in the premise even when it is not strictly entailed Making such inference necessitates a rich understanding of everyday physical conditions including object affordances and frame semantics

On stage, a woman takes a seat  at the piano. She

- a) sits on a bench as her sister plays with the doll.
- b) smiles with someone as the music plays.
- c) is in the crowd, watching the dancers.
- d) nervously sets her fingers on the keys.**

A girl is going across a set of monkey bars. She

- a) jumps up across the monkey bars,
- b) struggles onto the monkey bars to grab her head.
- c) gets to the end and stands on a wooden plank.**
- d) jumps up and does a back flip.

The woman is now blow drying the dog. The dog

- a) is placed in the kennel next to a woman's feet.**
- b) washes her face with the shampoo.
- c) walks into frame and walks towards the dog.
- d) tried to cut her face, so she is trying to do something very close to her face.

Table 1: Examples from Swag; the correct answer is **bolded**. Adversarial Filtering ensures that stylistic models find all options equally appealing.

Q3. What is the Pix2Pix network?

Answer:

Pix2Pix network: It is a Conditional GANs (cGAN) that learn the mapping from an input image to output an image





Image-To-Image Translation is the process for translating one representation of the image into another representation

The image-to-image translation is another example of a task that GANs (Generative Adversarial Networks) are ideally suited for. These are tasks in which it is nearly impossible to hard-code a loss function. Studies on GANs are concerned with novel image synthesis translating from a random vector z into an image. Image-to-Image translation converts one image to another like the edges of the bag below to the photo image. Another exciting example of this is shown below:



In Pix2Pix Dual Objective Function with an Adversarial and L1 Loss

A naive way to do Image-to-Image translation would be to discard the adversarial framework altogether. A source image would just be passed through a parametric function and the difference in the resulting image and the ground truth output would be used to update the weights of the network. However, designing this loss function with standard distance measures such as L1 and L2 will fail to capture many of the essential distinctive characteristics between these images. However,

authors do find some value to the L1 loss function as a weighted sidekick to the adversarial loss function

The Conditional-Adversarial Loss (Generator versus Discriminator) is very popularly formatted as follows:

$$\begin{aligned}\mathcal{L}_{cGAN}(G, D) = & \mathbb{E}_{x,y}[\log D(x, y)] + \\ & \mathbb{E}_{x,z}[\log(1 - D(x, G(x, z)))]\end{aligned}$$

The L1 loss function previously mentioned is shown below:

$$\mathcal{L}_{L1}(G) = \mathbb{E}_{x,y,z}[\|y - G(x, z)\|_1].$$

Combining these functions results in:

$$G^* = \arg \min_G \max_D \mathcal{L}_{cGAN}(G, D) + \lambda \mathcal{L}_{L1}(G).$$


In the experiments the authors report that they found the most success with the lambda parameter equal to 100

Q4. Explain UNet Architecture?

Answer:


U-Net architecture: It is built upon the Fully Convolutional Network and modified in a way that it yields better segmentation in medical imaging. Compared to FCN-8 the two main differences are (a) U-net is symmetric and (b) the skip connections between the downsampling path and upsampling path apply a concatenation operator instead of a sum. These skip connections intend to provide local information to the global information while upsampling. Because of its symmetry the network has a large number of feature maps in the upsampling path which allows transferring information. By comparison the underlying FCN architecture only had the *number of classes* feature maps in its upsampling way.

How does it work?



The UNet architecture looks like a U which justifies its name. This UNet architecture consists of 3 sections: The contraction, the bottleneck and the expansion section. The contraction section is made of many contraction blocks. Each block takes an input that applies two 3X3 convolution layers followed by a 2X2 max pooling. The number of features or kernel maps after each block doubles so that UNet architecture can learn complex structures. Bottommost layer mediates between the contraction layer and the expansion layer. It uses two 3X3 CNN layers followed by 2X2 up convolution layer.

But the heart of this architecture lies in the expansion section. Similar to the contraction layer, it also has several expansion blocks. Each block passes input to two 3X3 CNN layers followed by a 2X2 upsampling layer. After each block, the number of feature maps used by the convolutional layer get halved to maintain symmetry. However, every time input is also appended by feature maps of the corresponding contraction layer. This action would ensure that features that are learned while contracting the image will be used to reconstruct it. The number of expansion blocks is as same as the number of contraction blocks. After that, the resultant mapping passes through another 3X3 CNN layer with the number of feature maps equal to the number of segments desired.



Q5. What is pair2vec?

Answer:


This paper pre-trains *word pair representations* by maximizing pointwise mutual information of pairs of words with their context. This encourages a model to learn more meaningful representations of word pairs than with more general objectives like modeling. The pre-trained representations are useful in tasks like SQuAD and MultiNLI that require cross-sentence inference. You can expect to see more pretraining tasks that capture properties particularly suited to specific downstream tasks and are complementary to more general-purpose tasks like language modeling.

Reasoning about implied relationships between pairs of words is crucial for cross-sentence inference problems like question answering (QA) and natural language inference (NLI). In NLI, e.g., given a premise such as *golf is prohibitively expensive*, inferring that the hypothesis *golf is a cheap pastime* is a contradiction requires one to know that *expensive* and *cheap* are antonyms. Recent work has shown that current models which rely heavily on unsupervised single-word embeddings struggle to grasp such relationships. In this pair2vec paper, we show that they can be learned with word pair2vec (pair vector) which are trained unsupervised at a huge scale and which significantly improve performance when added to existing cross-sentence attention mechanisms.

X	Y	Contexts
hot	cold	with X and Y baths too X or too Y neither X nor Y in X, Y
Portland	Oregon	the X metropolitan area in Y X International Airport in Y
crop	wheat	food X are maize, Y, etc dry X, such as Y, more X circles appeared in Y fields
Android	Google	X OS comes with Y play the X team at Y X is developed by Y

Table 1: Example word pairs (italicized) and their contexts (Wikipedia).

Unlike single word representations which are typically trained by modeling the co-occurrence of a target word x with its context c our word-pair representations are learned by modeling the three-way co-occurrence between two words (x, y) and the context c that ties them together as illustrated in above Table While similar training signal has been used to learn models for ontology construction and knowledge base completion this paper shows for the first time that considerable scale learning of pairwise embeddings can be used to improve the performance of neural cross-sentence inference models directly



Q6. What is Meta-Learning?

Answer:


Meta-learning: It is an exciting area of research that tackles the problem of learning to learn. The goal is to design models that can learn new skills or fastly to adapt to new environments with minimum training examples. Not only does this dramatically speed up and improve the design of ML(Machine Learning) pipelines or neural architectures but it also allows us to replace hand-engineered algorithms with novel approaches learned in a data-driven way.

The goal of meta-learning is to train the model on a variety of learning tasks such that it can solve new learning tasks with only a small number of training samples. It tends to focus on finding **model agnostic** solutions whereas multi-task learning remains deeply tied to model architecture.

Thus meta-level AI algorithms make AI systems:

- Learn faster
- Generalizable to many tasks
- Adaptable to environmental changes like in Reinforcement Learning

One can solve any problem with a single model but meta-learning should not be confused with one-shot learning.



Q7. What is ALiPy(Active Learning in Python)?


Answer:

Supervised ML methods usually require a large set of labeled examples for model training. However in many real applications there are ample unlabeled data but limited labeled data; and acquisition of labels is costly. Active learning (AL) reduces labeling costs by iteratively selecting the most valuable data to query their labels from the annotator.

Active learning is the leading approach to learning with limited labeled data. It tries to reduce human efforts on data annotation by actively querying the most prominent examples.

ALiPy is a Python toolbox for active learning(AL) which is suitable for various users. On the one hand the entire process of active learning has been well implemented. Users can efficiently perform experiments by many lines of codes to finish the entire process from data pre-processes to

result in visualization. More than 20 commonly used active learning(AL) methods have been implemented in the toolbox providing users many choices.




Q8.What is the Lingvo model?

Answer:

Lingvo: It is a Tensorflow framework offering a complete solution for collaborative deep learning research with a particular focus towards sequence-to-sequence models. These models are composed of modular building blocks that are flexible and easily extensible and experiment configurations are centralized and highly customizable. Distributed training and quantized inference are supported directly within a framework and it contains existing implementations of an ample number of utilities helper functions and newest research ideas. This model has been used in collaboration by dozens of researchers in more than 20 papers over the last two years.

Why does this Lingvo research matter?

The process of establishing a new deep learning(DL) system is quite complicated. It involves exploring an ample space of design choices involving training data, data processing logic, the size and type of model components, the optimization procedures and the path to deployment. This complexity requires the framework that quickly facilitates the production of new combinations and the modifications from existing documents and experiments and shares these new results. It is a workspace ready to be used by deep learning researchers or developers. Nguyen Says: We have researchers working on state-of-the-art(SOTA) products and research algorithms basing their research off of the same codebase. This ensures that code is battle-tested. Our collective experience is encoded in means of good defaults and primitives that we have found useful over these tasks.



Q9. What is Dropout Neural Networks?

Answer:


The term **dropout** refers to dropping out units (both hidden and visible) in a neural network

At each training stage individual nodes are either dropped out of the net with probability $1-p$ or kept with probability p so that a reduced network is left; incoming and outgoing edges to a dropped-out node are also removed

Why do we need Dropout?

The answer to these questions is to prevent over-fitting

A fully connected layer occupies most of the parameters and hence neurons develop co-dependency amongst each other during training which curbs the individual power of each neuron leading to over-fitting of training data




Q10. What is GAN?

Answer:

A generative adversarial network (GAN): It is a class of machine learning systems invented by Ian Goodfellow and his colleagues in 2014. Two neural networks are contesting with each other in a game (in the idea of game theory often but not always in the form of a zero-sum game). Given a training set this technique learns to generate new data with the same statistics as the training set. E.g. a GAN trained on photographs can produce original pictures that look at least superficially authentic to human observers having many realistic characteristics. Though initially proposed as a form of a generative model for unsupervised learning, GANs have also proven useful for semi-supervised learning^[2], fully supervised learning and reinforcement learning.

Example of GAN



- Given an image of a face the network can construct an image that represents how that person could look when they are old

Generative Adversarial Networks takes up a game-theoretic approach unlike a conventional neural network. The network learns to generate from a training distribution through a 2-player game. The two entities are Generator and Discriminator. These two adversaries are in constant battle throughout the training process.

**DATA SCIENCE
INTERVIEW
PREPARATION
(30 Days of Interview
Preparation)**

Day21

Q1. Explain Grad-CAM architecture?

Answer:

According to the research paper We propose a technique for making Convolutional Neural Network CNN -based models more transparent by visualizing input regions that are important for predictions producing *visual explanations* Our approach is called Gradient-weighted Class Activation Mapping Grad-CAM which uses class-specific gradient information to localize the crucial regions These localizations are combined with the existing pixel-space visualizations to create a new high-resolution and class-discriminative display called the Guided Grad-CAM These methods help better to understand CNN-based models including image captioning and the apparent question answering VQA models We evaluate our visual explanations by measuring the ability to discriminate between the classes and to inspire trust in humans and their correlation with the occlusion maps Grad-CAM provides a new way to understand the CNN-based models

A technique for making CNN Convolutional Neural Network -based models more transparent by visualizing the regions of input that are important for predictions from these models or visual explanations


Guided Grad-CAM for "Cat"



Guided Grad-CAM for "Dog"



This visualization is both high-resolution when the class of interest is tiger cat it identifies crucial tiger cat features like stripes pointy ears and eyes and class-discriminative it shows the tiger cat but not the boxer dog




Q2.Explain squeeze-net architecture?

Answer:


Nowadays technology is at its peak. Self-driving cars and IoT is going to be household talks in the next few years to come. Therefore everything is controlled remotely say e.g. in self-driving cars we will need our system to communicate with the servers regularly. So accordingly if we have a model that has a small size then we can quickly deploy it in the cloud. So that's why we needed an architecture that is less in size and also achieves the same level of accuracy that other architecture achieves.

It's Architecture

- **Replace 3x3 filters with 1x1 filter-** We plan to use the maximum number of x filters as using a X filter rather than a 3x3 filter can reduce the number of parameters by $9X$. We may think that replacing 3x3 filters with X filters may perform badly as it has less information to work on. But this is not a case. Typically 3x3 filter may capture the spatial information of pixels close to each other while the X filter zeros in on pixel and captures features amongst its channels.
- **Decrease number of input channels to 3x3 filters-** to maintain a small total number of parameters in a CNN and it is crucial not only to decrease the number of 3x3 filters but also to decrease the number of input channels to 3x3 filters. We reduce the number of input channels to 3x3 filters using *squeeze layers*. The author of this paper has used a term called the *fire module*, in which there is a squeeze layer and an expanded layer. In the squeeze layer we are using X filters while in the expanded layer we are using a combo of 3x3 filters and X filters. The author is trying to limit the number of inputs to 3x3 filters to reduce the number of parameters in the layer.



- **Downsample late in a network so that convolution layers have a large activation map-** Having got an intuition about contracting the sheer number of parameters we are working with how the model is getting most out of the remaining set of parameters The author in this paper has downsampled the feature map in later layers and this increases the accuracy But this is an excellent contrast to networks like VGG where a large feature map is taken and then it gets smaller as network approach towards the end This different approach is too interesting and they cite the [paper by K He and H Sun](#) that similarly applies delayed downsampling that leads to higher classification accuracy
This architecture consists of the fire module which enables it to bring down the number of parameters




And other thing that surprises me is the lack of fully connected layers or dense layers at the end which one will see in a typical CNN architecture The dense layers in the end learn all the relationships between the high-level features and the classes it is trying to identify The fully connected layers are designed to learn that noses and ears make up a face and wheels and lights indicate cars However in this architecture that extra learning step seems to be embedded within the transformations between various fire modules

CNN architecture	Compression Approach	Data Type	Original → Compressed Model Size	Reduction in Model Size vs. AlexNet	Top-1 ImageNet Accuracy	Top-5 ImageNet Accuracy
AlexNet	None (baseline)	32 bit	240MB	1x	57.3%	80.3%
AlexNet	SVD [3]	32 bit	240MB → 48MB	5x	56.0%	79.4%
AlexNet	Network Pruning [13]	32 bit	240MB → 27MB	9x	57.2%	80.3%
AlexNet	Deep Compression [10]	5-8 bit	240MB → 6.9MB	35x	57.2%	80.3%
SqueezeNet (ours)	None	32 bit	4.8MB	50x	57.5%	80.3%
SqueezeNet (ours)	Deep Compression	8 bit	4.8MB → 0.66MB	363x	57.5%	80.3%
SqueezeNet (ours)	Deep Compression	6 bit	4.8MB → 0.47MB	510x	57.5%	80.3%


The squeeze-net can accomplish an accuracy nearly equal to AlexNet with 50X less number of parameters. The most impressive part is that if we apply Deep compression to the already smaller model then it can reduce the size of the squeeze-net model to 500x times that of AlexNet.

Q3.ZFNet architecture

Answer:



The architecture of the network is an optimized version of the last year's winner - AlexNet. The authors spent some time to find out the bottlenecks of AlexNet and removing them achieving superior performance.



a : First layer ZFNET features without feature scale clipping b : the First layer features from AlexNet. Note that there are lot of dead features - ones where the network did not learn any patterns c : the First layer features for ZFNet. Note that there are only a few dead features d : Second layer features from AlexNet. The grid-like patterns are so-called aliasing artifacts. They appear when

receptive fields of convolutional neurons overlap and neighboring neurons learn similar structures e : 2nd layer features for ZFNet Note that there are no aliasing artifacts Source: original paper

In particular they reduced the filter size in the st convolutional layer from 5×5 to 7×7 which resulted in fewer dead features learned in the first layer see the image below for an example of that A dead feature is a situation where a convolutional kernel fails to learn any significant representation Visually it looks like a monotonic single-color image where all the values are close to each other

In addition to changing the filter size the authors of FZNet have doubled the number of filters in all convolutional layers and the number of neurons in the fully connected layers as compared to the AlexNet In the AlexNet there were 48- 28- 92- 92- 28-2048-2048 kernels/neurons and in the ZFNet all these doubled to 96-256-384-384-256-4096-4096 This modification allowed the network to increase the complexity of internal representations and as a result decrease the error rate from 5.4% for last year s winner to 4.8%to become the winner in 2013

Q4. What is NAS (Neural Architecture Search)?

Answer:

Developing the neural network models often requires significant architecture engineering We can sometimes get by with transfer learning but if we want the best possible performance it s usually best to design your network This requires specialized skills and is challenging in general; we may not even know the limits of the current state-of-the-art SOTA techniques Its a lot of trial and error and experimentation itself is time-consuming and expensive

This is the NAS Neural Architecture Search comes in NAS Neural Architecture Search is an algorithm that searches for the best neural network architecture Most of the algorithms work in the following way Start off by defining the set of building blocks that can be used for our network E g the state-of-the-art SOTA NASNet paper proposes these commonly used blocks for an image recognition network-

- | | |
|---|---|
| <ul style="list-style-type: none">• identity• 1×7 then 7×1 convolution• 3×3 average pooling• 5×5 max pooling• 1×1 convolution• 3×3 depthwise-separable conv• 7×7 depthwise-separable conv | <ul style="list-style-type: none">• 1×3 then 3×1 convolution• 3×3 dilated convolution• 3×3 max pooling• 7×7 max pooling• 3×3 convolution• 5×5 depthwise-separable conv |
|---|---|

In the NAS algorithm the controller Recurrent Neural Network RNN samples the building blocks putting them together to create some end to end architecture. Architecture generally combines the same style as state-of-the-art SOTA networks such as DenseNets or ResNets but uses a much different combination and the configuration of blocks.

This new network architecture is then trained to convergence to obtain the least accuracy on the held-out validation set. The resulting efficiencies are used to update the controller so that the controller will generate better architectures over time perhaps by selecting better blocks or making better connections. The controller weights are updated with a policy gradient. The whole end-to-end setup is shown below.





Figure 1. Overview of Neural Architecture Search [71]. A controller RNN predicts architecture A from a search space with probability p . A child network with architecture A is trained to convergence achieving accuracy R . Scale the gradients of p by R to update the RNN controller.

It's a reasonably intuitive approach! In simple means: have an algorithm grab different blocks and put those blocks together to make the network. Train and test out that network. Based on our results adjust the blocks we used to make the network and how you put them together!

Q5. What is SENets?

Answer:



SENet stands for Squeeze-and-Excitation Networks introduces a building block for CNNs that improves channel interdependencies at almost no computational cost. They have used in the 2017 ImageNet competition and helped to improve the result from last year by 25%. Besides this large performance boost they can be easily added to existing architectures. The idea is this:

Let's add parameters to each channel of the convolutional block so that the network can adaptively adjust the weighting of each feature map

As simple as it may sound this is it So let's take a closer look at why this works so well

Why it works too well?

CNN's uses its convolutional filters to extract hierachal information from the images Lower layers find little pieces of context like high frequencies or edges while upper layers can detect faces text or other complex geometrical shapes They extract whatever is necessary to solve the task precisely


All of this works by fusing spatial and channel information of an image The different filters will first find the spatial features in each input channel before adding the information across all available output channels

All we need to understand for now is that the network weights each of its channels equally when creating output feature maps It is all about changing this by adding a content-aware mechanism to weight each channel adaptively In its too basic form this could mean adding a single parameter to each channel and giving it linear scalar how relevant each one is

However the authors push it a little further First they get the global understanding of each channel by squeezing feature maps to a single numeric value This results in the vector of size n where n is equal to the number of convolutional channels Afterward it is fed through a two-layer neural network which outputs a vector of the same size These n values can now be used as weights on the original features maps scaling each channel based on its importance

Q6. Feature Pyramid Network (FPN)

Answer:



The Bottom-Up Pathway

The bottom-up pathway is feedforward computation of backbone ConvNet. It is known as one pyramid level is for each stage. The output of last layer of each step will be used as the reference set of feature maps for enriching the top-down pathway by lateral connection.

Top-Down Pathway and Lateral Connection

- The higher resolution features are upsampled spatially coarser but semantically stronger feature maps from higher pyramid levels. More particularly the spatial resolution is upsampled by a factor of 2 using nearest neighbor for simplicity.
- Each lateral connection adds feature maps of the same spatial size from the bottom-up pathway and top-down pathway.
- Specifically **the feature maps from the bottom-up pathway undergo 1x1 convolutions to reduce channel dimensions.**
- And **feature maps from the bottom-up pathway and top-down pathway are merged by element-wise addition.**


Prediction in FPN

- Finally **the 3x3 convolution is appended on each merged map to generate a final feature map, which is to reduce the aliasing effect of upsampling.** This last set of feature maps is called $\{P_2 \ P_3 \ P_4 \ P_5\}$ corresponding to $\{C_2 \ C_3 \ C_4 \ C_5\}$ that are respectively of same spatial sizes.
- Because all levels of pyramid use shared classifiers/regressors as in a traditional featured image pyramid feature dimension at output d is fixed with $d = 256$. Thus all extra convolutional layers have 256 channel outputs.

Q7. DeepID-Net(Def-Pooling Layer)


Answer:

A new def-pooling deformable constrained pooling layer is used to model the deformation of the object parts with geometric constraints and penalties. That means except detecting the whole object directly it is also important to identify object parts which can then assist in detecting the whole object.



The steps in **black** color are the **old stuff** that existed in R-CNN. The stages in **red** color do not appear in R-CNN.

Selective Search



- First color similarities, texture similarities, regions size and region filling are used as **non-object-based segmentation**. Therefore you obtain **many small segmented areas** as shown at the bottom left of the image above.
- Then the bottom-up approach is used that **small segmented areas are merged to form the larger segment areas**.
- Thus **about 2K regions, proposals (bounding box candidates)** are generated, as shown in the above image.

2. Box Rejection

R-CNN is used to reject bounding boxes that are most likely to be the background


3. Pre train Using Object-Level Annotations


	Pretrained on object-level annoation	Pretrained on image-level annotation
Image		
Visualized model		

Usually pretraining is on **image-level annotation**. It is **not good** when an object is too small within the **image** because the object should occupy a large area within the bounding box created by the selective search.

Thus **pretraining is on object-level annotation**. And the deep learning(DL) model can be any **models** such as ZFNet VGGNet and GoogLeNet.

4. Def-Pooling Layer





$$b_c^{(x,y)} = \max_{\delta_x, \delta_y \in \{-R, \dots, R\}} \{ m_c^{\mathbf{z}_{\delta_x, \delta_y}} - \sum_{n=1}^N a_{c,n} d_{c,n}^{\delta_x, \delta_y} \}$$

where $\mathbf{z}_{\delta_x, \delta_y} = (s_x \cdot x + \delta_x, s_y \cdot y + \delta_y)$.

For the def-pooling path output from conv5 goes through the Conv layer then goes through the def-pooling layer and then has a max-pooling layer

In simple terms the summation of ac multiplied by dc n is the 5×5 deformation penalty in the figure above. The penalty of placing object part from assumed the central position

By training the DeepID-Net object parts of the object to be detected will give a high activation value after the def-pooling layer if they are closed to their anchor places. And this output will connect to 200-class scores for improvement

5. Context Modeling

In object detection tasks in ILSVRC there are 200 classes. And there is also the classification competition task in ILSVRC for classifying and localizing 1000-class objects. The contents are more diverse compared with the object detection task. Hence **1000-class scores, obtained by classification network, are used to refine 200-class scores.**

6. The Model Averaging-

Multiple models are used to increase the accuracy and **the results from all models are averaged**. This technique has been used since AlexNet, LeNet and so on

7. Bounding Box Regression


Bounding box regression is to **fine-tune the bounding box location** which has been used in R-CNN

Q8. What is FractalNet Architecture?

Answer:

In 2015 after the invention of ResNet with numerous champion won there are plenty of researchers working on how to improve the ResNet such as Pre-Activation ResNet, RiR, RoR, Stochastic Depth and WRN. In this story conversely a non-residual-network approach FractalNet is shortly reviewed. When VGGNet is starting to degrade when it goes from 6 layers VGG-6 to 9 layers VGG-9 FractalNet can go up to 40 layers or even 80 layers.

Architecture



In the above picture: A Simple Fractal Expansion on Left Recursively Stacking of Fractal Expansion as One Block in the Middle 5 Blocks Cascaded as FractalNet on the Right

For the base case $f_C(z)$ is the convolutional layer:

$$f_1(z) = \text{conv}(z)$$

After that recursive fractals are:

$$f_{C+1}(z) = [(f_C \circ f_C)(z)] \oplus [\text{conv}(z)]$$

Where C is a number of columns as in the middle of the above figure. The number of the convolutional layers at the deepest path within the block will have $2^B C$. In this case $C=4$ thereby a number of convolutional layers are $2^3=8$ layers.

For the **join layer** green the **element-wise mean** is computed. It is not concatenation or addition.


With five blocks $B=5$ cascaded as FractalNet at the right of the figure then the number of convolutional layers at the most profound path within the whole network is $B \times 2^B C$ i.e. $5 \times 2^3 = 40$ layers.

In between 2 blocks 2×2 max pooling is done to reduce the size of feature maps. Batch Norm and ReLU are used after each convolution.

Q9. What is the SSPNet architecture?

Answer:

SPPNet has introduced the new technique in CNN called **Spatial Pyramid Pooling (SPP)** at the transition of the convolutional layer and fully connected layer. This is a work from **Microsoft**.



Conventionally at the transformation of the Conv layer and FC layer there is one single pooling layer or even no pooling layer. In SPPNet it suggests having **multiple pooling layers with different scales**.

In the figure **3-level SPP** is used. Suppose conv5 layer has 256 feature maps. Then at the SPP layer

-
- first each feature map is **pooled to become one value (which is grey)** Thus **256-d vector is formed**
- 2 Then each feature map is **pooled to have four values (which is green)** and form the **4×256-d vector**
 - 3 Similarly each feature map is **pooled to have 16 values (in blue)** and form the **16×256-d vector**
 - 4 **The above three vectors are concatenated to form a 1-d vector**
 - 5 Finally this **1-d vector is going into FC layers** as usual

With SPP you don't need to crop the image to a fixed size like AlexNet before going into CNN **Any image sizes can be inputted.**

DATA SCIENCE
INTERVIEW
PREPARATION
(30 Days of Interview Preparation)

Day22